

LOCATION	PREFORMED PAVEMENT MARKING	THERMOPLASTIC PAVEMENT MARKING							AERIAL SPEED CHECK MARKING	SHORT TERM PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS			WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	PAVEMENT MARKING REMOVAL
		SKIP-DASH WHITE 4"	SKIP-DASH YELLOW 4"	SOLID WHITE 4"	SOLID YELLOW 4"	SOLID WHITE 6"	SOLID WHITE 8"	SOLID WHITE 12"				SOLID WHITE 24"	ONE WAY CRYSTAL	ONE WAY AMBER			
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH			
MARKET RAMPS																	
RAMP A LT																	
307+46.00 TO 316+82.00				936						74	6		6		12		
316+82.00 TO 317+38.00				91						6					1		
RAMP A RT																	
307+46.00 TO 316+89.00			943							74					13		
316+89.00 TO 317+72.00			133							6					1		
317+26.00 TO 317+57.00					116		57	36									
RAMP B LT																	
320+54.00 TO 321+70.00				141						10					2		
321+70.00 TO 331+70.50				1001						78					13		
RAMP B RT																	
320+00.00 TO 321+31.00			149							10					2		
321+31.00 TO 331+70.50			1040							86					14		
RAMP C LT																	
3+01.00 TO 6+62.40							361			32	9	9			5		
366+62.40 TO 366+64.00							2			72					13		
366+64.00 TO 367+14.00				50							2		2				
367+14.00 TO 375+27.00				813							9		9				
375+27.00 TO 376+08.00				105													
RAMP C RT																	
0+45.00 TO 6+62.40			617							48	31	31			8		
366+62.40 TO 374+88.00			826							72					13		
374+88.00 TO 376+00.00			201														
375+67.00 TO 376+09.00					185		118	36									
RAMP D LT																	
380+31.00 TO 380+93.00				87													
380+93.00 TO 388+41.00				748						69					11		
388+41.00 TO 388+91.00				50						1							
388+91.00 TO 390+22.97							132			10	7	7			2		
0+00.00 TO 1+49.00							149			8					1		
RAMP D RT																	
380+00.00 TO 381+01.00			121														
381+01.00 TO 390+22.97			922							80					13		
0+00.00 TO 8+63.00			863							72					12		
SUB-TOTAL	0	0	5815	4022	301	644	175	72	0	808	64	47	17	0	137	0	
MARKET STREET																	
136+85.00 TO 142+15.76		130								104	7						
144+40.68 TO 149+62.00		130								104	7				7		
LT 136+85.00 TO 137+46.00			61														
RT 136+85.00 TO 137+51.00			66														
LT 139+00.00 TO 142+15.76			316														
RT 139+20.00 TO 142+15.76			296														
LT 144+40.68 TO 147+61.00			320														
RT 144+40.68 TO 147+61.00			320														
LT 148+78.20 TO 149+62.00			84														
RT 149+52.23 TO 149+62.00			10														
SUB-TOTAL	0	260	1473	0	0	0	0	0	0	208	14	0	0	14	0	0	0
TOTAL	7160	260	37805	35868	662	2401	391	144	108	8908	900	842	44	14	10116	28629	8518
GRAND TOTAL	7160		73933		662	2401	391	144	108	8908	900		900		10116	28629	8518

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING SCHEDULE

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34, 10-35)RS-2(SB)	CHAMPAIGN	66	21
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70923	