

SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
						80% FEDERAL 20% STATE			100% LOCAL
						ROADWAY 0004 URBAN	BRIDGE 0011 URBAN	TRAINEES 0042 URBAN	
		42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	69	69			
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,121	1121			
		44000100	PAVEMENT REMOVAL	SQ YD	276	276			
		44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1,366	1366			
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	107	107			
		44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	55	55			
		44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	59	59			
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,231	1231			
		48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	235	235			
		48203009	HOT-MIX ASPHALT SHOULDERS, 3"	SQ YD	62	62			
		48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	66	66			
		50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
		50105220	PIPE CULVERT REMOVAL	FOOT	352	352			
		50200100	STRUCTURE EXCAVATION	CU YD	423		423		
		50300225	CONCRETE STRUCTURES	CU YD	316.5		316.5		
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	197.9		197.9		
		50300260	BRIDGE DECK GROOVING	SQ YD	1,095		1095		
		50300280	CONCRETE ENCASEMENT	CU YD	8.4		8.4		
		50300300	PROTECTIVE COAT	SQ YD	4,923	3411	1512		
		50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	9,010		9010		
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	86,420		86420		
		50800515	BAR SPLICERS	EACH	452		452		
	*	50901750	PARAPET RAILING	FOOT	326		326		
		51201600	FURNISHING STEEL PILES HP12X53	FOOT	748		748		
		51201800	FURNISHING STEEL PILES HP14X73	FOOT	1,232		1232		
		51202305	DRIVING PILES	FOOT	1,980		1980		
		51203600	TEST PILE STEEL HP12X53	EACH	2		2		
		51203800	TEST PILE STEEL HP14X73	EACH	2		2		
		51500100	NAME PLATES	EACH	1		1		
		54213459	END SECTIONS 24"	EACH	2	2			
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	148	148			
		550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	7	7			

FILE NAME = M:\Projects\2010\100954_Beston\pgh\locad\C:\v1\Ogn\Shr\S002.dgn

WBK WILLS BURKE KELSEY ASSOCIATES LTD.
118 West Main Street, Suite 201
St. Charles, Illinois 60174
(630) 443-7755

USER NAME = #USER#	DESIGNED - DPB	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 7/6/2011	CHECKED - SBP	REVISED -
	DATE - 7/8/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 5 OF 88 SHEETS STA. TO STA.

F.A.J. RTE. 5355	SECTION 04-00167-00-BR	COUNTY DEKALB	TOTAL SHEETS 88	SHEET NO. 5
CONTRACT NO. 87491				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				