

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	O/S (LT)	O/S (RT)	REMARKS
8	16+11.80	54.30		8"
8	16+45.00	57.30		8"
24	17+07.20	62.00		4x6"
30	17+19.20	58.00		5x6"
18	17+25.10	66.60		3x6"
12	18+25.80		43.3	12"
8	18+37.10	47.20		8"
8	18+73.70	64.4		8"
12	18+84.30	49.7		12"
12	21+69.80		46.6	12"
140	TOTAL			

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	O/S (LT)	O/S (RT)	REMARKS
18	15+90.60	53.60		18
18	TOTAL			

20800150 TRENCH BACKFILL

VOLUME (CU YD)	LOCATION	O/S	LENGTH (FT)	WIDTH (FT)	DEPTH (FT)	REMARKS	
30.0	15+00.00	15+50.00	LT	26.0	4.90	6.35	18" WM REQ.
5.2	16+00.00	16+00.00	LT	4.5	4.90	6.4	18" WM REQ.
57.7	16+00.00	16+00.00	LT/RT	53.0	4.90	6	18" RCP
16.0	16+00.00	16+00.00	RT	16.0	4.90	5.5	18" RCP
34.1	19+00.00	19+74.00	LT	74.0	2.83	4.4	12" RCP
5.4	19+74.00	19+74.00	LT	4.5	5.75	5.6	24" RCP
56.1	19+74.00	19+74.00	LT/RT	47.0	5.75	5.6	24" RCP
31.0	19+00.00	19+74.00	RT	74.0	2.83	4	12" RCP
19.4	19+74.00	19+74.00	RT	16.0	5.75	5.7	24" RCP
255.0	TOTAL						

42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

AREA (SQ YD)	LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)	REMARKS
34.5	17+10.20	17+16.20	6	51.8	HMA
34.4	18+79.87	18+85.87	6	51.6	
69	TOTAL				

50105220 PIPE CULVERT REMOVAL

FOOT	LOCATION	O/S	REMARKS
25.0	15+13.70	15+38.50	LT 12" CMP - DRIVEWAY
172.0	15+63.00	17+35.00	RT 15" CMP
155.0	18+45.00	20+00.00	RT 15" CMP
352.0	TOTAL		

54213459 END SECTIONS 24"

EACH	LOCATION	O/S	REMARKS
1.0	17+47.20	42.00	LT END SEC 1
1.0	18+19.90	42.00	LT END SEC 2
2.0	TOTAL		

550A0340 STORM SEWERS, CLASS A, TYPE 2 12"

FOOT	LOCATION	O/S	REMARKS
74.0	19+00.00	19+74.00	LT 12" RCP
74.0	19+00.00	19+74.00	RT 12" RCP
148.0	TOTAL		

550A0360 STORM SEWERS, CLASS A, TYPE 2 15"

FOOT	LOCATION	O/S	REMARKS
7.0	15+63.00	15+63.00	RT 15" RCP
7.0	TOTAL		

550A0380 STORM SEWERS, CLASS A, TYPE 2 18"

FOOT	LOCATION	O/S	REMARKS
53.0	16+00.00	16+00.00	LT/RT 18" RCP
16.0	16+00.00	16+00.00	RT 18" RCP
69.0	TOTAL		

FILE NAME = W:\Projects\2011\08054_Berthel\B-Accred\Civil\Draw\Sht\SCHEDULE1.dgn