

STRIPING, SIGNAGE AND MARKERS SCHEDULE

LOCATION	REMARKS	72000100	72000100	72800100	78200410	78200520	78201000	78001100	78001110	78001140	78001150	78001180	78300100
		SIGN PANEL - TYPE 1	REMOVE SIGN PANEL ASSEMBLY- TYPE A	TELESCOPING SIGN SUPPORT	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKER - DIRECT APPLIED	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 8"	PAINT PAVEMENT MARKING - LINE 12"	PAINT PAVEMENT MARKING - LINE 24"	PAVEMENT MARKING REMOVAL
		(SQ FT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
MAINLINE													
12+19.00 - 12+50.00	PERMANENT								124.0	89.0			
12+50.00 - 13+00.00									200.0	100.0			
13+00.00 - 13+50.00								31.2	193.0	93.0			9.3
13+50.00 - 14+00.00								46.8	190.0	49.0		29.0	70.7
14+00.00 - 14+50.00									278.0	13.0	6.0		70.7
14+50.00 - 15+00.00									300.0	13.0	19.0		70.7
15+00.00 - 15+50.00									311.0	3.0	11.0		70.7
15+50.00 - 16+00.00									400.0		30.0		70.7
16+00.00 - 16+50.00						2.0		2.0	400.0		35.0		70.7
16+50.00 - 17+00.00									400.0		28.0		70.7
17+00.00 - 17+50.00									400.0		24.0		
17+50.00 - 18+00.00									300.0		12.0		
18+00.00 - 18+50.00									300.0		24.0		66.0
18+50.00 - 19+00.00									300.0		12.0		66.0
19+00.00 - 19+50.00						2.0			300.0		24.0		66.0
19+50.00 - 20+00.00								2.0	300.0		12.0		66.0
20+00.00 - 20+50.00									234.0				66.0
20+50.00 - 21+00.00									200.0				66.0
21+00.00 - 21+50.00									200.0				4.7
21+50.00 - 22+00.00									200.0				
22+00.00 - 22+50.00									200.0				
22+50.00 - 23+00.00									200.0				
SIGNAGE													
14+62.70 27.1 LT	R3-8 MOD	7.5		17.0									
14+64.60 33.0 RT	R3-8 MOD	7.5		17.0									
15+00.00 27.0 RT	R4-9	5.0		17.0									
20+50.00 22.0 LT	R4-9	5.0		17.0									
SIGN REMOVAL													
17+10.00 17.1 LT	OM-3L		1.0										
18+56.00 17.1 RT	OM-3L		1.0										
18+56.00 17.1 LT	OM-3L		1.0										
TOTAL		25.0	3.0	68.0	4.0	6.0	4.0	78.0	5,930.0	360.0	237.0	29.0	905.0

FILE NAME = \\N:\Projects\2010\000054_Berthouge\Road\G:\1\Drawings\Sched\SCHEDULE7.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = #USER#	DESIGNED - DPB	REVISED -
DRAWN - NDP	REVISED -	
PLOT SCALE =	CHECKED - SBP	REVISED -
PLOT DATE = 7/6/2011	DATE - 7/8/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 15 OF 88 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	04-00167-00-BR	DEKALB	88	15
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 87491				