

PAVEMENT REMOVAL SCHEDULE

LOCATION	OFF.	REMARKS	40600982	40600990	44000100	44000158	44000200	44201777	44201781	X4430200
			HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"	DRIVEWAY PAVEMENT REMOVAL	CLASS D PATCHES, TYPE II, 11 INCH	CLASS D PATCHES, TYPE III, 11 INCH	REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL
			(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)
MAINLINE										
13+19.00 - 14+00.00	LT/RT		25.1	37.6		888.0				100.0
13+50.00 - 14+00.00						75.8				80.0
14+00.00 - 14+50.00						95.7				
14+50.00 - 15+00.00						43.0				
15+00.00 - 15+26.00										66.0
15+26.00 - 15+50.00					1.1					58.0
15+50.00 - 16+00.00					11.1					56.0
16+00.00 - 16+50.00					11.2					54.0
16+50.00 - 16+87.20					8.3					
16+87.20 - 17+00.00					38.8					
17+00.00 - 17+16.20			17.0	25.5	52.7					
BRIDGE										
18+49.87 - 18+79.87			17.0	25.5	27.2					
18+79.87 - 19+00.00					92.3					
19+00.00 - 19+50.00					4.5					44.0
19+50.00 - 20+00.00					11.3					44.0
20+00.00 - 20+50.00					11.2					
20+50.00 - 21+00.00					5.5					
21+00.00 - 21+50.00						48.5				44.0
21+50.00 - 21+80.00			12.2	18.2		133.1				
21+80.00 - 21+80.00						81.2				
PATCHES										
13+50.00 - 14+00.00	LT/RT								22.3	
14+00.00 - 14+50.00									17.9	
15+00.00 - 15+26.00								14.6		
15+26.00 - 15+50.00								12.9		
16+00.00 - 16+50.00		STORM SEWER						12.1	18.7	
19+50.00 - 20+00.00		STORM SEWER						14.7		
DRIVEWAYS										
14+50.00 - 15+00.00							11.6			
15+00.00 - 15+26.00	LT	HMA					50.8			
15+26.00 - 15+50.00							44.2			
TOTAL			72.0	107.0	276.0	1366.0	107.0	55.0	59.0	546.0

FILE NAME = M:\Projects\2010\080854_Bethel\g\roads\Civil\Drawings\Schedule.dgn

WBK WILLS BURKE KELSEY ASSOCIATES LTD.
 115 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = #USER#	DESIGNED - DPB	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 7/6/2011	CHECKED - SBP	REVISED -
	DATE - 7/8/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 18 OF 88 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	04-00167-00-BR	DEKALB	88	18
CONTRACT NO. 87491				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				