

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	STU FUNDS	STE FUNDS
20200100	EARTH EXCAVATION	CU YD	1,915	1,915	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	30	30	
* 25100115	MULCH, METHOD 2	ACRE	0.1	0.1	
* 25200100	SODDING	SQ YD	279		279
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	27	27	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	3,239	3,239	
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	15	15	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,672	1,672	
40600300	AGGREGATE (PRIME COAT)	TON	11	11	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,070	1,070	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	486	486	
S 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	312	312	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	15	15	
S 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5,978	5,978	
S 42400800	DETECTABLE WARNINGS	SQ FT	178	178	
44000100	PAVEMENT REMOVAL	SQ YD	1,686	1,686	
S 44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,607	1,607	
44000300	CURB REMOVAL	FOOT	122	122	
44000600	SIDEWALK REMOVAL	SQ FT	4,524	4,524	
S 44200919	CLASS B PATCHES, TYPE II, 7 INCH	SQ YD	85	85	
S 60600605	CONCRETE CURB, TYPE B	FOOT	246	246	
S 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,022	1,022	
67100100	MOBILIZATION	L SUM	1	1	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	STU FUNDS	STE FUNDS
S 70300100	SHORT TERM PAVEMENT MARKING	FOOT	165	165	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4,016	4,016	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	495	495	
72000100	SIGN PANEL - TYPE 1	SQ FT	68	68	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,683	2,683	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	336	336	
* 78006150	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	286	286	
* 81017525	CONDUIT IN TRENCH, 2" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	838	838	
* 81017535	CONDUIT IN TRENCH, 3" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	401	401	
S * 81028060	CONDUIT, BORED AND PULLED, COILABLE NON- METALLIC CONDUIT, 2"	FOOT	56	56	
S * 81028080	CONDUIT, BORED AND PULLED, COILABLE NON- METALLIC CONDUIT, 3"	FOOT	132	132	
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6		6
S LR430030	CONCRETE PAVER PAVEMENT	SQ YD	123	123	
S Z0012450	CONCRETE STEPS	CU YD	0.3	0.3	
S * Z0036200	PAINT CURB	FOOT	420	420	
S X0327008	REMOVE AND RELOCATE SIGN (SPECIAL)	EACH	2	2	
S X4240420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	1,593	1,593	
S X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
S * XX002918	TREE FRAME AND GRATES	EACH	8		8
S XX006213	METAL POST, SPECIAL	EACH	9		9
* A2005140	TREE, KOELREUTERIA PANICULATA (GOLDEN RAINTREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	6		6
S	SPECIAL PROVISION				
*	SPECIALITY ITEMS				