

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		• (1818, ETC, 2324.6-1)PR-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE					
				ROADWAY	SIGNING	SURVEILLANCE	SN 016-2625	SN 016-0142 SN 016-1148	
				J000-2A	Y002-1C	Y032-1F	X928-2A	SFTY-2A	
20200100	EARTH EXCAVATION	CU YD	172,538	172,538					
20800150	TRENCH BACKFILL	CU YD	30,946	30,946	▲				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	218,645	218,645					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,139	2,139					
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	3,208	3,208					
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	3,208	3,208					
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	540	540					
25000210	SEEDING, CLASS 2A	ACRE	1	1					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	99	99					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	99	99					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	99	99					
25100115	MULCH, METHOD 2	ACRE	1	1					
25100630	EROSION CONTROL BLANKET	SQ YD	5,347	5,347					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	110	110					
28000400	PERIMETER EROSION BARRIER	FOOT	1,744	1,744					
28000510	INLET FILTERS	EACH	209	209					
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	90,155	90,155	▲				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	456				456		
42001300	PROTECTIVE COAT	SQ YD	229,991	229,991	▲				
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE 14" PAVEMENT	SQ YD	148,588	148,588	▲				
42101448	LUG SYSTEM COMPLETE 48'	EACH	2	2					
42101452	LUG SYSTEM COMPLETE 52'	EACH	1	1					
44000013	BITUMINOUS SURFACE REMOVAL, 5"	SQ YD	143				143		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	82				82		
44000100	PAVEMENT REMOVAL	SQ YD	151,628	151,628	▲				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,832	8,832					
44000700	APPROACH SLAB REMOVAL	SQ YD	219				219		
44001980	CONCRETE BARRIER REMOVAL	FOOT	21,284	21,284	▲				
44004250	PAVED SHOULDER REMOVAL	SQ YD	63,526	63,526	▲				
44201474	CLASS C PATCHES, TYPE I	SQ YD	25	25					
44201476	CLASS C PATCHES, TYPE II	SQ YD	60	60					
44201478	CLASS C PATCHES, TYPE III	SQ YD	50	50					
44213200	SAW CUTS	FOOT	100	100					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	36	36					
50300225	CONCRETE STRUCTURES	CU YD	57	57					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,157	1,157	▲		112		

• SPECIALITY ITEM



Rev. 8-29-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 NB EXPRESS LANE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 7/7/05

DRAWN BY: TAI
 CHECKED BY: PJM

S00-1

06/29/2005 12:43:51 PM