

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62300		• (1818, ETC, 2324.6-1)PR-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE				
				ROADWAY J000-2A	SIGNING Y002-1C	SURVEILLANCE Y032-1F	SN 016-2625 X928-2A	SN 016-0142 SN 016-1148 SFTY-2A
Z0018800	DRAINAGE SYSTEM	L SUM	1	1				
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	15,387	15,387				
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	39,302	39,302				
* X5120905	FURNISHING SOLDIER PILES W 12X72	FOOT	3,040	3,040				
* X5120906	FURNISHING SOLDIER PILES W 12X106	FOOT	4,980	4,980				
* X5120907	FURNISHING SOLDIER PILES W 12X120	FOOT	4,170	4,170				
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	5,818	5,818				
50200100	STRUCTURE EXCAVATION	CU YD	835	835				
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1				
60248640	JUNCTIONCHAMBER NO. 11	EACH	1	1				
60248650	JUNCTIONCHAMBER NO. 12	EACH	1	1				
60248660	JUNCTIONCHAMBER NO. 13	EACH	1	1				
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	6			6		
XX005489	STEEL CASINGS 48"	FOOT	600	600				
Z0026420	STEEL CASINGS 60"	FOOT	71	71				
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	133,172	133,172				
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	44,744	44,744				
50102400	CONCRETE REMOVAL	CU YD	8	8				

* SPECIALITY ITEM

Edwards AND Kelcey
 ONE NORTH FRANKLIN
 CHICAGO, IL 60606
 PHONE: (312) 251-3000
 FAX: (312) 251-3015
 WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 NB EXPRESS LANE RECONSTRUCTION
 SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 7/7/05

DRAWN BY: TAI
 CHECKED BY: PJM

Rev. 0-29-05

S00-7

06/28/2005 12:44:36 PM