

SCHEDULE OF STORM SEWERS

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	147
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		1818, ETC, 2324.6-1PIR-8		

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 1, 12	SS CL A 1, 15	SS CL A 1, 18	SS CL A 1, 21	SS CL A 1, 24	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS CL A 2, 21	SS CL A 2, 24	SS CL A 2, 27	SS CL A 2, 30	SS CL A 2, 33	SS CL A 2, 36	SS CL A 2, 42	SS CL A 2, 48	SS CL A 3, 12	SS CL A 3, 21	SS CL A 3, 24	SS CL A 3, 27	SS CL A 3, 30	SS CL A 3, 36	SS CL A 3, 42	SS CL B 1, 12	SS CL B 1, 15	TRENCH BACKFILL (CU. YD.)
35-07	35-11	7.5	12	1.00%						7.5																			1.9	
35-14	35-11	9.5	12	1.00%						9.5																			0.7	
EX CB	35-07	1.0	12	1.00%						1.0																				
EX CB	35-05	1.7	15	1.00%																								1.7		
35-16	35-17	0.8	12	1.00%						0.8																				
35-18	JC35-01	5.6	12	1.00%						5.6																			1.3	
EX CB	35-15	1.8	12	1.00%																							1.8			
36-05	DMH36-01	49.6	21	0.21%																			49.6						72.6	
36-06	36-05	153.0	21	0.44%									153.0																150.4	
36-03	36-05	13.0	18	0.25%								13.0																	9.7	
36-02	36-03	1.3	12	1.00%						1.3																				
36-04	36-03	55.0	12	1.00%						55.0																			6.5	
EX CB	36-01	2.1	12	1.00%																							2.1		0.2	
EX MH	36-01	13.2	12	1.00%																							13.2		4.5	
EX P	36-06	12.2	12	1.00%						12.2																			6.9	
37-05	JC37-01	49.4	36	0.10%														49.4											74.4	
37-08	37-05	143.2	24	0.17%										143.2															146.0	
37-15	37-08	25.0	21	0.21%									25.0															18.9		
37-22	37-15	145.5	21	0.44%									145.5																47.5	
37-07	37-08	0.8	12	1.00%						0.8																				
37-09	37-08	54.5	12	1.00%						54.5																			6.3	
EX CB	37-06	2.3	12	1.00%																							2.3		0.1	
37-14	37-11	11.0	15	1.00%									11.0																6.2	
37-13	37-14	3.2	15	1.00%									3.2																0.3	
37-16	37-12	11.0	15	1.00%									11.0																1.0	
37-11	37-15	0.8	15	1.00%									0.8																	
37-18	37-14	11.0	15	1.00%									11.0																3.7	
37-17	37-18	1.9	15	1.00%									1.9																0.1	
EX CB	37-17	1.7	15	1.00%																								1.7		
37-12	37-15	54.5	15	1.00%									54.5																9.1	
37-19	37-16	11.0	12	1.00%						11.0																			0.8	
37-21	37-22	1.3	12	1.00%						1.3																				
37-23	37-22	55.0	12	1.00%						55.0																			6.4	
EX P	37-20	2.0	12	2.10%																							2.0			
EX CB	37-20	6.5	12	1.00%																							6.5		0.3	
37-03	37-05	26.8	30	0.15%												26.8													19.7	
36-11	37-03	205.1	30	0.21%												205.1													241.3	
36-07	36-11	135.4	21	0.44%										135.4															113.0	
36-08	36-07	8.1	15	1.00%								8.1																	5.1	
EX P	36-08	1.2	15	0.32%																								1.2		
36-10	36-11	0.8	12	1.00%						0.8																				
36-12	36-11	64.1	12	1.00%						64.1																			9.9	
36-09	36-10	2.8	12	1.00%						2.8																			1.1	
EX CB	36-09	2.8	12	1.00%																							2.8		0.4	
37-02	37-03	0.8	12	1.00%						0.8																				

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
DRAINAGE SCHEDULES
PROPOSED STORM SEWER PIPES
SCALE: 1"=N.T.S. DRAWN BY: JAM
DATE: 07/07/05 CHECKED BY: DDM

DS-32

#1660/04/01/11/14/15/16/17/18/19/20/21/22/23/24/25/26/27/28/29/30/31/32/33/34/35/36/37/38/39/40/41/42/43/44/45/46/47/48/49/50/51/52/53/54/55/56/57/58/59/60/61/62/63/64/65/66/67/68/69/70/71/72/73/74/75/76/77/78/79/80/81/82/83/84/85/86/87/88/89/90/91/92/93/94/95/96/97/98/99/100