PROFILE	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	GRADES CHECKED		
NO.	BM NOTED		
	STRUCTURE NOTATIONS CHKD		

Edwards AND Kelcey
ONE NORTH FRANKLIN
SUITE 1900
CHICAGO, ILLINOIS 60606
PHONE (312) 251-3000
FAX (312) 251-3015
WEB: WWW.EKCORP.COM

2435+00.00
℄ NB EXPRESS

4434+98.10
℄ NB LOCAL

℄ CTA TRACK

4.0 % -0.13 2.0 % 1.5 % 1.5 % 2.0 % 4.0 % -0.22

1:3 1:3

2435+00.00

36"Ø

EARTH EXCAVATION	215
EMBANKMENT	0
UNSUITABLE MATERIAL	0

ALL END AREAS AREA IN SQUARE FEET

2434+00.00
℄ NB EXPRESS

℄ CTA TRACK

4.0 % -0.37 2.0 % 1.5 % 1.5 % 2.0 % 4.0 %

1:3 1:3

2434+00.00

36"Ø

EARTH EXCAVATION	202
EMBANKMENT	0
UNSUITABLE MATERIAL	0

ALL END AREAS AREA IN SQUARE FEET

2433+00.00
℄ NB EXPRESS

℄ CTA TRACK

4.0 % -0.87 2.0 % 1.5 % 1.5 % 2.0 % 4.0 %

1:3 1:3

TEMPORARY SOIL RETENTION 0.5 FEET

2433+00.00

36"Ø

EARTH EXCAVATION	194
EMBANKMENT	0
UNSUITABLE MATERIAL	0

ALL END AREAS AREA IN SQUARE FEET

2432+00.00
℄ NB EXPRESS

℄ CTA TRACK

4.00 % -0.37 2.0 % 1.5 % 1.5 % 2.0 % 4.0 %

1:3 1:3

2432+00.00

EARTH EXCAVATION	190
EMBANKMENT	0
UNSUITABLE MATERIAL	0

ALL END AREAS AREA IN SQUARE FEET

HORIZONTAL SCALE 10' 0 10' 20'

VERTICAL SCALE 5' 0 5' 10'

STA.

62300 • I.B.I.B. ETC. 23246-1PIR-8

F.A.I. RTE.	SECTION	COUNTY	SHEET NO.	SHEETS
94/90	0	COOK	556	473

STA. TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

pw300\19035\con 148\i5\cadd\A\xsec\446828_Final.ctm