F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	556	214
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

62300 * (1818, ETC, 2324.6-IP)R-8

EXISTING ℄ NB I-94/90 EXPRESS LANES PROFILE

PROPOSED ℄ NB I-94/90 EXPRESS LANES PROFILE

MATCH LINE STA. 2515+00

MATCH LINE STA. 2530+00

26-01 26-09 26-04 27-03 27-06 27-08 27-15 27-17 28-02 28-03 28-07 28-15

INV = 3.76

30"-12" CLA 1 @ 0.68%

INV = 3.19

INV = 2.94

INV = -1.19

INV = -0.9

193'-24" CLA 2 @ 0.45%

INV = -4.14

INV = -2.82

INV = -5.00

INV = -5.50

71'-30" CLA 2 @ 0.32%

INV = -5.73

INV = -5.83

INV = 8.48

INV = -11.85

129'-36" CLA 2 @ 0.2%

INV = -13.06

INV = -13.32

INV = -13.42

INV = -13.52

50'-36" CLA 2 @ 0.2%

20" GAS

INV = -14.15

96'-42" CLA 2 @ 0.15%

INV = -17.37

INV = -17.51

INV = -17.71

52'-42" CLA 2 @ 0.15%

24" CTA S.S., INV. ELEV.= -13.70

165'-15" CLA 1 @ 0.5%

INV = -12.51

INV = -17.99

INV = -17.79

INV = -11.68

INV = -11.58

10" CTA S.S., INV. ELEV.= -8.71

8'-1" X 9'-0" ARCH PIPE

8'-1" X 9'-0" ARCH PIPE

9.45' X 10.5' ARCH PIPE

INV. ELEV.= -43.2

INV. ELEV.= -43.7

INV. ELEV.= -44.3

2515+00	2516+00	2517+00	2518+00	2519+00	2520+00	2521+00	2522+00	2523+00	2524+00	2525+00	2526+00	2527+00	2528+00	2529+00
10.12 / 10.07	10.16 / 10.09	10.09 / 10.03	10.03 / 9.90	9.88 / 9.69	9.56 / 9.40	9.24 / 9.04	8.81 / 8.61	8.43 / 8.10	7.85 / 7.51	7.26 / 6.85	6.48 / 6.11	5.70 / 5.31	4.90 / 4.50	4.04 / 3.69	3.11 / 2.87	2.16 / 2.06	1.38 / 1.25	0.45 / 0.43	-0.37 / -0.38	-1.09 / -1.19	-1.69 / -2.00	-2.31 / -2.73	-2.83 / -3.30	-3.22 / -3.70	-3.54 / -3.93	-3.67 / -4.00	-3.67 / -3.91	-3.44 / -3.64	-3.19 / -3.22

DPR-6

REVISIONS	
NAME	DATE
ADDENDUM 2	9/16/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)

31ST STREET TO 71ST STREET

NB EXPRESS LANE RECONSTRUCTION

DRAINAGE PROFILES

NORTHBOUND STA. 2515+00 TO STA. 2530+00

SCALE: H 1"=50' 0' 50' 100' V 1"=5' 0' 5' 10'

DATE: 7/7/05

DRAWN BY: LPN

CHECKED BY: PJM

Edwards AND Kelcey
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

PLAN | SURVEYED | DATE | ALIGNMENT CHECKED | PLAN OF ALIGNMENT CHECKED | NOTE BOOK | NO. | BY | DATE

p:\03009\05\Sheets\Addendum 2\dpr6.dgn 09/15/2005 03:30:36 PM