

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
94/90		COOK	598	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62302	•(1818, ETC, 2324.6-1)PR-9			

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE							
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A	
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	486	486								
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	26	26								
552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	85	85								
552A1500	STORM SEWERS JACKED IN PLACE, CLASS A 42"	FOOT	259	259								
552A1600	STORM SEWERS JACKED IN PLACE, CLASS A 48"	FOOT	161	161								
X0320870	BRACED EXCAVATION	CU YD	5,499	5,499								
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	957	957								
X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	567	567								
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	222	222								
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	53,371	53,371								
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	54,685	54,685								
X0324112	BARRIER BASE	FOOT	29,867	29,867								
X0324431	TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE)	SQ FT	16,000		16,000							
X0324697	SOIL STABILIZERS	POUND	163,129	163,129								
X0324698	APPLY DUST SUPPRESSION AGENTS	UNIT	110	110								
X4210400	LUG SYSTEM REMOVAL	EACH	3	3								
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS - 14"	SQ YD	57,423	57,423								
* X5120905	FURNISHING SOLDIER PILES W 12X72	FOOT	2,520	2,520								
* X5120907	FURNISHING SOLDIER PILES W 12X120	FOOT	9,330	9,330								
* X5120952	FURNISHING SOLDIER PILES W 24X106	FOOT	4,800	4,800								
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAMES AND GRATES	EACH	53	53								
X6020167	DRAINAGE STRUCTURES, TYPE 2 SPECIAL WITH TWO TYPE 22 FRAMES AND GRATES	EACH	4	4								
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	674	674								
X6370910	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT	FOOT	2,672	2,672								
X6370925	CONCRETE BARRIER, SINGLE FACE, 42" (SPECIAL)	FOOT	21,918	21,918								
X6370930	CONCRETE BARRIER, DOUBLE FACE, 32" HEIGHT	FOOT	2,677	2,677								
X6370935	CONCRETE BARRIER, SINGLE FACE, 32" (MODIFIED)	FOOT	815	815								
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1								
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	270	270								
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	55	55								
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	15,824	15,824								
* X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	46			46						
* X8160380	UNIT DUCT, W 3-1/2 NO.2 AND 1/2 NO.4 GRND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	825						825			
XX001854	STABILIZED SUB-BASE 6"	SQ YD	215,074	215,074								

☐ - NON-PARTICIPATING  
\* - SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 31ST STREET TO 71ST STREET  
 SB EXPRESS LANE RECONSTRUCTION  
 SUMMARY OF QUANTITIES  
 SCHEDULE

SCALE: NTS  
 DATE: 01/07/05

DRAWN BY: RA  
 CHECKED BY: JDC

BOWMAN, BARRETT & ASSOCIATES INC.  
 CONSULTING ENGINEERS  
 Chicago, Illinois  
 312.228.0100  
 www.bbainc.com

S00-06

6/29/2005 5:56:48 PM