F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	160
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62302 * (1818, ETC, 2324.6-1P)R-9

SCHEDULE OF PIPE UNDERDRAINS

STATION	TO STATION	OFFSET	PIPE UNDERDRAINS 6" (FT)	CONNECTING STRUCTURE	PIPE UNDERDRAINS 6" SPECIAL (FT)
1367+00	1367+23	RT	23	1-01	8
1371+19	1367+23	RT	396	1-01	8
1375+02	1371+19	RT	383	1-05	8
1375+02	1378+01	RT	299	2-04	1
1378+01	1378+44	RT	43	2-06	1
1379+93	1378+44	RT	149	2-06	1
1383+06	1379+93	RT	313	3-02	0
1386+92	1383+06	RT	386	3-06	5
1388+00	1386+92	RT	108	4-02	6
1391+00	1393+56	LT	256	5-06	0
1396+69	1393+56	LT	313	5-06	0
1398+23	1396+69	LT	154	5-12	0
1401+29	1398+23	LT	306	6-04	0
1401+29	1403+18	LT	189	7-03	0
1406+00	1406+81	RT	81	7-09	3
1403+18	1405+06	LT	188	7-11	0
1405+06	1406+95	LT	189	7-07	0
1406+81	1409+66	RT	285	8-05	6
1406+95	1408+52	LT	157	8-03	0
1408+52	1410+29	LT	177	8-06	0
1409+66	1411+65	RT	199	8-17	1
1410+29	1411+65	LT	136	8-11	0
1415+01	1411+65	RT	336	8-17	1
1413+55	1411+65	LT	190	8-11	0
1418+94	1415+01	RT	393	9-03	6
1416+90	1413+55	LT	335	9-05	0
1418+94	1416+90	LT	204	9-06	0
1421+88	1418+94	RT	294	9-11	6
1420+75	1418+94	LT	181	9-10	0
1425+00	1421+88	RT	312	10-06	6
1423+10	1420+75	LT	235	10-02	0
1425+00	1423+10	LT	190	10-08	0
1426+09	1425+00	RT	109	10-14	6
1426+09	1425+00	LT	109	10-13	0
1426+09	1429+58	RT	349	11-07	3
1426+09	1428+87	LT	278	11-04	0
1429+58	1433+11	RT	353	11-09	6
1428+87	1430+99	LT	212	12-01	0
1430+99	1433+11	LT	212	12-05	0
1433+11	1434+91	RT	180	12-06	6
1433+11	1435+56	LT	245	12-08	0
1434+91	1437+12	RT	221	13-05	6
1435+56	1437+12	LT	156	13-01	0
1439+69	1437+12	RT	257	13-05	6
1438+46	1437+12	LT	134	13-01	0
1440+81	1438+46	LT	235	13-09	0
1443+32	1439+69	RT	363	13-12	6
1443+32	1440+81	LT	251	13-13	0
1443+32	1447+55	RT	423	14-07	6
1443+32	1445+39	LT	207	14-03	0
1445+39	1448+00	LT	261	14-08	0
1447+55	1450+47	RT	292	15-18	3
1448+00	1449+49	LT	149	15-20	0
1449+49	1450+34	LT	85	15-11	0
1453+32	1450+47	RT	285	15-18	3
1451+35	1450+34	LT	101	15-11	0
1453+32	1451+35	LT	197	15-28	0
1455+35	1453+32	RT	203	15-25	6
1454+64	1453+32	LT	132	15-24	0
311+92	310+59	LT	133	15-08	0
314+28	311+92	LT	236	15-20	0
316+47	314+28	LT	219	15-26	0
1455+35	1457+69	RT	234	16-03	6

STATION	TO STATION	OFFSET	PIPE UNDERDRAINS 6" (FT)	CONNECTING STRUCTURE	PIPE UNDERDRAINS 6" SPECIAL (FT)
316+47	318+64	LT	217	16-01	2
1457+69	1460+35	RT	266	17-18	1
318+64	320+60	LT	196	16-06	0
1459+71	1460+35	LT	64	17-02	0
1463+31	1460+35	RT	296	17-18	1
1463+31	1460+35	LT	296	17-02	0
1467+28	1463+31	RT	397	17-12	6
1465+13	1463+31	LT	182	17-11	0
1467+29	1465+13	LT	216	17-14	0
1467+28	1471+18	RT	390	18-06	6
1467+29	1469+30	LT	201	18-01	0
1469+30	1471+11	LT	181	18-04	0
1471+18	1473+75	RT	257	19-06	6
1471+11	1473+75	LT	264	19-10	0
1476+03	1473+75	RT	228	19-06	6
1474+58	1473+75	LT	83	19-10	0
1475+98	1474+58	LT	140	19-15	0
1477+81	1476+03	RT	178	19-17	5
1477+81	1475+98	LT	183	19-18	0
1481+55	1477+81	RT	374	19-20	3
1479+78	1477+81	LT	197	19-19	0
1481+55	1479+78	LT	177	20-03	0
1485+69	1481+55	RT	414	20-06	3
1483+55	1481+55	LT	200	20-05	0
1485+69	1483+55	LT	214	20-09	0
1488+19	1485+69	RT	250	21-03	3
1488+19	1485+69	LT	250	21-02	0
1488+19	1490+69	RT	250	22-02	3
1488+19	1490+69	LT	250	22-01	0
1490+69	1494+63	RT	394	22-10	3
1490+69	1492+66	LT	197	22-06	0
1492+66	1494+63	LT	197	22-09	0
1494+63	1498+57	RT	394	23-05	4
1494+63	1496+43	LT	180	23-01	0
1496+43	1498+73	LT	230	23-06	0
1498+57	1500+54	RT	197	23-10	4
1498+73	1500+75	LT	202	23-11	0
1500+54	1503+59	RT	305	24-10	4
1500+75	1502+61	LT	186	24-02	0
1502+61	1503+59	LT	98	24-06	0
1506+59	1503+59	RT	300	24-10	4
1506+59	1503+59	LT	300	24-17	0
1508+83	1506+59	RT	224	24-18	4
332+12	1506+59	LT	206	24-17	0
1510+96	1508+83	RT	213	25-03	4
333+55	332+12	LT	143	25-02	0
334+85	333+55	LT	130	25-05	0
1512+96	1510+96	RT	200	25-08	4
1515+16	1512+96	RT	220	25-12	4
336+93	336+20	RT	73	25-13	0
336+93	340+75	RT	382	26-06	2
1515+16	1517+46	RT	230	26-05	4
1517+46	1519+42	RT	196	26-10	4
340+75	342+59	RT	184	26-08	2
1519+42	1522+70	RT	328	27-08	2
342+59	344+76	RT	217	27-03	3
344+76	1522+66	LT	124	27-06	6
1522+70	1525+28	RT	258	27-12	2
1522+66	1525+28	LT	262	27-10	0
1525+28	1527+56	RT	228	28-02	2
1525+28	1527+53	LT	225	28-06	0
1530+00	1527+56	RT	244	28-02	2
1530+00	1527+53	LT	247	28-06	0
1413+55	1412+36	LT	119	8-18	0
1416+90	1413+55	LT	335	9-05	0
1418+94	1416+90	LT	204	9-06	0
1420+75	1418+94	LT	181	9-10	0
1422+00	1420+75	LT	125	10-02	0

DS-40

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION

DRAINAGE SCHEDULES
PROPOSED PIPE UNDERDRAINS

SCALE:
DATE: 7/7/05
DRAWN BY: MJO
CHECKED BY: LPN

Edwards AND Kelcey
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

p:\03009035\Com 14\ACADD\DS\DS002E.dgn
06/27/2005 06:53:36 PM