

SCHEDULE OF QUANTITIES

INDIVIDUAL TRUSS LOCATIONS

Location No.	5-01		
Structure No.	5 S 010 1057 R249.73		
County / Route	CHAMPAIGN CO. - I-57 NB - Off Ramp to US 136		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	138.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	222.50
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	64.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X7012617	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	EACH	1.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	34.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	5-02		
Structure No.	5 S 010 1057 L250.43		
County / Route	CHAMPAIGN CO. - I-57 SB - Off Ramp to US 136		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	138.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	222.50
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	64.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00
81400100	HANDHOLE	EACH	1.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X7012617	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	EACH	1.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	34.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Install HANDHOLE in ground around the backside of Lt. Fdn. to maintain electrical connection for highway lighting.

Location No.	5-03		
Structure No.	5 S 010 1057 L237.52		
County / Route	CHAMPAIGN CO. - I-57 SB - just North of I-74		
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
28000510	INLET FILTERS	EACH	2.00
63400105	GUARD POSTS	EACH	20.00
63400205	GUARD POSTS REMOVAL	EACH	20.00
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	538.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	481.50
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	90.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	25.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	54.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0002005	ATTENUATOR BASE	SQYD	102.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2.00
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.00

Pay Item for Changeable Message Signs is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-04		
Structure No.	5 S 010 1074 R185.40		
County / Route	CHAMPAIGN CO. - University Ave. / IL 130 at interchange to I-74 - East edge Urbana		
Scope of Work	This overhead sign structure is being replaced with a Tri-Chord on new foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	192.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	135.00
73306100	TRICHORD SIGN STRUCTURE TYPE - TRI-I-S	FOOT	53.00
73306500	TRICHORD SIGN WALKWAY TYPE - S	FOOT	40.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00

The Signage designating "END ILLINOIS 130" will be replaced by the District 5 Sign Shop