



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 20, 2010

SUBJECT: FAP Route 303 (IL 173)  
Section 134 (B & B-2) R-1  
Lake County  
Contract No. 62037  
Item No. 2, November 5, 2010 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Added page 183 to the Special Provisions.
4. Revised sheets 2 & 7 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; R. E. Anderson;  
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
C2001536	S-CORNUS RACEMOSA 3'	EACH	38.000				
C2009624	S-SAMBUCUS CANAD 2'	EACH	35.000				
C2011936	S-VIBURN DEN R S 3'	EACH	37.000				
K0013030	P PL WETLND 2X4 DPPLG	UNIT	6.840				
MX030199	TEMP PAVEMENT	SQ M	210.000				
MX033276	TEMP SOIL RETEN SYSTM	SQ M	70.000				
MX033460	WET TEM PM TAP T3 100	METER	1,956.000				
MX033694	STR REP CON DP =< 125	SQ M	23.000				
MX033782	WET TEM PM TAP T3 600	METER	16.000				
MX207400	POROUS GRAN EMB SPEC	CU M	305.000				
MZ001050	AGG SUBGRADE 300	SQ M	3,402.000				
MZ011100	P UNDR - STRUCT 100	METER	120.000				
MZ022800	FENCE REMOVAL	METER	80.000				
M2010110	TREE REMOV 6-15	UNIT	400.000				
M2010210	TREE REMOV OVER 15	UNIT	200.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M2010500	TREE REMOV HECTARES	HA	0.300				
M2011000	TEMPORARY FENCE	METER	126.000				
M2020010	EARTH EXCAVATION	CU M	1,430.000				
M2021200	REM & DISP UNS MATL	CU M	550.000				
M2040800	FURNISHED EXCAVATION	CU M	3,222.000				
M2113100	TOPSOIL F & P 100	SQ M	5,308.000				
M2500210	SEEDING CL 2A	HA	0.300				
M2500310	SEEDING CL 4	HA	0.400				
M2500400	NITROGEN FERT NUTR	KG	54.000				
M2500600	POTASSIUM FERT NUTR	KG	54.000				
M2510630	EROSION CONTR BLANKET	SQ M	5,308.000				
M2800250	TEMP EROS CONTR SEED	KG	2,101.000				
M2800305	TEMP DITCH CHECKS	METER	96.000				
M2800400	PERIMETER EROS BAR	METER	705.000				
M2810107	STONE RIPRAP CL A4	SQ M	1,005.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M2820200	FILTER FABRIC	SQ M	1,065.000				
M3550500	HMA BASE CSE 200	SQ M	595.000				
M4030100	BIT MATLS PR CT	LITER	6,260.000				
M4060300	AGG PR CT	M TON	44.000				
M4060895	CONSTRUC TEST STRIP	EACH	2.000				
M4060982	HMA SURF REM BUTT JT	SQ M	60.000				
M4061005	HMA REPL OVER PATCH	M TON	71.000				
M4062135	LEV BIND MM N70	M TON	10.000				
M4063085	HMA BC IL-19.0 N70	M TON	155.000				
M4063310	HMA SC "C" N50	M TON	75.000				
M4063595	P HMA SC "F" N90	M TON	24.000				
M4075320	HMA PAVT FD 320	SQ M	2,910.000				
M4080500	INCIDENTAL HMA SURF	M TON	30.000				
M4206200	BR APPR PVT CON (FLX)	SQ M	766.000				
M4400765	HMA SURF REM 65	SQ M	451.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M4401250	HMA RM OV PATCH 150	SQ M	195.000				
M4402000	PAVEMENT REM	SQ M	1,902.000				
M4402010	DRIVE PAVEMENT REM	SQ M	555.000				
M4402030	GUTTER REM	METER	10.000				
M4402040	COMB CURB GUTTER REM	METER	195.000				
M4402060	APPROACH SLAB REM	SQ M	444.000				
M4402530	PAVED SHLD REMOVAL	SQ M	1,363.000				
M4428010	CL D PATCH T1 150	SQ M	60.000				
M4428210	CL D PATCH T2 150	SQ M	60.000				
M4428310	CL D PATCH T3 150	SQ M	75.000				
M4430080	REF CR CONT TR SP 900	METER	48.000				
M5010240	CONC REM	CU M	14.000				
M5010570	PROTECTIVE SHIELD	SQ M	615.000				
M5020100	STRUCTURE EXCAVATION	CU M	1,175.000				
M5030280	CONCRETE ENCASEMENT	CU M	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5030350	CONC STRUCT	CU M	143.000				
M5030360	CONC SUP-STR	CU M	400.000				
M5030390	BR DECK GROOVING	SQ M	1,123.000				
M5030450	PROTECTIVE COAT	SQ M	1,319.000				
M5080205	REINF BARS, EPOXY CTD	KG	67,280.000				
M5120160	F STL PILE HP310X79	METER	380.000				
M5120335	DRIVING PILES	METER	380.000				
M5120460	TEST PIL ST HP310X79	EACH	3.000				
M5120900	TEMP SHT PILING	SQ M	25.000				
M5210022	ANCHOR BOLTS M24	EACH	60.000				
M542E012	END SECTIONS 300	EACH	3.000				
M5900200	EPOXY CRACK INJECTION	METER	42.000				
M5910100	GEOCOMPOSITE WALL DR	SQ M	145.000				
M6010125	PIPE DRAINS 300	METER	24.000				
M6060700	COMB CC&G TB15.60	METER	228.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M6300103	SPBGR TY A 2.74 POSTS	METER	384.000				
M6320030	GUARDRAIL REMOV	METER	402.000				
* M6690200	NON SPL WASTE DISPOSL	CU M	1,200.000				
M7030100	SHORT-TERM PAVT MKING	METER	2,412.000				
M7031000	WORK ZONE PAVT MK REM	SQ M	610.000				
M7040100	TEMP CONC BARRIER	METER	290.000				
M7040200	REL TEMP CONC BARRIER	METER	290.000				
M7800105	THPL PVT MK LINE 100	METER	1,888.000				
M7802010	POLYUREA PM T1 LN 100	METER	353.000				
M7830100	PAVT MARKING REMOVAL	SQ M	821.000				
X0325290	CORED DRAIN HOLES	EACH	1.000				
X0326276	TEMP LGHT SNGL LN STG	L SUM	1.000				
X2800510	INLET FILTER CLEANING	EACH	2.000				
X5020501	UNWAT STR EX PROT L1	EACH	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030275	IMP ATTN TEMP SUN TL2	EACH	4.000				
Z0030355	IMP ATTN REL S U TL2	EACH	4.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				
28000510	INLET FILTERS	EACH	2.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50101500	REM EXIST SUP-STR	EACH	1.000				
50500305	ERECT STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	3,798.000				
50800515	BAR SPLICERS	EACH	1,107.000				
51500100	NAME PLATES	EACH	2.000				
60900315	TY D INLET BOX 609006	EACH	3.000				
60900515	CONC THRUST BLOCKS	EACH	3.000				
63100085	TRAF BAR TERM T6	EACH	8.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	5.000				
63500105	DELINEATORS	EACH	10.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62037

State Job # - C-91-443-00  
 PPS NBR - 1-75701-0200  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 134(B&B-2)R-1

Project Number

Route  
 FAP 303

\* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
* 66900530	SOIL DISPOSAL ANALY	EACH	2.000				
67000400	ENGR FIELD OFFICE A	CAL MO	15.000				
67100100	MOBILIZATION	L SUM	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	270.000				
78100100	RAISED REFL PAVT MKR	EACH	84.000				
78100105	RAISED REF PVT MKR BR	EACH	14.000				
78200200	BIDIR PRIS BAR REFL	EACH	152.000				
78200410	GUARDRAIL MKR TYPE A	EACH	18.000				
78201000	TERMINAL MARKER - DA	EACH	5.000				
78300200	RAISED REF PVT MK REM	EACH	84.000				
89000100	TEMP TR SIG INSTALL	EACH	2.000				

IMPACT ATTENUATORS, TEMPORARY (BDE) .....	147
LIQUIDATED DAMAGES (BDE).....	149
MENTOR-PROTÉGÉ PROGRAM (BDE) .....	149
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) .....	150
NOTIFICATION OF REDUCED WIDTH (BDE) .....	151
ORGANIC ZINC-RICH PAINT SYSTEM (BDE).....	151
PAVEMENT MARKING REMOVAL (BDE).....	155
PAVEMENT PATCHING (BDE).....	155
PAYMENTS TO SUBCONTRACTORS (BDE) .....	155
PERSONAL PROTECTIVE EQUIPMENT (BDE) .....	156
POLYUREA PAVEMENT MARKING (BDE).....	156
PORTLAND CEMENT CONCRETE PLANTS (BDE) .....	163
RAISED REFLECTIVE PAVEMENT MARKERS (BDE).....	164
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) .....	164
REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE).....	165
SEEDING (BDE) .....	165
SELECTION OF LABOR (BDE).....	168
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	168
TEMPORARY EROSION CONTROL (BDE) .....	169
THERMOPLASTIC PAVEMENT MARKINGS (BDE) .....	170
TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE) .....	171
TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) .....	171
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID).....	172
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) .....	175
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) .....	179
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES .....	183

Revised 10/20/2010

## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

### REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. Implementation of this Special Provision will likely require the Contractor to subcontract for the execution of certain activities. It will be the Contractor's responsibility to assess the working conditions and adjust anticipated production rates accordingly.

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.

Any soil classified as a non-special waste shall be excavated and disposed of as directed by this project or the Engineer. Any excavation or disposal beyond what is required by this project or the Engineer will be at no additional cost to the Department. The information provided by the District and preliminary environmental site assessment (PESA) report, available through the District's Environmental Studies Unit. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

- A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below.
1. Station 26+240 to Station 26+255 0 to 20 meters (0 to 66 feet) RT (Webb's Marina, Site 2068-4, 25837 IL 173, Antioch) – non-special waste. Contaminants of concern sampling parameters: BETX and PAHs.
  2. All sediment at East Boat Cannel and IL 173 (East Boat Channel, Site 2068-5, 25800 Block of IL 173, Antioch) – non-special waste. Contaminants of concern sampling parameters: PCBs, PAHs, and Metals.
  3. All sediment at West Boat Cannel and IL 173 (West Boat Channel, Site 2067-3, 26300 Block of IL 173, Antioch) – non-special waste. Contaminants of concern sampling parameters: PCBs, PAHs, and Metals.