

SUMMARY OF QUANTITIES					Paxton Ave.	River Oaks Dr.	Traffic Signals
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	1000-1A	J000-1A	Y031-1F
					80% Fed, 20% City	80% Fed, 20% State	80% Fed, 20% City
	60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	2	2		
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2		2	
	60218400	MANHOLES, TYPE A, 4"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60221100	MANHOLES, TYPE A, 5"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
	60223800	MANHOLES, TYPE A, 6"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1		
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2		
	60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	2	1	
	60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	5	5		
	602501740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1		
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	2	2	
	60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2		
	60500050	REMOVING CATCH BASINS	EACH	3	2	1	
	60500205	FILLING CATCH BASINS	EACH	1	1		
	60600605	CONCRETE CURB, TYPE B	FOOT	195	195		
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1458	1458		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	714	434	280	
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	267		267	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
	67100100	MOBILIZATION	L SUM	1	0.72	0.28	
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.72	0.28	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1000	1000		
	70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	4277	4277		
	70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	311	311		
	70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	100	100		
*	72000100	SIGN PANEL - TYPE 1	SQ FT	15			15
*	72000200	SIGN PANEL - TYPE 2	SQ FT	36			36
*	78000100	THERMOPLASTIC PAVEMENT MARKING -LETTERS AND SYMBOLS	SQ FT	255	255		
*	78000200	THERMOPLASTIC PAVEMENT MARKING -LINE 4"	FOOT	2950	2950		
*	78000400	THERMOPLASTIC PAVEMENT MARKING -LINE 6"	FOOT	755	755		
*	78000600	THERMOPLASTIC PAVEMENT MARKING -LINE 12"	FOOT	152	152		
*	78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -LETTERS AND SYMBOLS	SQ FT	148		148	
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -LINE 4"	FOOT	192		192	
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -LINE 6"	FOOT	1128		1128	
*	78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -LINE 24"	FOOT	194		194	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	27		27	
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1
*	81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	200			200
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1053			1053
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	61			61
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	101			101
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	139			139
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	720			720
*	81400100	HANDHOLE	EACH	7			7
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4			4
*	81400300	DOUBLE HANDHOLE	EACH	1			1
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1416			1416

* - INDICATES SPECIALTY ITEMS

FILE NAME = 08328-quin-01 - 002	USER NAME =	DESIGNED -- RW	REVISED -- 02-04-10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US ROUTE 6 (RIVER OAKS DRIVE) AT PAXTON AVENUE INTERSECTION IMPROVEMENT SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED -- RW	REVISED --		351	06-00139-00-CH	COOK	044	004				
	PLOT SCALE =	DRAWN -- RG/PS	REVISED --		SCALE:		SHEET NO. 004 OF 044 SHEETS		STA.	TO STA.	CONTRACT NO. 63268		
	PLOT DATE = 01-25-10	CHECKED -- AG	REVISED --		FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT HD-M-9003(258)					