

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				0043
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	RDWY 0003	STRUCTURAL 0040	TRAFFIC SIGNALS 0021	LIGHTING 0021	100% LOCAL FUNDING	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,631	4,631					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	747	747					
42001200	PAVEMENT FABRIC	SQ YD	747	747					
42001300	PROTECTIVE COAT	SQ YD	747	747					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	222	222					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9,365	9,365					
44000100	PAVEMENT REMOVAL	SQ YD	152,389	152,389					
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	23,397	23,397					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,897	2,897					
44000300	CURB REMOVAL	FOOT	500	500					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,309	6,309					
44000600	SIDEWALK REMOVAL	SQ FT	7,583	7,583					
* X 440 2020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	1,030	1,030					
44003100	MEDIAN REMOVAL	SQ FT	5,669	5,669					
44004250	PAVED SHOULDER REMOVAL	SQ YD	13,132	13,132					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	100	100					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	146	146					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	56	56					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	9	9					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,123	2,123					
50200100	STRUCTURE EXCAVATION	CU YD	676		676				
50300225	CONCRETE STRUCTURES	CU YD	96		96				
50300285	FORM LINER TEXTURED SURFACE	SQ FT	582					582	
50300300	PROTECTIVE COAT	SQ YD	414		414				
50800105	REINFORCEMENT BARS	POUND	16,400		16,400				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	11,020		11,020				
# X 509 1725	BICYCLE RAILING, SPECIAL	FOOT	43		43				
51201400	FURNISHING STEEL PILES HP10X42	FOOT	160		160				
51202305	DRIVING PILES	FOOT	160		160				
51203400	TEST PILE STEEL HP10X42	EACH	2		2				
51500100	NAME PLATES	EACH	2		2				
54002020	EXPANSION BOLTS 3/4 INCH	EACH	33		33				
54003000	CONCRETE BOX CULVERTS	CU YD	106		106				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	19	19					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	7	7					
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	13	13					
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	4					
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1					
* 54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	13	13					
* 54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	4	4					
* 54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	4	4					

* DENOTES SPECIAL PROVISION
DENOTES SPECIALTY ITEM



USER NAME = Rdwy.Lisle
PLOT CONFIG = PDF(Grey, Large).plt
PLOT SCALE = 1:50
PLOT DATE = 7/28/2010

DESIGNED - MJP
DRAWN - TCK
CHECKED - JAH
DATE - 8/2/2010

REVISED -
REVISED -
REVISED -
REVISED -



MCHENRY COUNTY
DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31
SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 500 2 OF 10 STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0336	05-00308-00-WR	MCHENRY	606	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63398	