

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				0043
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	RDWY 0003	STRUCTURAL 0040	TRAFFIC SIGNALS 0021	LIGHTING 0021	100% LOCAL FUNDING	
# 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	7	7					
58700300	CONCRETE SEALER	SQ FT	195		195				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	41		41				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3					
60107600	PIPE UNDERDRAINS 4"	FOOT	600	600					
* 60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	75	75					
* Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	76		76				
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	19	19					
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	17	17					
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	169	169					
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	8	8					
60204825	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	1	1					
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	9	9					
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	18	18					
60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	19	19					
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	82	82					
60218400	MANHOLE, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	41	41					
60221100	MANHOLE, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	26	26					
60223800	MANHOLE, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	21	21					
60224446	MANHOLE, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	33	33					
60224448	MANHOLE, TYPE A, 7'-DIAMETER, TYPE 8 GRATE	EACH	3	3					
* XX008433	MANHOLES, SPECIAL, TYPE 1	EACH	3	3					
* XX008434	MANHOLES, SPECIAL, TYPE 2	EACH	3	3					
* XX008435	MANHOLES, SPECIAL, TYPE 3	EACH	7	7					
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	24	24					
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	1	1					
* XX008436	VALVE VAULTS, 5'-DIAMETER	EACH	5					5	
* 60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	3	3					
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1	1					
* 60266500	VALVE VAULTS TO BE REMOVED	EACH	3					3	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	8	8					
* 60266910	VALVE BOXES TO BE REMOVED	EACH	3					3	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	9					
60500040	REMOVING MANHOLES	EACH	19	19					
60500050	REMOVING CATCH BASINS	EACH	19	19					
60500060	REMOVING INLETS	EACH	11	11					
* 60603300	GUTTER OUTLET	EACH	7	7					
* 60603400	GUTTER OUTLET SPECIAL	EACH	16	16					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	716	716					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	65,280	65,280					
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	330	330					
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	513	513					

* DENOTES SPECIAL PROVISION
DENOTES SPECIALTY ITEM



USER NAME = Rdwy.Lisle
PLOT CONFIG = PDF(Grey, Large).plt
PLOT SCALE = 1:50
PLOT DATE = 7/28/2010

DESIGNED - MJP
DRAWN - TCK
CHECKED - JAH
DATE - 8/2/2010

REVISED -
REVISED -
REVISED -
REVISED -



MCHENRY COUNTY
DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31
SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. - SQ 4 OF 10 STA. TO STA.

F.A.P. RTE. 0336	SECTION 05-00308-00-WR	COUNTY MCHENRY	TOTAL SHEETS 606	SHEET NO. 7
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 63398	