

| SUMMARY OF QUANTITIES | | | | | CONSTRUCTION TYPE CODE | | | | 0043 |
|-----------------------|---|--------|------------|-----------|------------------------|----------------------|---------------|--------------------|------|
| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QTY. | RDWY 0003 | STRUCTURAL 0040 | TRAFFIC SIGNALS 0021 | LIGHTING 0021 | 100% LOCAL FUNDING | |
| * X4023000 | TEMPORARY ACCESS (ROAD) | EACH | 7 | 7 | | | | | |
| * X6062500 | PORTLAND CEMENT CONCRETE SIDEWALK ACCESSIBILITY RAMP, TYPE B, 5 INCH | SQ FT | 194 | 194 | | | | | |
| #* X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | FOOT | 38,322 | 38,322 | | | | | |
| #* X7830074 | GROOVING FOR RECESSED PAVEMENT MARKING 7" | FOOT | 14,768 | 14,768 | | | | | |
| #* X7830076 | GROOVING FOR RECESSED PAVEMENT MARKING 9" | FOOT | 7,327 | 7,327 | | | | | |
| #* X7330095 | OVERHEAD SIGN STRUCTURE - CANTILEVER MONOTUBE | FOOT | 41 | | 41 | | | | |
| #* X8050015 | SERVICE INSTALLATION - POLE MOUNTED | EACH | 5 | | | 5 | | | |
| #* X8210405 | LUMINAIRE SHIELD | EACH | 38 | | | | 38 | | |
| #* X8250085 | LIGHTING CONTROLLER, DUPLEX CONSOLE TYPE | EACH | 2 | | | | 2 | | |
| #* 82500340 | LIGHTING CONTROLLER, PEDESTAL MOUNTED, 480 VOLT, 60 AMP | EACH | 1 | | | | 1 | | |
| #* X8620020 | UNINTERRUPTIBLE POWER SUPPLY | EACH | 6 | | | 6 | | | |
| #* X8710020 | FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F | FOOT | 15,691 | | | 15,691 | | | |
| #* X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 2,750 | | | 2,750 | | | |
| #* X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED | FOOT | 5,522 | | | 5,522 | | | |
| #* XX005723 | VIDEO DETECTION SYSTEM COMPLETE INTERSECTION | EACH | 5 | | | 5 | | | |
| * XX005855 | WATER MAIN CASING PIPE | FOOT | 373 | | | | | 373 | |
| #* XX005937 | LED INTERNALLY ILLUMINATED STREET NAME SIGN | EACH | 20 | | | 20 | | | |
| * XX006277 | TEMPORARY SEDIMENT TRAP | EACH | 4 | 4 | | | | | |
| #* 81603175 | UNIT DUCT, 600 V, 3 1/C NO. 8, 1/C NO. 8 GROUND, (EPR-TYPE RHW), 1" DIA. POLYETHYLENE | FOOT | 2,300 | | | | 2,300 | | |
| * XX008133 | MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS | UNIT | 75,000 | 75,000 | | | | | |
| * Z0001040 | AGGREGATE SUBGRADE 8" | SQ YD | 2,123 | 2,123 | | | | | |
| * Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 195,078 | 195,078 | | | | | |
| * Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | | | | | |
| * Z0019500 | DRYWELL | EACH | 2 | 2 | | | | | |
| * Z0019600 | DUST CONTROL WATERING | UNIT | 4,182 | 4,182 | | | | | |
| * Z0030255 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 | EACH | 2 | 2 | | | | | |
| * Z0034210 | MECHANICALLY STABILIZED EARTH RETAINING WALL | SQ FT | 3,400 | | 3,400 | | | | |
| * Z0042500 | POST, SPECIAL | EACH | 2 | 2 | | | | | |
| * Z0066400 | STABILIZED DRIVEWAYS 6" | SQ YD | 15 | 15 | | | | | |
| * Z0066600 | STABILIZED DRIVEWAYS 8" | SQ YD | 879 | 879 | | | | | |
| +* Z0076600 | TRAINEES | HOURLY | 6,000 | 6,000 | | | | | |
| #* 81603232 | UNIT DUCT, 600V, 3-1/C NO. 1/0, 1/C NO. 2 GROUND, (EPR-TYPE RHW), 2" DIA., POLYETHYLENE | FOOT | 6,700 | | | | 6,700 | | |
| #* X0327080 | WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS - LINE 8" | FOOT | 7,327 | | | | | 7,327 | |

+ (0042)

* DENOTES SPECIAL PROVISION
DENOTES SPECIALTY ITEM



USER NAME = tkoeppen(Rdwg_L1s1e)
PLOT CONFIG = PDF(Grey_Large).plt
PLOT SCALE = 1:50
PLOT DATE = 9/21/2010

DESIGNED - MJP
DRAWN - TCK
CHECKED - JAH
DATE - 8/2/2010

REVISED -
REVISED -
REVISED -
REVISED -



MCHENRY COUNTY
DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31
SUMMARY OF QUANTITIES
SCALE: NA SHEET NO. 9 OF 10 STA. TO STA.

| | | | | |
|------------------------------|------------------------|-------------------------------------|------------------|--------------|
| F.A.P. RTE. 0336 | SECTION 05-00308-00-WR | COUNTY MCHENRY | TOTAL SHEETS 606 | SHEET NO. 12 |
| FED. ROAD DIST. NO. ILLINOIS | | FED. AID PROJECT CONTRACT NO. 63398 | | |