

SUMMARY OF QUANTITIES					100% LOCAL FUNDING	CONSTRUCTION TYPE CODE			0043
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	RDWY 0003	STRUCTURAL 0040	TRAFFIC SIGNALS 0021	LIGHTING 0021	100% LOCAL FUNDING	
	FULL-DEPTH PAVEMENT OPTION (RAKOW ROAD) <i>ALTERNATE A</i>								
Δ 20200100	EARTH EXCAVATION	CU YD	145,565	145,565					
Δ 20400800	FURNISHED EXCAVATION	CU YD	8,395	8,395					
Δ 35501331	HOT-MIX ASPHALT BASE COURSE, 11 3/4"	SQ YD	148,602	148,602					
Δ 40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	17,150	17,150					
	COMPOSITE PAVEMENT OPTION (RAKOW ROAD) <i>ALTERNATE B</i>								
Δ 20200100	EARTH EXCAVATION	CU YD	128,625	128,625					
		CU YD	46,260	46,260					
Δ 20400800	FURNISHED EXCAVATION	CU YD	16,090	16,090					
Δ 35300205	PORTLAND CEMENT CONCRETE BASE COURSE 7 1/4"	SQ YD	148,602	148,602					
Δ 40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	15,007	15,007					

Δ 100% LOCAL FUNDING



USER NAME = Rdwg.Lisle  
 PLOT CONFIG = PDF(Grey, Large).plt  
 PLOT SCALE = 1:50  
 PLOT DATE = 7/28/2010

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE = 8/2/2010

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -



MCHENRY COUNTY  
 DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31  
 SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 500 10 OF 10 STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0336	05-00308-00-WR	MCHENRY	606	13
CONTRACT NO. 63398				

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT