

RAKOW ROAD EARTHWORK COMPOSITE PAVEMENT			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
187+00.00	TO	188+00.00	0.00	26.71	183.68	46.67	95.25	14.86	0.00	22.71	156.12	107.80	142.08	73.13	-107.80	-119.38	82.99
188+00.00	TO	188+47.94	0.00	16.42	84.21	14.47	43.33	13.46	0.00	13.96	71.57	28.69	53.41	5.57	-28.69	-39.46	66.01
188+47.94	TO	189+00.00	0.00	28.06	95.21	6.88	45.54	12.58	0.00	23.85	80.93	18.70	39.33	2.69	-18.70	-15.47	78.23
189+00.00	TO	190+00.00	0.00	74.49	223.21	19.16	95.61	30.09	0.00	63.32	198.73	18.87	73.18	0.90	-18.87	-9.86	188.83
190+00.00	TO	190+68.04	0.00	59.18	164.79	24.68	69.81	24.68	0.00	50.30	140.07	15.38	66.88	0.00	-15.38	-16.58	140.07
190+68.04	TO	191+00.00	0.00	29.84	78.62	9.92	33.61	9.92	0.00	25.36	66.82	8.13	37.20	0.00	-8.13	-11.84	66.82
191+00.00	TO	192+00.00	0.00	97.04	247.89	25.89	110.26	25.89	0.00	82.48	210.71	18.40	104.99	0.04	-18.40	-22.51	210.67
192+00.00	TO	193+00.00	0.00	93.10	233.31	24.53	112.40	24.53	0.00	79.14	198.31	12.10	84.07	0.94	-12.10	-4.94	197.37
193+00.00	TO	194+00.00	0.00	72.70	195.08	26.13	106.80	26.13	0.00	61.80	165.82	13.20	74.07	5.26	-13.20	-12.28	160.56
194+00.00	TO	195+00.00	0.00	48.38	163.29	28.32	100.95	28.32	0.00	41.12	138.79	14.22	100.23	9.67	-14.22	-59.11	129.13
195+00.00	TO	196+00.00	0.00	49.66	163.50	27.44	94.86	27.44	0.00	42.21	138.98	12.39	91.34	8.32	-12.39	-49.13	130.65
196+00.00	TO	197+00.00	0.00	108.01	184.62	24.28	95.78	24.28	0.00	91.81	156.93	10.96	26.59	4.75	-10.96	65.22	152.18
197+00.00	TO	198+00.00	0.00	138.18	190.61	23.23	96.43	11.59	0.00	117.45	162.02	8.92	0.20	3.56	-8.92	117.25	158.45
198+00.00	TO	199+00.00	0.00	106.19	189.84	23.12	95.94	11.48	0.00	90.26	161.37	10.05	32.16	4.22	-10.05	58.10	157.14
199+00.00	TO	200+00.00	0.00	77.53	198.18	22.14	97.29	22.14	0.00	65.90	168.45	12.28	58.25	4.24	-12.28	7.65	164.21
200+00.00	TO	201+00.00	0.00	94.37	200.25	21.40	98.94	21.40	0.00	80.21	170.21	11.18	40.46	3.81	-11.18	39.75	166.41
201+00.00	TO	202+00.00	0.00	126.73	200.72	21.04	104.61	21.04	0.00	107.72	170.61	10.11	29.34	3.74	-10.11	78.38	166.87
202+00.00	TO	203+00.00	0.00	123.89	192.06	20.25	104.22	20.25	0.00	105.31	163.26	8.55	31.25	3.80	-8.55	74.06	159.46
203+00.00	TO	204+00.00	0.00	101.10	170.21	19.99	101.44	19.99	0.00	85.94	144.68	6.81	35.19	4.88	-6.81	50.75	139.80
204+00.00	TO	205+00.00	0.00	74.19	130.35	21.07	99.47	21.07	0.00	63.06	110.80	5.90	39.56	9.08	-5.90	23.49	101.72
205+00.00	TO	206+00.00	0.00	79.98	89.10	11.04	99.80	21.79	0.00	67.98	75.74	2.97	40.78	14.99	-2.97	27.21	60.75
206+00.00	TO	207+00.00	0.00	160.61	90.31	0.00	104.87	20.67	0.00	136.52	76.77	0.00	28.44	13.70	0.00	108.08	63.06
207+00.00	TO	208+00.00	0.00	319.46	140.80	0.00	112.61	17.19	0.00	271.54	119.68	0.00	8.93	5.36	0.00	262.62	114.32
208+00.00	TO	209+00.00	0.00	448.81	195.92	0.00	118.49	21.30	0.00	381.48	166.53	0.00	0.81	0.43	0.00	380.68	166.10
209+00.00	TO	210+00.00	0.00	491.85	223.98	0.00	120.53	26.81	0.00	418.07	190.38	0.00	0.09	0.00	0.00	417.98	190.38
210+00.00	TO	211+00.00	0.00	449.10	230.48	0.00	121.97	26.72	0.00	381.74	195.91	0.00	7.21	0.00	0.00	374.52	195.91
211+00.00	TO	212+00.00	0.00	369.08	217.48	0.00	123.68	24.59	0.00	313.72	184.86	0.00	24.65	0.01	0.00	289.07	184.85
212+00.00	TO	213+00.00	0.00	297.02	188.68	0.00	122.13	24.79	0.00	252.47	160.37	2.20	39.52	6.06	-2.20	212.95	154.32
213+00.00	TO	214+00.00	0.00	227.74	136.20	0.00	119.38	34.37	0.00	193.58	115.77	4.31	57.34	20.10	-4.31	136.24	95.67
214+00.00	TO	215+00.00	0.00	169.56	86.70	0.00	118.34	54.58	0.00	144.13	73.70	4.65	86.81	48.19	-4.65	57.32	25.51
215+00.00	TO	216+00.00	0.00	95.23	94.86	0.00	115.95	66.37	0.00	80.95	80.63	5.62	132.94	64.69	-5.62	-52.00	15.94
216+00.00	TO	216+54.54	0.00	20.97	82.63	0.00	61.07	34.98	0.00	17.82	70.23	4.19	83.33	37.45	-4.19	-65.51	32.79
216+54.54	TO	217+00.00	0.00	12.59	80.70	0.00	49.88	28.84	0.00	10.70	68.59	6.71	71.46	33.97	-6.71	-60.76	34.62
217+00.00	TO	217+66.64	0.00	27.35	119.80	0.00	75.54	40.69	0.00	23.25	101.83	11.16	154.66	42.01	-11.16	-131.42	59.82
217+66.64	TO	218+00.00	0.00	17.99	60.82	0.00	38.89	19.66	0.00	15.29	51.70	4.41	103.28	16.82	-4.41	-87.99	34.88
218+00.00	TO	219+00.00	0.00	71.91	156.19	25.94	107.09	29.22	0.00	61.12	132.76	30.76	285.38	41.77	-30.76	-224.26	90.99
219+00.00	TO	219+66.76	0.00	62.11	88.08	36.43	69.63	0.00	0.00	52.79	74.87	29.97	165.97	25.37	-29.97	-113.17	49.49
219+66.76	TO	220+00.00	0.00	34.04	41.81	19.21	36.14	0.00	0.00	28.93	35.54	14.15	82.69	13.46	-14.15	-53.76	22.08
220+00.00	TO	221+00.00	0.00	124.60	141.91	57.82	105.49	0.00	0.00	105.91	120.62	33.14	216.59	38.18	-33.14	-110.68	82.45
221+00.00	TO	221+45.14	0.00	69.01	82.87	12.93	49.81	12.02	0.00	58.66	70.44	5.11	98.78	10.90	-5.11	-40.12	59.54
221+45.14	TO	223+34.98	0.00	270.59	449.43	24.50	186.80	90.31	0.00	230.00	382.01	20.09	260.59	15.73	-20.09	-30.59	366.28
223+34.98	TO	224+00.00	0.00	69.19	154.18	19.73	53.33	25.39	0.00	58.81	131.05	31.06	13.33	6.62	-31.06	45.48	124.43
224+00.00	TO	224+83.97	0.00	82.10	178.10	28.14	70.19	34.85	0.00	69.79	151.39	50.27	13.12	15.99	-50.27	56.67	135.39
224+83.97	TO	225+00.00	0.00	17.51	34.30	5.11	12.91	7.50	0.00	14.89	29.16	6.78	2.32	3.94	-6.78	12.57	25.21
225+00.00	TO	226+00.00	0.00	140.97	200.22	29.79	83.41	39.72	0.00	119.83	170.19	31.19	6.45	16.16	-31.19	113.37	154.03
226+00.00	TO	226+30.00	0.00	46.74	57.39	8.03	26.86	12.94	0.00	39.73	48.78	6.39	0.00	2.05	-6.39	39.73	46.73
226+30.00	TO	226+83.71	0.00	68.94	87.56	13.26	48.42	28.19	0.00	58.60	74.43	11.16	0.00	8.28	-11.16	58.60	66.15
226+83.71	TO	227+00.00	0.00	18.23	19.93	3.89	14.70	8.17	0.00	15.50	16.94	3.72	0.00	3.96	-3.72	15.50	12.97
227+00.00	TO	227+53.61	0.00	52.32	47.05	13.92	46.13	23.70	0.00	44.47	39.99	15.48	6.22	22.84	-15.48	38.25	17.15
227+53.61	TO	228+00.00	0.00	42.54	25.47	13.69	38.02	18.18	0.00	36.16	21.65	18.10	15.57	32.26	-18.10	20.59	-10.62
228+00.00	TO	229+00.00	0.00	100.51	56.96	31.92	84.85	39.80	0.00	85.43	48.42	50.25	56.50	81.92	-50.25	28.93	-33.50
229+00.00	TO	229+53.61	0.00	58.15	36.93	18.83	47.27	22.00	0.00	49.42	31.39	37.82	58.25	52.83	-37.82	-8.82	-21.44
229+53.61	TO	230+00.00	0.00	53.57	30.00	16.82	39.69	18.87	0.00	45.54	25.50	36.97	57.24	51.77	-36.97	-11.71	-26.27
230+00.00	TO	231+00.00	0.00	123.24	78.84	27.49	78.81	45.40	0.00	104.75	67.02	46.89	77.28	65.92	-46.89	27.48	1.10
231+00.00	TO	231+19.00	0.00	25.59	22.09	2.91	13.63	9.85	0.00	21.75	18.77	2.49	8.10	2.92	-2.49	13.65	15.85
231+19.00	TO	231+53.61	0.00	45.81	51.41	1.85	23.61	14.50	0.00	38.94	43.70	1.26	6.88	2.53	-1.26	32.06	41.17
231+53.61	TO	232+10.61	0.00	35.52	47.03	0.00	19.45	8.81	0.00	30.19	39.98	0.00	2.98	1.76	0.00	27.21	38.22
232+10.61	TO	232+67.61	0.00	46.12	76.76	0.00	14.94	8.82	0.00	39.20	65.25	0.00	0.00	0.00	0.00	39.20	65.25
232+67.61	TO	233+00.00	0.00	56.07	95.30	0.00	19.11	13.07	0.00	47.66	81.00	0.00	3.93	0.00	0.00	43.73	81.00
233+00.00	TO	234+00.00	0.00	284.65	337.30	0.00	72.16	50.27	0.00	241.95	286.70	1.77	12.13	0.00	-1.77	229.82	286.70
234+00.00	TO	234+69.94	0.00	225.65	221.30	0.00	59.38	34.36	0.00	191.81	188.10	2.81	0.00	0.93	-2.81	191.81	187.17

	USER NAME = Rdwy.Lisle PLOT CONFID = PDF(Dwg_Large).plt PLOT SCALE = 1:50 PLOT DATE = 7/28/2010	DESIGNED - MJP DRAWN - TCK CHECKED - JAH DATE - 8/2/2010	REVISED - REVISED - REVISED - REVISED -		RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31 RAKOW ROAD EARTHWORK SCHEDULE COMPOSITE PAVEMENT	F.A.P. RTE. 0336 SECTION 05-00308-00-WR COUNTY MCHENRY TOTAL SHEETS 606 SHEET NO. 21 CONTRACT NO. 63398	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
	SCALE: 1"=50' SHEET NO. SHD 8 OF 17 STA. TO STA.						

G:\MCDOT\20950_001\Drawings\RDWY\shhs\rd\15.Earth.Sched.01.dgn