

ACKMAN ROAD EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
7+00.00	TO	8+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+00.00	TO	9+03.18	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9+03.18	TO	9+43.18	0.00	0.00	39.70	0.00	0.00	9.81	0.00	0.00	33.75	0.00	0.00	0.94	0.00	0.00	32.81
9+43.18	TO	10+00.00	0.00	0.00	116.11	0.00	0.00	29.28	0.00	0.00	98.69	0.00	0.00	2.89	0.00	0.00	95.80
10+00.00	TO	10+48.62	3.51	0.00	100.90	7.34	0.00	21.32	2.98	0.00	85.76	0.00	0.00	3.78	2.98	0.00	81.98
10+48.62	TO	11+00.00	16.71	0.00	113.49	18.43	0.00	26.43	14.20	0.00	96.46	0.00	0.00	5.72	14.20	0.00	90.75
11+00.00	TO	12+00.00	25.30	0.00	246.45	33.31	0.00	59.48	21.50	0.00	209.49	6.02	0.00	18.34	15.48	0.00	191.14
12+00.00	TO	13+00.00	4.31	0.00	244.42	21.93	0.00	51.72	3.67	0.00	207.75	6.02	0.00	26.48	-2.35	0.00	181.27
13+00.00	TO	14+00.00	48.79	0.00	214.55	15.41	0.00	61.02	41.47	0.00	182.36	0.00	0.00	44.63	41.47	0.00	137.73
14+00.00	TO	14+53.25	41.63	0.00	101.12	6.76	0.00	31.80	35.38	0.00	85.95	0.00	0.00	29.17	35.38	0.00	56.78
14+53.25	TO	15+15.45	20.96	0.00	117.56	4.15	0.00	15.87	17.82	0.00	99.92	0.00	0.00	15.18	17.82	0.00	84.75
15+15.45	TO	15+87.17	40.53	0.00	152.88	7.74	0.00	22.65	34.45	0.00	129.95	0.00	0.00	1.83	34.45	0.00	128.12
15+87.17	TO	16+00.00	14.89	0.00	30.13	3.41	0.00	7.36	12.66	0.00	25.61	0.00	0.00	0.41	12.66	0.00	25.20
16+00.00	TO	17+00.00	140.89	0.00	220.03	36.55	0.00	36.64	119.76	0.00	187.02	0.00	0.00	5.37	119.76	0.00	181.65
17+00.00	TO	17+28.25	46.43	0.00	52.11	12.08	0.00	6.52	39.46	0.00	44.29	0.00	0.00	2.69	39.46	0.00	41.60
17+28.25	TO	18+00.00	120.72	0.00	112.07	30.22	0.00	32.21	102.61	0.00	95.26	0.00	0.00	12.56	102.61	0.00	82.70
18+00.00	TO	18+21.03	32.87	0.00	26.93	8.59	0.00	13.36	27.94	0.00	22.89	0.00	0.00	5.99	27.94	0.00	16.90
18+21.03	TO	18+86.41	55.20	0.00	49.11	28.46	0.00	44.80	46.92	0.00	41.74	0.00	0.00	45.00	46.92	0.00	-3.26
18+86.41	TO	21+24.20	57.80	571.51	47.47	73.43	41.33	89.70	49.13	485.78	40.35	0.00	0.00	126.27	49.13	485.78	-85.92
21+24.20	TO	21+87.44	29.11	234.42	0.00	11.30	12.77	0.00	24.75	199.26	0.00	0.00	0.00	0.00	24.75	199.26	0.00
21+87.44	TO	22+00.00	4.40	16.37	0.00	1.22	0.35	0.00	3.74	13.92	0.00	0.00	0.00	0.00	3.74	13.92	0.00
TOTALS =			704.05	822.30	1985.01	320.32	54.45	559.97	598.45	698.96	1687.26	12.04	0.00	347.23	586.41	698.96	1340.03

EARTH EXCAVATION = 3511 CU YD
FURNISHED EXCAVATION = 2625 CU YD
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL = 935 CU YD

G:\MCDOT\2010\Drawings\RDW\shits\rd\15.Earth_Sched_01.dgn