

MCHENRY AVENUE EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
6+50.00	TO	6+81.33	0.00	0.00	4.55	0.00	0.00	7.38	0.00	0.00	3.86	0.00	0.00	2.72	0.00	0.00	1.15
6+81.33	TO	7+00.00	0.00	0.00	5.69	0.00	0.00	9.83	0.00	0.00	4.84	0.00	0.00	3.44	0.00	0.00	1.40
7+00.00	TO	8+00.00	0.00	0.00	65.86	0.00	0.00	73.56	0.00	0.00	55.98	0.00	0.00	34.69	0.00	0.00	21.29
8+00.00	TO	8+89.46	0.00	0.00	75.72	0.00	0.00	94.38	0.00	0.00	64.36	0.00	0.00	64.60	0.00	0.00	-0.24
8+89.46	TO	9+23.26	0.00	0.00	16.91	0.00	0.00	40.67	0.00	0.00	14.37	0.00	0.00	35.02	0.00	0.00	-20.64
9+23.26	TO	9+59.84	0.00	0.00	35.27	0.00	0.00	56.12	0.00	0.00	29.98	0.00	0.00	45.62	0.00	0.00	-15.64
9+59.84	TO	9+86.69	0.00	0.00	28.98	0.00	0.00	50.00	0.00	0.00	24.63	0.00	0.00	63.14	0.00	0.00	-38.51
9+86.69	TO	10+00.00	0.00	0.00	7.23	0.00	0.00	24.32	0.00	0.00	6.15	0.00	0.00	42.93	0.00	0.00	-36.78
10+00.00	TO	11+00.00	0.00	0.00	50.42	5.40	0.00	164.08	0.00	0.00	42.85	2.78	0.00	300.29	-2.78	0.00	-257.43
11+00.00	TO	12+00.00	0.00	0.00	42.27	14.44	0.00	143.04	0.00	0.00	35.93	5.56	0.00	268.45	-5.56	0.00	-232.53
12+00.00	TO	12+25.14	0.00	0.00	11.07	4.89	0.00	34.48	0.00	0.00	9.41	2.31	0.00	61.87	-2.31	0.00	-52.46
12+25.14	TO	12+56.20	0.00	0.00	13.81	3.24	0.00	43.83	0.00	0.00	11.74	3.08	0.00	74.31	-3.08	0.00	-62.57
12+56.20	TO	13+00.00	0.00	0.00	44.64	6.87	0.00	67.39	0.00	0.00	37.94	7.58	0.00	92.20	-7.58	0.00	-54.26
13+00.00	TO	14+00.00	0.00	0.00	197.12	33.71	0.00	137.69	0.00	0.00	167.55	30.42	0.00	168.36	-30.42	0.00	-0.81
14+00.00	TO	14+43.15	0.00	0.00	107.92	15.55	0.00	46.68	0.00	0.00	91.73	14.76	0.00	42.83	-14.76	0.00	48.90
14+43.15	TO	14+65.06	0.00	0.00	47.36	3.95	0.00	31.15	0.00	0.00	40.26	3.85	0.00	10.49	-3.85	0.00	29.77
14+65.06	TO	15+00.00	1.74	0.00	50.44	2.76	0.00	48.06	1.48	0.00	42.87	0.00	0.00	23.32	1.48	0.00	19.55
15+00.00	TO	16+00.00	4.99	0.00	64.99	18.94	0.00	82.57	4.24	0.00	55.24	7.04	0.00	128.12	-2.79	0.00	-72.88
16+00.00	TO	17+00.00	0.00	0.00	11.80	19.89	0.00	97.10	0.00	0.00	10.03	13.06	0.00	574.88	-13.06	0.00	-564.85
17+00.00	TO	18+00.00	0.00	0.00	11.25	17.36	0.00	120.96	0.00	0.00	9.56	11.76	0.00	1070.57	-11.76	0.00	-1061.01
18+00.00	TO	18+46.95	0.00	0.00	0.56	8.74	0.00	56.29	0.00	0.00	0.48	6.19	0.00	540.09	-6.19	0.00	-539.61
18+46.95	TO	21+13.02	0.00	532.04	0.00	26.85	102.36	158.63	0.00	452.24	0.00	19.83	0.00	1515.98	-19.83	452.24	-1515.98
21+13.02	TO	21+57.54	0.00	143.70	0.00	0.00	33.73	0.00	0.00	122.15	0.00	0.00	0.58	0.00	0.00	121.56	0.00
21+57.54	TO	22+00.00	2.56	78.84	0.00	0.00	24.04	0.00	2.17	67.01	0.00	0.00	1.00	0.00	2.17	66.01	0.00
TOTALS =			9.29	754.58	893.86	182.58	160.13	1588.22	7.90	641.39	759.78	128.21	1.58	5163.92	-120.32	639.81	-4404.14

EARTH EXCAVATION = **1658** **CU YD**
FURNISHED EXCAVATION = **3885** **CU YD**
REMOVAL AND DISPOSAL OF **1931** **CU YD**
UNSUITABLE MATERIAL =

G:\MCDOT\20950_001\Drawings\RDWY\shs\rd\15.Earth.Sched.01.dgn