

PYOTT ROAD EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
43+98.32	TO	44+98.32	0.00	90.54	0.00	0.00	62.68	0.00	0.00	76.96	0.00	0.00	46.81	0.00	0.00	30.14	0.00
44+98.32	TO	45+38.37	0.00	45.30	0.00	0.00	26.92	0.00	0.00	38.51	0.00	0.00	22.60	0.00	0.00	15.91	0.00
45+38.37	TO	46+17.26	0.00	97.12	0.00	12.05	44.57	0.00	0.00	82.55	0.00	23.69	84.19	0.00	-23.69	-1.64	0.00
46+17.26	TO	46+92.65	0.00	98.79	0.00	25.62	44.07	0.00	0.00	83.97	0.00	56.90	119.82	0.00	-56.90	-35.85	0.00
46+92.65	TO	47+41.24	0.00	79.86	0.00	18.47	18.60	0.00	0.00	67.88	0.00	47.38	63.38	0.00	-47.38	4.51	0.00
47+41.24	TO	47+91.42	0.00	83.76	0.00	20.70	20.01	0.00	0.00	71.20	0.00	59.01	64.60	0.00	-59.01	6.60	0.00
47+91.42	TO	48+47.64	0.00	65.01	0.00	25.06	37.40	0.00	0.00	55.26	0.00	72.10	95.00	0.00	-72.10	-39.75	0.00
48+47.64	TO	49+00.55	0.00	154.30	0.00	24.02	38.17	0.00	0.00	131.16	0.00	71.67	97.33	0.00	-71.67	33.83	0.00
49+00.55	TO	51+04.12	0.00	486.42	1206.11	109.91	75.98	108.14	0.00	413.46	1025.20	416.24	192.90	26.95	-416.24	220.55	998.24
51+04.12	TO	51+79.93	0.00	0.00	645.14	48.35	0.00	47.14	0.00	0.00	548.37	158.38	0.00	38.80	-158.38	0.00	509.57
51+79.93	TO	52+00.00	0.00	0.00	99.02	13.17	0.00	3.66	0.00	0.00	84.16	30.64	0.00	16.92	-30.64	0.00	67.25
52+00.00	TO	52+19.59	0.00	0.00	89.40	13.35	0.00	10.45	0.00	0.00	75.99	39.62	0.00	29.09	-39.62	0.00	46.89
52+19.59	TO	52+98.37	0.00	0.00	328.51	54.24	0.00	42.90	0.00	0.00	279.24	205.26	0.00	155.13	-205.26	0.00	124.10
52+98.37	TO	53+45.58	0.00	0.00	200.37	23.25	0.00	6.93	0.00	0.00	170.31	77.42	0.00	63.64	-77.42	0.00	106.67
53+45.58	TO	53+88.84	0.00	0.00	188.65	22.24	0.00	7.31	0.00	0.00	160.35	42.72	0.00	37.97	-42.72	0.00	122.38
53+88.84	TO	54+00.00	0.00	0.00	45.91	6.97	0.00	3.85	0.00	0.00	39.03	14.66	0.00	10.56	-14.66	0.00	28.47
54+00.00	TO	55+00.00	0.00	0.00	427.26	48.34	0.00	53.14	0.00	0.00	363.17	130.57	0.00	97.95	-130.57	0.00	265.22
55+00.00	TO	55+89.30	0.00	0.00	326.83	36.27	0.00	58.10	0.00	0.00	277.81	103.86	0.00	120.16	-103.86	0.00	157.65
55+89.30	TO	56+00.00	0.00	0.00	29.92	4.56	0.00	6.59	0.00	0.00	25.43	8.52	0.00	18.00	-8.52	0.00	7.43
56+00.00	TO	56+33.42	0.00	0.00	83.96	8.87	0.00	17.15	0.00	0.00	71.36	12.27	0.00	60.57	-12.27	0.00	10.79
56+33.42	TO	56+73.47	0.00	0.00	87.32	11.09	0.00	20.71	0.00	0.00	74.22	11.11	0.00	70.05	-11.11	0.00	4.16
56+73.47	TO	57+00.00	0.00	0.00	52.41	11.39	0.00	16.01	0.00	0.00	44.55	11.00	0.00	39.66	-11.00	0.00	4.88
57+00.00	TO	58+00.00	0.00	0.00	210.79	43.09	0.00	49.12	0.00	0.00	179.17	59.95	0.00	112.57	-59.95	0.00	66.59
58+00.00	TO	58+46.61	3.96	0.00	117.07	24.16	0.00	13.85	3.36	0.00	99.51	34.92	0.00	36.05	-31.55	0.00	63.47
58+46.61	TO	59+00.00	4.53	0.00	146.22	30.73	0.00	14.61	3.85	0.00	124.29	36.55	0.00	43.97	-32.69	0.00	80.32
59+00.00	TO	59+25.00	0.00	0.00	66.10	14.98	0.00	10.09	0.00	0.00	56.19	17.60	0.00	21.75	-17.60	0.00	34.44
59+25.00	TO	60+00.00	0.00	0.00	165.87	41.64	0.00	27.59	0.00	0.00	140.99	72.46	0.00	68.28	-72.46	0.00	72.71
60+00.00	TO	60+57.67	0.00	0.00	110.75	31.48	0.00	15.92	0.00	0.00	94.14	68.34	0.00	53.62	-68.34	0.00	40.52
60+57.67	TO	61+00.00	0.00	0.00	86.02	17.59	0.00	20.12	0.00	0.00	73.11	30.61	0.00	25.48	-30.61	0.00	47.63
61+00.00	TO	61+35.94	0.00	0.00	68.25	8.71	0.00	20.44	0.00	0.00	58.01	9.21	0.00	10.43	-9.21	0.00	47.58
61+35.94	TO	62+00.00	0.00	0.00	105.90	6.92	0.00	33.44	0.00	0.00	90.02	13.64	0.00	14.41	-13.64	0.00	75.60

TOTALS = 8.49 1201.10 4887.77 757.24 368.41 607.25 7.22 1020.93 4154.61 1936.31 786.63 1172.05 -1929.10 234.30 2982.56

EARTH EXCAVATION = 6097 CU YD
 FURNISHED EXCAVATION = 1288 CU YD
 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL = 1733 CU YD

Q:\MCDOT\20950_001\Drawings\RDW\shhs\rd\NS_Earth_Sched_01.dgn