

VIRGINIA ROAD EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
40+00.00	TO	41+00.00	0.00	21.84	0.00	37.37	54.59	0.00	0.00	18.57	0.00	69.41	114.51	0.00	-69.41	-95.94	0.00
41+00.00	TO	42+00.00	0.00	67.33	0.00	37.85	75.21	0.00	0.00	57.23	0.00	64.37	118.24	0.00	-64.37	-61.01	0.00
42+00.00	TO	43+00.00	0.00	117.71	0.00	36.01	77.18	0.00	0.00	100.06	0.00	48.64	110.54	0.00	-48.64	-10.48	0.00
43+00.00	TO	44+00.00	0.00	137.38	0.00	31.69	72.03	0.00	0.00	116.77	0.00	35.85	127.10	0.00	-35.85	-10.33	0.00
44+00.00	TO	45+00.00	0.00	101.43	0.00	32.46	72.97	0.00	0.00	86.21	0.00	47.46	150.27	0.00	-47.46	-64.06	0.00
45+00.00	TO	46+00.00	0.00	94.55	0.00	38.15	68.15	0.00	0.00	80.36	0.00	73.18	152.59	0.00	-73.18	-72.23	0.00
46+00.00	TO	47+00.00	0.00	186.44	0.00	45.76	67.90	0.00	0.00	158.48	0.00	116.94	139.18	0.00	-116.94	19.30	0.00
47+00.00	TO	47+24.18	0.00	60.74	0.00	11.97	16.37	0.00	0.00	51.63	0.00	34.93	35.38	0.00	-34.93	16.26	0.00
47+24.18	TO	48+00.00	0.00	191.23	0.00	37.75	54.88	0.00	0.00	162.55	0.00	120.63	141.01	0.00	-120.63	21.54	0.00
48+00.00	TO	48+20.36	0.00	48.55	0.00	9.98	13.84	0.00	0.00	41.27	0.00	36.19	45.19	0.00	-36.19	-3.92	0.00
48+20.36	TO	51+80.28	216.25	417.71	237.11	161.66	108.74	41.22	183.81	355.05	201.55	323.29	414.17	52.49	-139.48	-59.12	149.06
51+80.28	TO	52+00.00	21.01	0.00	25.05	8.04	0.00	5.22	17.86	0.00	21.30	0.00	0.00	6.32	17.86	0.00	14.98
52+00.00	TO	53+00.00	46.48	0.00	95.81	35.66	0.00	36.90	39.51	0.00	81.44	0.00	0.00	45.39	39.51	0.00	36.05
53+00.00	TO	53+53.45	0.00	0.00	34.08	17.00	0.00	18.53	0.00	0.00	28.97	0.00	0.00	32.89	0.00	0.00	-3.92
53+53.45	TO	54+00.00	0.00	0.00	28.39	14.87	0.00	12.02	0.00	0.00	24.13	0.00	0.00	31.68	0.00	0.00	-7.55
54+00.00	TO	54+96.04	0.00	0.00	66.95	30.07	0.00	25.39	0.00	0.00	56.91	0.00	0.00	61.94	0.00	0.00	-5.03
54+96.04	TO	55+19.83	0.00	0.00	18.63	6.30	0.00	8.96	0.00	0.00	15.84	0.00	0.00	14.73	0.00	0.00	1.11
55+19.83	TO	55+41.96	0.00	0.00	18.35	4.91	0.00	9.17	0.00	0.00	15.60	0.00	0.00	12.35	0.00	0.00	3.25
55+41.96	TO	56+00.00	0.00	0.00	50.73	11.42	0.00	18.71	0.00	0.00	43.12	0.00	0.00	25.89	0.00	0.00	17.23
56+00.00	TO	57+00.00	6.58	0.00	101.70	18.29	0.00	23.59	5.60	0.00	86.45	0.00	0.00	29.17	5.60	0.00	57.28
57+00.00	TO	57+62.70	7.49	0.00	76.49	10.69	0.00	12.87	6.37	0.00	65.02	0.00	0.00	7.76	6.37	0.00	57.26
57+62.70	TO	58+00.00	2.00	0.00	68.90	2.91	0.00	17.64	1.70	0.00	58.57	0.00	0.00	9.32	1.70	0.00	49.25
58+00.00	TO	59+00.00	0.00	0.00	119.47	0.00	0.00	35.34	0.00	0.00	101.55	0.00	0.00	21.11	0.00	0.00	80.44
TOTALS =			299.83	1444.92	941.69	640.80	681.86	265.57	254.86	1228.18	800.43	970.90	1548.18	351.02	-716.05	-320.00	449.41

EARTH EXCAVATION = 2686 CU YD
FURNISHED EXCAVATION = 587 CU YD
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL = 1588 CU YD

G:\MCD01\20950_001\Drawings\ROW\Asht\Road\Virginia Road_Sched_01.dgn