

PINGREE ROAD EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
18+65.38	TO	19+00.00	0.00	22.44	0.00	3.53	10.97	0.00	0.00	19.08	0.00	45.75	17.60	0.00	-45.75	1.48	0.00
19+00.00	TO	21+00.00	0.00	69.04	243.22	82.44	51.63	42.37	0.00	58.68	206.74	276.28	90.61	158.98	-276.28	-31.93	47.76
21+00.00	TO	21+48.48	0.00	0.00	81.18	43.02	0.00	12.13	0.00	0.00	69.00	95.91	0.00	104.75	-95.91	0.00	-35.74
21+48.48	TO	22+00.00	0.00	0.00	36.05	49.39	0.00	5.46	0.00	0.00	30.65	124.10	0.00	118.04	-124.10	0.00	-87.39
22+00.00	TO	22+90.28	0.00	0.00	37.75	79.25	0.00	13.54	0.00	0.00	32.09	170.60	0.00	170.41	-170.60	0.00	-138.32
22+90.28	TO	23+65.33	0.00	0.00	24.86	49.44	0.00	25.16	0.00	0.00	21.13	96.61	0.00	129.62	-96.61	0.00	-108.49
23+65.33	TO	24+61.41	0.00	0.00	45.99	39.09	0.00	49.90	0.00	0.00	39.09	57.41	0.00	108.77	-57.41	0.00	-69.67
24+61.41	TO	24+90.28	0.00	0.00	24.04	10.34	0.00	14.16	0.00	0.00	20.43	9.66	0.00	16.10	-9.66	0.00	4.33
24+90.28	TO	26+00.00	0.00	0.00	130.30	37.35	0.00	61.84	0.00	0.00	110.76	20.01	0.00	26.06	-20.01	0.00	84.70
26+00.00	TO	27+00.00	0.00	0.00	103.81	28.17	0.00	63.76	0.00	0.00	88.23	4.45	0.00	15.07	-4.45	0.00	73.16
27+00.00	TO	27+17.46	0.00	0.00	12.36	4.09	0.00	11.04	0.00	0.00	10.51	0.00	0.00	4.44	0.00	0.00	6.06
27+17.46	TO	28+00.00	0.00	0.00	51.50	19.44	0.00	49.37	0.00	0.00	43.77	5.44	0.00	23.84	-5.44	0.00	19.93
28+00.00	TO	29+00.00	0.00	0.00	57.76	18.42	0.00	50.94	0.00	0.00	49.10	6.59	0.00	18.49	-6.59	0.00	30.60
29+00.00	TO	29+70.31	0.00	0.00	31.91	8.01	0.00	26.49	0.00	0.00	27.12	0.00	0.00	5.47	0.00	0.00	21.65
29+70.31	TO	30+00.00	0.00	0.00	4.49	1.53	0.00	3.88	0.00	0.00	3.81	0.00	0.00	0.92	0.00	0.00	2.89
TOTALS =			0.00	91.48	885.22	473.50	62.60	430.04	0.00	77.76	752.44	912.80	108.21	900.96	-912.80	-30.45	-148.52

EARTH EXCAVATION = 977 CU YD
 FURNISHED EXCAVATION = 1092 CU YD
 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL = 966 CU YD

G:\MCDOT\2010\Drawings\RD\W\shs\rd\15.Earth.Sched.01.dgn