

IL RTE 31 EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2	PRESTAGE	STAGE 1	STAGE 2
51+34.64	TO	52+00.00	0.00	0.00	126.43	0.00	0.00	28.90	0.00	0.00	107.46	0.00	0.00	5.49	0.00	0.00	101.98
52+00.00	TO	52+18.16	0.00	0.00	21.70	0.00	0.00	4.36	0.00	0.00	18.45	0.00	0.00	2.41	0.00	0.00	16.04
52+18.16	TO	52+40.59	0.00	0.00	26.27	0.00	0.00	4.22	0.00	0.00	22.33	0.00	0.00	1.86	0.00	0.00	20.47
52+40.59	TO	52+79.93	0.00	0.00	23.13	0.00	0.00	3.45	0.00	0.00	19.66	0.00	0.00	1.36	0.00	0.00	18.30
52+79.93	TO	53+19.22	0.00	0.00	23.21	0.00	0.00	3.94	0.00	0.00	19.73	0.00	0.00	1.19	0.00	0.00	18.54
53+19.22	TO	54+00.00	0.00	0.00	91.57	0.00	0.00	17.92	0.00	0.00	77.84	0.00	0.00	4.33	0.00	0.00	73.51
54+00.00	TO	54+86.37	0.00	0.00	86.02	0.00	0.00	28.38	0.00	0.00	73.12	0.00	0.00	14.36	0.00	0.00	58.75
54+86.37	TO	55+00.00	0.00	0.00	12.05	0.00	0.00	5.57	0.00	0.00	10.24	0.00	0.00	3.56	0.00	0.00	6.68
55+00.00	TO	56+00.00	0.00	0.00	77.37	0.00	0.00	34.38	0.00	0.00	65.76	0.00	0.00	14.89	0.00	0.00	50.88
56+00.00	TO	56+13.81	0.00	0.00	9.30	0.00	0.00	3.75	0.00	0.00	7.90	0.00	0.00	0.79	0.00	0.00	7.11
56+13.81	TO	56+60.66	0.00	0.00	15.46	0.00	0.00	6.08	0.00	0.00	13.15	0.00	0.00	1.26	0.00	0.00	11.88
56+60.66	TO	57+00.00	0.00	0.00	12.90	0.00	0.00	7.01	0.00	0.00	10.97	0.00	0.00	0.00	0.00	0.00	10.97
57+00.00	TO	57+51.37	0.00	0.00	32.98	0.00	0.00	17.01	0.00	0.00	28.03	0.00	0.00	0.00	0.00	0.00	28.03
TOTALS =			0.00	0.00	558.40	0.00	0.00	164.98	0.00	0.00	474.64	0.00	0.00	51.51	0.00	0.00	423.13

EARTH EXCAVATION = 558 CU YD
FURNISHED EXCAVATION = 423 CU YD
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL = 165 CU YD

Q:\MCDOT\2010\Drawings\RDWY\shde\rd\31.Earth.Sched.01.dgn