

BIKE PATH EARTHWORK			EARTH EXCAVATION (CUT) (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL) (CU YD)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)			EMBANKMENT (FILL) (CU YD)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)		
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
12+00.00	TO	13+00.00	0.00	0.00	185.73	0.00	0.00	106.35	0.00	0.00	157.87	0.00	0.00	102.56	0.00	0.00	55.32
13+00.00	TO	14+00.00	0.00	0.00	42.55	0.00	0.00	95.89	0.00	0.00	36.17	0.00	0.00	183.25	0.00	0.00	-147.08
14+00.00	TO	15+00.00	0.00	0.00	171.98	0.00	0.00	110.93	0.00	0.00	146.18	0.00	0.00	104.92	0.00	0.00	41.26
15+00.00	TO	16+00.00	0.00	0.00	296.13	0.00	0.00	133.63	0.00	0.00	251.71	0.00	0.00	86.69	0.00	0.00	165.02
16+00.00	TO	17+00.00	0.00	0.00	153.11	0.00	0.00	141.78	0.00	0.00	130.14	0.00	0.00	615.55	0.00	0.00	-485.40
17+00.00	TO	17+50.00	0.00	0.00	0.00	0.00	0.00	78.70	0.00	0.00	0.00	0.00	0.00	766.53	0.00	0.00	-766.53
17+50.00	TO	18+00.00	0.00	0.00	0.00	0.00	0.00	93.66	0.00	0.00	0.00	0.00	0.00	1184.01	0.00	0.00	-1184.01
18+00.00	TO	18+25.00	0.00	0.00	0.00	0.00	0.00	49.89	0.00	0.00	0.00	0.00	0.00	756.56	0.00	0.00	-756.56
18+25.00	TO	18+50.00	0.00	0.00	0.00	0.00	0.00	49.35	0.00	0.00	0.00	0.00	0.00	859.25	0.00	0.00	-859.25
18+50.00	TO	18+80.00	0.00	0.00	0.00	0.00	0.00	58.10	0.00	0.00	0.00	0.00	0.00	1149.61	0.00	0.00	-1149.61
PEDESTRIAN BRIDGE																	
21+70.00	TO	22+00.00	0.00	0.00	0.00	0.00	0.00	53.96	0.00	0.00	0.00	0.00	0.00	975.78	0.00	0.00	-975.78
22+00.00	TO	22+25.00	0.00	0.00	0.00	0.00	0.00	44.36	0.00	0.00	0.00	0.00	0.00	702.92	0.00	0.00	-702.92
22+25.00	TO	22+50.00	0.00	0.00	0.00	0.00	0.00	42.90	0.00	0.00	0.00	0.00	0.00	600.95	0.00	0.00	-600.95
22+50.00	TO	23+00.00	0.00	0.00	0.00	0.00	0.00	77.28	0.00	0.00	0.00	0.00	0.00	904.38	0.00	0.00	-904.38
23+00.00	TO	23+50.00	0.00	0.00	0.00	0.00	0.00	63.83	0.00	0.00	0.00	0.00	0.00	557.24	0.00	0.00	-557.24
23+50.00	TO	24+00.00	0.00	0.00	0.00	0.00	0.00	51.35	0.00	0.00	0.00	0.00	0.00	298.59	0.00	0.00	-298.59
24+00.00	TO	26+00.00	0.00	0.00	174.06	0.00	0.00	183.85	0.00	0.00	147.95	0.00	0.00	384.85	0.00	0.00	-236.90
26+00.00	TO	27+00.00	0.00	0.00	164.26	0.00	0.00	89.94	0.00	0.00	139.62	0.00	0.00	0.00	0.00	0.00	139.62
27+00.00	TO	28+00.00	0.00	0.00	166.33	0.00	0.00	88.93	0.00	0.00	141.38	0.00	0.00	0.00	0.00	0.00	141.38
28+00.00	TO	29+00.00	0.00	0.00	135.60	0.00	0.00	77.20	0.00	0.00	115.26	0.00	0.00	0.00	0.00	0.00	115.26
TOTALS =			0.00	0.00	1489.75	0.00	0.00	1691.88	0.00	0.00	1266.28	0.00	0.00	10233.62	0.00	0.00	-8967.33

EARTH EXCAVATION = 1490 CU YD
FURNISHED EXCAVATION = 8967 CU YD
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL = 1692 CU YD

Q:\MCDOT\2010\Drawings\RDHW\shits\rd\15.Earth_Sched_01.dgn