

SIGNING SCHEDULE										
SIGN INFORMATION					NEW SIGN PANELS		NEW SIGN PANELS		METAL POST	CAST IRON BASE
STATION	LOCATION	OFFSET		SIGN NUMBER	WIDTH (FT)	HEIGHT (FT)	(72000105)	(72000205)	(72800105)	(73100110)
		LT	RT				SIGN PANEL	SIGN PANEL	TELESCOPING STEEL	BASE FOR TELESCOPING
							TYPE 1, SPECIAL (SQ. FT.)	TYPE 2, SPECIAL (SQ. FT.)	SIGN SUPPORT, SPECIAL (L.F.)	SIGN SUPPORT, SPECIAL (EACH)
77+99	RAKOW ROAD	LT		7	2.50	3.00	7.50		11	1
89+06	RAKOW ROAD	LT		7	2.50	3.00	7.50		11	1
91+98	RAKOW ROAD	RT		30	7.00	2.50		17.50	11.5	1
92+19	RAKOW ROAD	LT		12	2.50	2.50	6.25		11.5	1
92+96	RAKOW ROAD	RT		71	6.00	1.50	9.00		9.5	1
93+79	RAKOW ROAD	RT		43	1.75	1.25	2.19		13.5	1
93+79	RAKOW ROAD	RT		50	2.00	2.00	4.00			
93+79	RAKOW ROAD	RT		51	3.00	0.75	2.25			
93+79	RAKOW ROAD	RT		38	1.75	1.25	2.19			
95+28	RAKOW ROAD	LT		10	2.50	2.50	6.25		10.5	1
96+98	RAKOW ROAD	RT		7	2.50	3.00	7.50		11	1
97+12	RAKOW ROAD	LT		12	2.50	2.50	6.25		10.5	1
98+38	RAKOW ROAD	LT		46	2.00	2.00	4.00		10	1
98+84	RAKOW ROAD	RT		50	2.00	2.00	4.00		12	1
98+84	RAKOW ROAD	RT		51	3.00	0.75	2.25			
98+84	RAKOW ROAD	RT		36	1.75	1.25	2.19			
99+10	RAKOW ROAD	LT		4	2.00	2.50	5.00		10.5	1
99+25	RAKOW ROAD	LT		10	2.50	2.50	6.25		10.5	1
99+25	RAKOW ROAD	LT		34	2.00	2.50	5.00			
100+90	RAKOW ROAD	RT		34	2.00	2.50	5.00		10.5	1
101+00	RAKOW ROAD	LT		50	2.00	2.00	4.00		12	1
101+00	RAKOW ROAD	LT		51	3.00	0.75	2.25			
101+00	RAKOW ROAD	LT		37	1.75	1.25	2.19			
102+31	RAKOW ROAD	RT		8	2.50	3.00	7.50		11	1
102+34	RAKOW ROAD	RT		30	7.00	2.50		17.50	10.5	1
104+07	RAKOW ROAD	RT		53	2.50	3.00	7.50		12.5	1
104+07	RAKOW ROAD	RT		59	2.50	1.50	3.75			
104+26	RAKOW ROAD	LT		10	2.50	2.50	6.25		10.5	1
105+06	RAKOW ROAD	RT		72	6.00	1.50	9.00		9.5	1
105+31	RAKOW ROAD	LT		43	1.75	1.25	2.19		13.25	1
105+31	RAKOW ROAD	LT		50	2.00	2.00	4.00			
105+31	RAKOW ROAD	LT		51	3.00	0.75	2.25			
105+31	RAKOW ROAD	LT		39	1.75	1.25	2.19			
105+98	RAKOW ROAD	LT		71	6.00	1.50	9.00		9.5	1
106+15	RAKOW ROAD	LT		53	2.50	3.00	7.50		12.5	1
106+15	RAKOW ROAD	LT		59	2.50	1.50	3.75			
106+17	RAKOW ROAD	RT		7	2.50	3.00	7.50		11	1
106+88	RAKOW ROAD	LT		26	6.00	2.50		15.00	10.5	1
107+82	RAKOW ROAD	LT		31	2.00	2.50	5.00		10.5	1
108+06	RAKOW ROAD	RT		70	4.00	2.00	8.00		10	1
108+16	RAKOW ROAD	LT		10	2.50	2.50	6.25		10.5	1
108+16	RAKOW ROAD	LT		34	2.00	2.50	5.00			
109+68	RAKOW ROAD	RT		34	2.00	2.50	5.00		10.5	1
109+95	RAKOW ROAD	LT		69	4.00	2.00	8.00		10	1
110+53	RAKOW ROAD	RT		63	2.50	2.50	6.25		12.5	1
110+53	RAKOW ROAD	RT		64	1.50	2.00	3.00			
111+69	RAKOW ROAD	RT		8	2.50	3.00	7.50		11	1
111+70	RAKOW ROAD	LT		7	2.50	3.00	7.50		11	1
113+19	RAKOW ROAD	LT		72	6.00	1.50	9.00		9.5	1
114+68	RAKOW ROAD	RT		4	2.00	2.50	5.00		10.5	1
114+82	RAKOW ROAD	LT		26	6.00	2.50		15.00	10.5	1
116+55	RAKOW ROAD	RT		53	2.50	3.00	7.50		12.5	1
116+55	RAKOW ROAD	RT		58	2.50	1.50	3.75			
117+32	RAKOW ROAD	RT		49	2.00	2.00	4.00		10	1
134+82	RAKOW ROAD	RT		4	2.00	2.50	5.00		10.5	1
135+61	RAKOW ROAD	LT		4	2.00	2.50	5.00		10.5	1
141+26	RAKOW ROAD	RT		63	2.50	2.50	6.25		12.5	1
141+26	RAKOW ROAD	RT		64	1.50	2.00	3.00			
141+31	RAKOW ROAD	LT		63	2.50	2.50	6.25		12.5	1
141+31	RAKOW ROAD	LT		64	1.50	2.00	3.00			
154+59	RAKOW ROAD	RT		4	2.00	2.50	5.00		10.5	1
155+48	RAKOW ROAD	LT		11	2.50	2.50	6.25		10.5	1
156+06	RAKOW ROAD	RT		4	2.00	2.50	5.00		10.5	1
159+49	RAKOW ROAD	LT		11	2.50	2.50	6.25		10.5	1
162+74	RAKOW ROAD	RT		29	6.00	2.50		15.00	10.5	1
163+45	RAKOW ROAD	LT		63	2.50	2.50	6.25		12.5	1
163+45	RAKOW ROAD	LT		64	1.50	2.00	3.00			
163+83	RAKOW ROAD	RT		74	5.00	1.50	7.50		9.5	1
164+68	RAKOW ROAD	RT		7	2.50	3.00	7.50		11	1
164+72	RAKOW ROAD	LT		10	2.50	2.50	6.25		10.5	1
166+50	RAKOW ROAD	LT		53	2.50	3.00	7.50		12.5	1
166+50	RAKOW ROAD	LT		58	2.50	1.50	3.75			
SUB TOTALS							358.88	80.00	569.75	52



USER NAME = Rdwj.Lisle
 PLOT CONFIG = PDF(Grey, Large).plt
 PLOT SCALE = 1:500
 PLOT DATE = 7/29/2010

DESIGNED - EJB
 DRAWN - TCK
 CHECKED - JAH
 DATE - 8/2/2010



MCHENRY COUNTY
DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31
PROPOSED SIGNING SCHEDULE

SCALE: 1"=50'
 SHEET NO. PMK 18 OF 21

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0336	05-00308-00-WR	MCHENRY	606	285
CONTRACT NO. 63398				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

GA:\MCDOT\22950_001\Drawings\RDW\shas\Strp\AS_SignSched_01.dgn