

SIGNING SCHEDULE										
SIGN INFORMATION						NEW SIGN PANELS	NEW SIGN PANELS	METAL POST	CAST IRON BASE	
STATION	LOCATION	OFFSET		SIGN NUMBER	WIDTH (FT)	HEIGHT (FT)	(72000105)	(72000205)	(72800105)	(73100110)
		LT	RT				SIGN PANEL	SIGN PANEL	TELESCOPING STEEL	BASE FOR TELESCOPING
						TYPE 1, SPECIAL (SQ. FT.)	TYPE 2, SPECIAL (SQ. FT.)	SIGN SUPPORT, SPECIAL (L.F.)	SIGN SUPPORT, SPECIAL (EACH)	
15+45	McHENRY AVE.	LT		2	2.00	2.50	5.00		10.5	1
16+72	McHENRY AVE.	LT		8	2.50	3.00	7.50		11	1
16+88	McHENRY AVE.	RT		20	2.50	2.50	6.25		12	1
16+88	McHENRY AVE.	RT		21	2.00	1.50	3.00			
19+09	McHENRY AVE.	RT		31	2.00	2.50	5.00		10.5	1
19+14	McHENRY AVE.	LT		8	2.50	3.00	7.50		11	1
44+50	PYOTT ROAD	RT		75	5.00	1.50	7.50		9.5	1
45+43	PYOTT ROAD	RT		25	5.00	2.50		12.50	10.5	1
46+23	PYOTT ROAD	LT		16	2.50	3.00	7.50		11.5	1
46+23	PYOTT ROAD	LT		17	2.50	0.50	1.25			
47+00	PYOTT ROAD	LT		47	2.00	2.00	4.00		11	1
47+00	PYOTT ROAD	RT		7	2.50	3.00	7.50			
47+79	PYOTT ROAD	RT		1	2.50	2.50	6.25		10.5	1
47+86	PYOTT ROAD	LT		53	2.50	3.00	7.50		12.5	1
47+86	PYOTT ROAD	LT		54	2.50	1.50	3.75			
48+48	PYOTT ROAD	LT		12	2.50	2.50	6.25		10.5	1
48+71	PYOTT ROAD	LT		33	3.00	3.00	9.00		11	1
50+92	PYOTT ROAD	LT		23	3.00	3.00	9.00		11	1
51+06	PYOTT ROAD	RT		33	3.00	3.00	9.00		11	1
53+02	PYOTT ROAD	RT		53	2.50	3.00	7.50		12.5	1
53+02	PYOTT ROAD	RT		62	2.50	1.50	3.75			
53+12	PYOTT ROAD	LT		1	2.50	2.50	6.25		10.5	1
53+70	PYOTT ROAD	LT		79	5.00	1.50	7.50		9.5	1
53+84	PYOTT ROAD	LT		25	5.00	2.50		12.50	13	1
53+84	PYOTT ROAD	LT		95	2.00	2.50	5.00			
54+67	PYOTT ROAD	RT		47	2.00	2.00	4.00		10	1
54+98	PYOTT ROAD	LT		75	5.00	1.50	7.50		9.5	1
55+55	PYOTT ROAD	LT		66	4.00	1.50	6.00		11.5	1
55+55	PYOTT ROAD	LT		91	1.50	2.00	3.00			
43+79	VIRGINIA ROAD	RT		75	5.00	1.50	7.50		9.5	1
45+50	VIRGINIA ROAD	LT		48	2.00	2.00	4.00		10	1
47+07	VIRGINIA ROAD	LT		53	2.50	3.00	7.50		12.5	1
47+07	VIRGINIA ROAD	LT		55	2.50	1.50	3.75			
48+90	VIRGINIA ROAD	LT		33	3.00	3.00	9.00		11	1
51+08	VIRGINIA ROAD	RT		33	3.00	3.00	9.00		11	1
51+60	VIRGINIA ROAD	RT		3	2.00	2.50	5.00		10.5	1
51+78	VIRGINIA ROAD	LT		14	2.00	2.50	5.00		10.5	1
52+46	VIRGINIA ROAD	RT		53	2.50	3.00	7.50		12.5	1
52+46	VIRGINIA ROAD	RT		62	2.50	1.50	3.75			
53+56	VIRGINIA ROAD	RT		48	2.00	2.00	4.00		10	1
54+31	VIRGINIA ROAD	RT		13	2.00	2.50	5.00		10.5	1
54+52	VIRGINIA ROAD	LT		75	5.00	1.50	7.50		9.5	1
54+95	VIRGINIA ROAD	LT		1	2.50	2.50	6.25		10.5	1
55+22	VIRGINIA ROAD	RT		15	2.00	2.50	5.00		10.5	1
55+65	VIRGINIA ROAD	RT		1	2.50	2.50	6.25		10.5	1
57+93	VIRGINIA ROAD	LT		90	2.00	0.50	1.00		11.5	1
57+93	VIRGINIA ROAD	LT		82	2.00	0.50	1.00			
21+17	PINGREE ROAD	RT		33	3.00	3.00	9.00		11	1
24+13	PINGREE ROAD	RT		32	2.00	2.00	4.00		10	1
24+45	PINGREE ROAD	RT		87	2.00	0.50	1.00		14.5	1
24+45	PINGREE ROAD	RT		83	2.00	0.50	1.00			
24+45	PINGREE ROAD	RT		1	2.50	2.50	6.25			
24+45	PINGREE ROAD	RT		7	2.50	3.00	7.50			
24+90	PINGREE ROAD	LT		7	2.50	3.00	7.50		11	1
25+88	PINGREE ROAD	LT		75	5.00	1.50	7.50		9.5	1
29+69	PINGREE ROAD	LT		24	4.00	2.50	10.00		10.5	1
52+11	IL ROUTE 31	LT		49	2.00	2.00	4.00		11.75	1
52+11	IL ROUTE 31	LT		88	2.00	0.50	1.00			
52+11	IL ROUTE 31	LT		37	1.75	1.25	2.19			
54+42	IL ROUTE 31	LT		43	1.75	1.25	2.19		15.5	1
54+42	IL ROUTE 31	LT		49	2.00	2.00	4.00			
54+42	IL ROUTE 31	LT		88	2.00	0.50	1.00			
54+42	IL ROUTE 31	LT		39	1.75	1.25	2.19			
54+86	IL ROUTE 31	LT		7	2.50	3.00	7.50		11	1
55+84	IL ROUTE 31	LT		75	5.00	1.50	7.50		9.5	1
SUB TOTALS						346.56	25.00	515.25	47	
TOTALS						1,427	239	2,256	206	

***NOTES**
1. ALL SIGNS REMOVED SHALL BE RETURNED TO THE MCDOT SIGN SHOP.
2. ALL SIGNS OVER 12.0 SQ. FT. ARE TYPE 2 (SPECIAL).



USER NAME = Rdwj.Lisle
PLOT CONFIG = PDF(Grey, Large).plt
PLOT SCALE = 1:50
PLOT DATE = 7/29/2010

DESIGNED - EJB
DRAWN - TCK
CHECKED - JAH
DATE - 8/2/2010

REVISED -
REVISED -
REVISED -
REVISED -



MCHENRY COUNTY
DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31
PROPOSED SIGNING SCHEDULE
SCALE: 1"=50' SHEET NO. PMK 21 OF 21

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0336	05-00308-00-WR	MCHENRY	606	288
CONTRACT NO. 63398				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				