

CODE #	DESCRIPTION	UNIT	QUANTITY
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1320
81019100	CONDUIT PUSHED, 6" DIA., GALVANIZED STEEL	FOOT	280
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	15
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30
	UNIT DUCT, WITH 3-1/C NO.1/0 AND 1/C NO. 2 GROUND, 600V (EPR-TYPE RHW), 2" DIA., POLYETHYLENE	FOOT	6700
X0325254	UNIT DUCT WITH 3-1/C NO. 1 AND 1/C NO.1 GROUND, 600V (EPR-TYPE RHW), 2" DIAMETER SCHEDULE 40 POLYETHYLENE	FOOT	17200
XX007614	UNIT DUCT, 600 V, 3-1C NO. 8, 1/C NO. 8 GROUND, 1" DIA. POLYETHYLENE	FOOT	2300
X0322925	ELCBL C TRACER 14 1C	FOOT	26200
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	100
81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	300
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	24650
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	14
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	140
	LUMINAIRE SHIELDS	EACH	38
X8250400	LIGHTING CONTROLLER, PEDESTAL MOUNT	EACH	1
X8250085	LIGHTING CONTROLLER, DUPLEX CONSOLE TYPE	EACH	2
83008600	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. MAST ARM	EACH	123
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15" BOLT CIRCLE	EACH	123
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	123
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	38
84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	38
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1



USER NAME = tkoeppen(Rdwy.Lisle)
PLOT CONFIG= PDF(Greg.Large).plt
PLOT SCALE = 1:50
PLOT DATE = 7/29/2010

DESIGNED - CMH
DRAWN - MJP
CHECKED - DH
DATE - 8/2/2010

REVISED -
REVISED -
REVISED -
REVISED -



MCHENRY COUNTY
DIVISION OF TRANSPORTATION

RAKOW ROAD FROM ACKMAN ROAD TO ILLINOIS ROUTE 31
LIGHTING SCHEDULE AND SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. LT 2 OF 28 STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0336	05-00308-00-WR	MCHENRY	606	376
			CONTRACT NO. 63398	
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				