

SUMMARY OF QUANTITIES				IL RTE 132 (GRAND AVE) AT IL RTE 131 (GREEN BAY ROAD)	GRAND AVENUE AT BALDWIN AVENUE	GRAND AVENUE AT McAREE ROAD	GRAND AVENUE AT LEWIS AVENUE	GRAND AVENUE AT BUTTRICK STREET	GRAND AVENUE AT JACKSON STREET	GRAND AVENUE AT WEST STREET	GRAND AVENUE AT COUNTY STREET	GRAND AVENUE AT GENESEE STREET	GRAND AVENUE AT SHERIDAN ROAD	GRAND AVENUE AT ROBERT McCLORY BIKE PATH	INTERCONNECT IL RTE 131 (GREEN BAY RD) TO SHERIDAN RD
				CONSTRUCTION CODES											
NO.	CODE NO.	ITEM	UNIT	TOTAL	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F
86.	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1											
87.	X0325462	MEDIA CONVERTER	EACH	3		1	1								1
88.	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	8		1	1								
89.	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	7				1		1			1		
90.	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	8		1	1			1			1		
91.	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	8		1	1			1			1		
92.	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1/C	FOOT	4,412		417	568	600	473	467	506	734	647		
93.	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	3,268		260	548	477	363	463	359	511	287		
94.	XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	400								200	200		
95.	XX003661	ELECTRIC CABLE IN CONDUIT, COAXIAL	FOOT	1,029			235	174		102	184	109	225		
96.	XX005929	TRAFFIC SIGNAL POST, 14 FOOT, (SPECIAL)	EACH	12		2						4			
97.	XX005931	TRAFFIC SIGNAL POST, 16 FOOT, (SPECIAL)	EACH	17		2								2	
98.	XX005937	LED INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	32		4	4	4	4	4		4	4		
99.	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	EACH	6			1	1	1	1		1			
100.	XX006655	LAYER II (DATA LINK) SWITCH	EACH	6			1	1	1	1		1			
101.	XX007017	TERMINATE FIBER IN CABINET	EACH	12											12
102.	XX007021	PEDESTRIAN ACTIVATED CROSSWALK WARNING SYSTEM	EACH	2										2	
103.	XX008246	FIBER OPTIC CABLE IN CONDUIT, 24 SINGLEMODE	FOOT	15,735											15,735
104.	XX008253	VIDEO ENCODER	EACH	6			1	1	1	1		1			
105.	Z0076600	TRANEES	HOUR	1,000											

* SPECIALTY ITEM
 Δ Y080

SPECIAL CONDITIONS FOR CONSTRUCTION WITHIN A LAKE COUNTY HIGHWAY RIGHT-OF-WAY

SPECIAL CONDITIONS FOR CONSTRUCTION WITHIN A LAKE COUNTY HIGHWAY RIGHT-OF-WAY (CONTD)

Work Notification
 Prior to starting construction, the Lake County Maintenance Section, 847-362-3960, and the Lake County Permit Section, 847-362-3950, shall be called and given the construction start date.

Signaling
 The construction and restoration methods and procedures, materials used and construction signing and traffic control shall, when applicable, conform to meet the standards and requirements set forth in the current "Manual on Uniform Traffic Control Devices for Street and Highways", "Standard Specifications for Road and Bridge Construction", "Standard Specification for Traffic Control Items", and the "Highway Standards" manual as published or adopted by the Illinois Department of Transportation.

Field Changes for Watermain or Sewer Location
 No changes to the depth or location of the watermain or sewer as shown on these plans due to unforeseen field conditions or conflicts can be made unless prior approval has been obtained from the Permit Section of the Lake County Division of Transportation.

Additions, Extensions or Deletions for the Watermain or Sewer
 No additions, extensions or deletions can be made to the watermain or sewer as shown on these plans unless prior approval has been obtained from the Permit Section of the Lake County Division of Transportation.

Hazards to the Public
 Measures shall be taken to prevent or protect the public from hazards caused by the construction operations.

Parking of Vehicles, Equipment and Storage of Materials
 Construction worker's vehicles and construction equipment shall be parked in areas outside of the County or State Highway right-of-way or in areas where there will be no interference with the normal use of the highway or vehicle sight distance. Construction materials shall be located at least 12 feet from a through traffic lane or outside of the County or State Highway right-of-way.

Maintaining Existing Traffic Control Devices
 Existing traffic control devices that are removed shall be re-erected as soon as possible in accordance with Article 107.25. Damaged or lost traffic control signs shall be reported to the Sign Shop, 847-362-3962 of the Lake County Division of Transportation or the IDOT Traffic Control Supervisor at 847-705-4470 for replacement.

Regulatory and warning traffic signs shall be kept in view of the highway traffic.

Existing Drainage and Access
 Disturbed highway drainage facilities shall be re-established at the close of each workday. Occupants of adjacent properties having access to the County Highway shall be notified prior to being blocked and suitable arrangements made with the occupants. Adjacent property access shall be re-established as soon as possible.

Highway Pavements
 Care shall be taken not to break, crack or damage the highway pavement with equipment operating on it. Also, all dirt or debris tracked onto the highway pavement shall be removed. Equipment with grozer pads, cleats or studs are not permitted to operate on the highway pavement.

If, due to construction operations, the highway pavement becomes damaged or undermined, all construction work in that area shall be stopped and the highway pavement repaired as directed by the engineer. Alternate construction measures shall then be used to prevent further highway pavement damage.

Excavations, Trenches and Bore Pits
 Excavated material shall, when practical, be piled on the near traffic side of the excavation, trench or bore pit. Open excavations, trenches or bore pits remaining after working hours shall not exceed 50 feet in length and shall be properly protected (fencing, covered, etc.) and marked (Type I or II barricades). If barricades are used in series, only steady burning lights shall be used. Bore pits shall be located no closer than 10 feet to the highway pavement, back of curb or gutter, or shoulder break line, whichever is further. If casing pipes are used, the voids in the casing pipe shall be filled and/or the ends sealed so there will be no siltation into the casing pipe.

Manholes, Valves, Valve Vaults and Appurtenances
 The top of the frame and lid or cover of a manhole, valve, or valve vault shall be flush and contoured to the surrounding ground. If this is not possible due to an excessive slope, the surrounding ground shall be graded or the frame and lid or cover partially buried to provide for a gradual transition slope so the area can be safely mowed and no hazard to the public will result. The top of the frame and lid or cover that is located within the gravel shoulder shall have a asphalt apron installed around the frame or cover as directed by the Lake County Division of Transportation. Any frame and lid or cover located in a paved area shall be contoured and 1/4 inch below the surface of the surrounding pavement. The top of frame and lid or cover shall not be located within the area of 2.5 feet to 30.5 feet from the highway pavement centerline.

Surface appurtenances that extend above the surrounding ground surface shall be located within two feet of the County or State Highway right-of-way.

Tile Lines and Storm Sewers
 Existing tile lines and storm sewers that are encountered during construction operations shall be replaced if broken with like size and kind of material. The line and storm sewer crossings of the excavation shall be bridged with rigid materials such as wood or steel. The location and depth of any encountered tile lines and storm sewers shall be recorded and a copy given to the engineer.

Winter Construction Work
 Snow and ice removal operations of the Lake County Division of Transportation or Illinois Department of Transportation shall have precedence over the construction operations. A 12 foot wide (minimum) clear area from the highway pavement edge shall be maintained for the roadside storage of snow and ice. No construction equipment or materials shall be stored in this 12 foot wide (minimum) clear area nor shall any piles of dirt or excavated materials be left in this area.

Restoration and Clean-Up
 The area of the County or State Highway right-of-way disturbed by construction operations shall be kept to a minimum and shall be restored as promptly as weather and soil conditions permit. If restoration is not accomplished voluntarily, the Lake County Division of Transportation or Illinois Department of Transportation may set a final date for the completion of the restoration work.

Turf areas of the right-of-way disturbed by construction operations shall be compacted and regraded to an equal or better condition than existed before construction. Sod shall be used in high erosion areas. This restoration work will not be considered completed until the turf cover is established.

Gravel and paved shoulders that are damaged shall be replaced as directed by the Lake County Division of Transportation. Driveways, side roads and other accesses, which are damaged, shall be restored with similar materials and thickness. The edges of excavated paved surfaces shall be sawcut prior to repair. Culverts, storm sewer systems and other drainage facilities including ditches lines shall be cleared of siltation and debris due to the construction operations. Other areas of the right-of-way that have been disturbed such as curb and gutters shall be restored with similar materials.

Any damaged property of the County of Lake, its Division of Transportation or Illinois Department of Transportation, or of others (including utility companies) shall be repaired or replaced or the owner of the damaged property reimbursed for the costs of repairing the damaged property by the owner.

Restoration Guarantee
 Any restoration work that falls within one year of completion shall be redone. Also, any settlement that occurs within one year of completion of the surface restoration work shall be filled and the surface area restored.

Keeping Roads Open to Traffic
 All roads shall remain open to traffic. The Contractor may close one lane because of construction only between the hours of 9:00 A.M. and 3:00 P.M. The Contractor shall maintain traffic during these restricted hours as shown on the Traffic Control Standards. Two lanes of traffic will be maintained between 3:00 P.M. and 9:00 A.M. and when no construction activities are being carried out. Traffic routed around construction areas shall be over paved surfaces and not over gravel shoulders.

LDOT GENERAL NOTES
 BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED).

10 FEET (3 METER) TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS & GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF WAUKEGAN.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE II BARRICADE USED—ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS
HMA PAVEMENTS - RESURFACING
 1/4" HMA SURFACE COURSE, MIX "C", N50 (IL 9.5mm); VOIDS OF 4% @ 50 GYR
 HMA BINDER COURSE, IL 19.0, N50; VOIDS OF 4% @ 50 GYR
HMA PAVEMENTS - DRIVEWAY PAVEMENT
 HMA SURFACE COURSE, MIX "C", N50 (IL-9.5mm); VOIDS OF 4% @ 50 GYR
 HMA BASE COURSE, 3" (IL-19 mm); VOIDS OF 4% @ 50 GYR
HMA PAVEMENTS - CLASS D PATCHING
 CLASS D PATCHES, TYPE I-IV, 6" (HMA BINDER IL-19 mm); VOIDS OF 4% @ 70 GYR

* The unit weight used to calculate all hot-mix asphalt surface mix quantities is 112 LB/SY/IN

** At the Engineer's discretion, use of surface and binder N30 L (Low ESAL) for ADT <700 and 10% trucks or less (3% Air Voids @ 30 GYR) may be allowed.

HMA the "AC Type" shall be "PG 62 - 22" unless modified by District One special provisions.

For percent of RCP see District One special provisions.

GENERAL NOTES

- A-1. THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" LATEST EDITION, THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS" LATEST EDITION, PROJECT SPECIFICATIONS, ALL APPLICABLE REQUIREMENTS OF THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, THE CITY OF WAUKEGAN, LAKE COUNTY DIVISION OF TRANSPORTATION, ALL APPLICABLE REQUIREMENTS OF THE ORDINANCES OF AUTHORITIES HAVING JURISDICTION AND ALL ADDENDA THERETO SHALL GOVERN THIS WORK.
- A-2. THE STANDARD SPECIFICATIONS, PROJECT SPECIFICATIONS, CONSTRUCTION PLANS AND SUBSEQUENT DETAILS ARE ALL TO BE CONSIDERED AS PART OF THE CONTRACT. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED A PART OF THE CONTRACT.
- A-3. NO CONSTRUCTION PLANS SHALL BE USED FOR CONSTRUCTION UNLESS SPECIFICALLY MARKED "FOR CONSTRUCTION". PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THEIR WORK WITH THE ACTUAL CONDITIONS AT THE JOB SITE. IN ADDITION, THE CONTRACTOR MUST VERIFY THE ENGINEER'S LINE AND GRADES. IF THERE ARE ANY DISCREPANCIES FROM WHAT IS SHOWN ON THE CONSTRUCTION PLANS, STANDARD SPECIFICATIONS AND/OR SPECIAL DETAILS, THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTION FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSION OR DISCREPANCIES. FAILING TO SECURE SUCH INSTRUCTION, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT HIS OWN RISK AND EXPENSE. IN THE EVENT OF ANY DOUBT OR QUESTION ARISING WITH RESPECT TO THE TRUE MEANING OF THE CONSTRUCTION PLANS OR SPECIFICATIONS, THE DECISION OF THE RESIDENT ENGINEER SHALL BE FINAL AND CONCLUSIVE.
- A-4. BEFORE ACCEPTANCE BY THE OWNER AND FINAL PAYMENT, ALL WORK SHALL BE INSPECTED AND APPROVED BY THE OWNER OR HIS REPRESENTATIVES. FINAL PAYMENT WILL BE MADE AFTER ALL OF THE CONTRACTOR'S WORK HAS BEEN APPROVED AND ACCEPTED.
- A-5. WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OR UNSUITABLE MATERIALS CREATED AS A RESULT THEREOF.
- A-6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.
- A-7. DURING CONSTRUCTION OPERATIONS THE CONTRACTOR SHALL ENSURE POSITIVE SITE DRAINAGE AT THE CONCLUSION OF EACH DAY. SITE DRAINAGE MAY BE ACHIEVED BY DITCHING, PUMPING OR ANY OTHER METHOD ACCEPTABLE TO THE ENGINEER AND THE CITY.
- A-8. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REMOVE FROM THE SITE ANY AND ALL MATERIALS AND DEBRIS WHICH RESULT FROM HIS CONSTRUCTION OPERATIONS AT NO ADDITIONAL EXPENSE TO THE OWNER.
- A-9. CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.
- A-10. EXISTING UTILITIES: WHEN THE PLANS OR SPECIAL PROVISIONS INCLUDE INFORMATION PERTAINING TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES, SUCH INFORMATION REPRESENTS ONLY THE OPINION OF THE ENGINEER AS TO THE LOCATION OF SUCH UTILITIES AND IS ONLY INCLUDED FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER AND OWNER ASSUME NO RESPONSIBILITY WHATSOEVER IN RESPECT TO THE SUFFICIENCY OR ACCURACY OF THE INFORMATION SHOWN ON THE PLANS RELATIVE TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES OR THE MANNER IN WHICH THEY ARE TO BE REMOVED OR ADJUSTED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH UTILITIES. HE SHALL ALSO OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES, J.U.L.I.E., DETAILED INFORMATION RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULES OF THE UTILITY COMPANIES FOR REMOVING OR ADJUSTING THEM.
- A-11. THE CITY OF WAUKEGAN SHOULD BE CONTACTED 48 HOURS PRIOR TO THE START OF ANY EXCAVATION. (847-625-6827)
- A-12. AGGREGATE SPECIFIED ON THESE PLANS SHALL BE CONSIDERED CRUSHED STONE MEETING THE GRADATION SPECIFIED. CRUSHED CONCRETE MAY NOT BE SUBSTITUTED FOR CRUSHED STONE, UNLESS APPROVED BY THE RESIDENT ENGINEER.

- A-13. EASEMENTS FOR THE EXISTING UTILITIES, BOTH PUBLIC AND PRIVATE, AND UTILITIES WITHIN PUBLIC RIGHTS-OF-WAY ARE SHOWN ON THE PLANS ACCORDING TO AVAILABLE RECORDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION IN THE FIELD OF THESE UTILITY LINES AND THEIR PROTECTION FROM DAMAGE DUE TO CONSTRUCTION OPERATIONS. IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED WHICH CONFLICT IN LOCATION WITH NEW CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER SO THAT THE CONFLICT MAY BE RESOLVED.
- A-14. REMOVED PAVEMENT, SIDEWALK, CURB AND GUTTER, ETC. SHALL BE DISPOSED OF OFFSITE AT LOCATIONS PROVIDED BY THE CONTRACTOR AT HIS EXPENSE.
- A-15. ALL PROPOSED SIDEWALK REMOVAL, COMBINATION CURB AND GUTTER REMOVAL, PCC SIDEWALK, 5" AND COMBINATION CONCRETE CURB AND GUTTER B6.12 OR B6.24 IDENTIFIED ON THE TEMPORARY TRAFFIC SIGNAL INSTALLATION OR THE TRAFFIC SIGNAL MODERNIZATION PLANS SHALL BE MARKED IN THE FIELD BY THE RESIDENT ENGINEER.

PAVING AND GRADING NOTES

- C-1. ALL PAVEMENT DIMENSIONS ARE TO THE EDGE OF PAVEMENT, UNLESS OTHERWISE INDICATED.
- C-2. PAVING WORK SHALL INCLUDE FINAL SUB-GRADE SHAPING AND PREPARATION, FORMING, PLACEMENT OF BASE COURSE MATERIALS, AND SUBSEQUENT BINDER AND/OR SURFACE COURSES, FINISHING AND CURING OF CONCRETE, FINAL CLEAN-UP AND ALL RELATED WORK.
- C-3. PAVEMENT DESIGN SHALL BE AS DETAILED. PRIOR TO THE PLACEMENT OF ANY STONE BASE ALL SUBBASE SHALL BE COMPACTED WITH A SELF-PROPELLED SHEEPSFOOT COMPACTOR (CAT B15 OR LARGER) TO A MINIMUM DENSITY OF 95% MODIFIED PROCTOR. TESTING SHALL BE BY NUCLEAR DENSITY TEST AND PROOF ROLLING. THE CONTRACTOR SHALL PROOF ROLL THE SUBGRADE BEFORE PAVEMENT CONSTRUCTION PROCEEDS. THE PROOF ROLL MUST BE WITNESSED BY THE ENGINEER AND A REPRESENTATIVE OF THE VILLAGE. THE SUBGRADE WILL NOT BE APPROVED AND ACCEPTED WITHOUT PROOF ROLLING. THE PROOF ROLLING SHALL BE DONE BY A FULLY LOADED THREE-AXLE DUMP TRUCK TOGETHER WITH LOAD WEIGHING AT LEAST TWENTY-FIVE (25) TONS. IF THE SUBGRADE OR BASE HAS FAILURE OR PUMPING AS INDICATED BY PROOF ROLLING, THE AREA OF FAILURE OR PUMPING SHALL BE SCARIFIED AND RECOMPACTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. SUBSEQUENT PROOF ROLL WILL BE CONDUCTED UNTIL THE SUBGRADE IS FOUND TO BE ACCEPTABLE TO THE ENGINEER.
- C-4. ALL DISTURBED NON-PAVEMENT AREAS SHALL BE ROUGH GRADED. THE CONTRACTOR IS RESPONSIBLE FOR ALL EROSION PREVENTION AND REPAIR.
- C-5. PRIME COAT FOR THE SURFACE COURSE SHALL BE APPLIED TO THE BINDER AT A RATE OF 0.07 GAL/SY (SS-1). PRIME COAT FOR THE BINDER COURSE SHALL BE APPLIED TO THE SUBBASE AT A RATE OF 0.25 GAL/SY (P.E.P.).
- C-6. ALL CURB AND SIDEWALK SHALL BE REINFORCED WITH TWO #4 REBARS (THREE EQUALLY SPACED REBAR FOR SIDEWALK) WHENEVER THE CURB OR SIDEWALK CROSSES A UTILITY TRENCH. EXTEND THE REBAR TEN FEET BEYOND THE TRENCH ON BOTH SIDES.
- C-7. EXTRA CARE SHALL BE EXERCISED WHEN OPERATING EQUIPMENT AROUND TREES AND SHRUBS. INJURED BRANCHES OR ROOTS SHALL BE PRUNED IN A MANNER SATISFACTORY TO THE ENGINEER AND SHALL BE PAINTED WHERE THE CUT WAS MADE. ROOTS EXPOSED DURING EXCAVATING OPERATIONS SHALL BE NEATLY PRUNED AND COVERED WITH TOPSOIL. THIS WORK SHALL BE DONE AS SOON AS POSSIBLE AND SHALL BE CONSIDERED AS INCIDENTAL TO THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

□ DENOTES A REFERENCE TO A PAY ITEM INCIDENTAL TO ANOTHER PAY ITEM WITHIN THE CONTRACT.

FILE NAME = 4136.800-TR2.cwg	USER NAME = GHA	DESIGNED - JRD	REVISED -		SUMMARY OF QUANTITIES AND GENERAL NOTES			FAP RTE 541	SECTION 08-00279-00-TL	COUNTY LAKE	TOTAL SHEETS 64	SHEET NO. 3
PLOT SCALE = 1" = .0533'	CHECKED - DPB	REVISED -	CONTRACT # 63436									
PLOT DATE = 3/10/10	DATE - 3/10/10	REVISED -	SCALE: NONE					SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		
GHA #4136.800												