

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				80% FED 20% VILLAGE ROADWAY	80% FED 20% VILLAGE BRIDGE	100% VILLAGE LIGHTING	100% VILLAGE BEAUTIFICATION	80% FED 20% VILLAGE TRAINEES
				0004 URBAN	0011 URBAN	0021 URBAN	0031 URBAN	0042 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	30				
20101000	TEMPORARY FENCE	FOOT	100	100				
20101100	TREE TRUNK PROTECTION	EACH	1	1				
20101200	TREE ROOT PRUNING	EACH	1	1				
20200100	EARTH EXCAVATION	CU YD	120	120				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	144	144				
20300100	CHANNEL EXCAVATION	CU YD	208	208				
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	82		82			
20800150	TRENCH BACKFILL	CU YD	5	5				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	718	718				
25000310	SEEDING, CLASS 4	ACRE	0.09	0.09				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12	12				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	12				
25100630	EROSION CONTROL BLANKET	SQ YD	1,129	1,129				
25200110	SODDING, SALT TOLERANT	SQ YD	307	307				
25200200	SUPPLEMENTAL WATERING	UNIT	16	16				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	15	15				
28000305	TEMPORARY DITCH CHECKS	FOOT	12	12				
28000400	PERIMETER EROSION BARRIER	FOOT	487	487				
28000510	INLET FILTERS	EACH	2	2				
28100107	STONE RIPRAP, CLASS A4	SQ YD	442		442			
28200200	FILTER FABRIC	SQ YD	442		442			
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	148	148				
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	20	20				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1				
40600300	AGGREGATE (PRIME COAT)	TON	0.2	0.2				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4	4				
40701846	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/4"	SQ YD	102	102				
42001300	PROTECTIVE COAT	SQ YD	107	107				
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	32	32				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	713	713				

* SPECIALTY ITEMS

(SHEET 1 OF 3)

FILE NAME =	USER NAME = poosecha	DESIGNED - LP	REVISED - PER IDOT 07/29/10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHORT STREET OVER EAST BRANCH DUPAGE RIVER SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
W:\071-002 Short Phase II\CA00.Sheets\071-002-shr-S00.dgn	DRAWN - LP	CHECKED - JP	REVISED -					03-00050-00-BR	DUPAGE	45	3	
PLOT SCALE = 20.0000' / IN.	DATE - 08/02/2010	REVISED -						CONTRACT NO. 63468				
PLOT DATE = 8/2/2010								ILLINOIS FED. AID PROJECT BFM-8003 (676)				
				SCALE: NTS	SHEET NO. 3 OF 45 SHEETS	STA. 6+24.80 TO STA. 8+33.80						