

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				80% FED 20% VILLAGE ROADWAY 0004 URBAN	80% FED 20% VILLAGE BRIDGE 0011 URBAN	100% VILLAGE LIGHTING 0021 URBAN	100% VILLAGE BEAUTIFICATION 0031 URBAN	80% FED 20% VILLAGE TRAINEES 0042 URBAN
44000100	PAVEMENT REMOVAL	SQ YD	354	354				
44000300	CURB REMOVAL	FOOT	54	54				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	109	109				
44000600	SIDEWALK REMOVAL	SQ FT	717	717				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	5	5				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1			
50104650	SLOPE WALL REMOVAL	SQ YD	272		272			
50200100	STRUCTURE EXCAVATION	CU YD	206		206			
50300225	CONCRETE STRUCTURES	CU YD	163.6		163.6			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	462.6		462.6			
50300260	BRIDGE DECK GROOVING	SQ YD	442		442			
50300280	CONCRETE ENCASEMENT	CU YD	11.4		11.4			
50300300	PROTECTIVE COAT	SQ YD	921		921			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	107,740		107,740			
* X509 1725	BICYCLE RAILING, SPECIAL	FOOT	158		158			
* X509 1755	PARAPET RAILING, SPECIAL	FOOT	391		391			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1,178		1,178			
51202305	DRIVING PILES	FOOT	1,178		1,178			
51203600	TEST PILE STEEL HP12X53	EACH	4		4			
51204650	PILE SHOES	EACH	32		32			
51500100	NAME PLATES	EACH	1		1			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	40	40				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	62		62			
<del>Z0046304</del>	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	132		132			
60200405	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 4 FRAME AND GRATE	EACH	1	1				
60207205	CATCH BASINS, TYPE C, TYPE 4 FRAME AND GRATE	EACH	1	1				
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	51	51				
60606800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18	FOOT	50	50				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8				
67100100	MOBILIZATION	L SUM	1	1				
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1				

\* SPECIALTY ITEMS

(SHEET 2 OF 3)

FILE NAME = W:\871-002 Short Phase I\ICADD_Sheets\871-002-sht-S00.dgn	USER NAME = pcc1eche	DESIGNED - LP	REVISED - PER IDOT 07/29/10	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SHORT STREET OVER EAST BRANCH DUPAGE RIVER SUMMARY OF QUANTITIES</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 20.0000' / IN.	DRAWN - LP	CHECKED - JP	REVISED -		SCALE: NTS	SHEET NO. 4 OF 45 SHEETS	STA. 6+24.80 TO STA. 8+33.80	03-00050-00-BR	DUPAGE	45	4	
PLOT DATE = 8/2/2010	DATE - 08/02/2010	REVISOR -	REVISOR -					ILLINOIS FED. AID PROJECT		BPM-8003 (676)		
CONTRACT NO. 63468												