	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
					80% FED 20% VILLAGE	80% FED 20% VILLAGE	100% VILLAGE	100% VILLAGE	80% FED 20% VILLAGE
					ROADWAY	BRIDGE	LIGHTING	BEAUTIFICATION	TRAINEES
					0004	0011	0021	0031	0042
					URBAN	URBAN	URBAN	URBAN	URBAN
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8				
	72000100	SIGN PANEL - TYPE 1	SQ FT	6	6				
	72900100	METAL POST - TYPE A	FOOT	50	50				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	106	106				
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	320	320				
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2				
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2				
*	81200240	CONDUIT EMBEDDED IN STRUCTURE, 2½" DIA., PVC	FOOT	330			330		
*	81304700	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 18" X 6"	EACH	4			4		
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52				
	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	199	199				
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1			
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1			
	X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	420	420				
	XX006277	TEMPORARY SEDIMENT TRAP	EACH	1	1				
	XX008003	FORM LINER TEXTURED SURFACE, SPECIAL	SQ FT	1,677				1,677	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
	Z0076600	TRAINEES	HOUR	1,000					1,000
	XX008403	CONCRETE SUPERSTRUCTURE, SPECIAL	CU YD	58.5		58.5			

* SPECIALTY ITEMS

(SHEET 3 OF 3)

FILE NAME = W:\871-002 Short Phase II\CADD_Sheets\871-002-sht-SOQ.dgn	USER NAME = pociecha	DESIGNED - LP	REVISED - PER IDOT 07/29/10
		DRAWN - LP	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED - JP	REVISED -
	PLOT DATE = 8/2/2010	DATE - 08/02/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SHORT STREET OVER EAST BRANCH DUPAGE RIVER
SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 5 OF 45 SHEETS | STA. 6+24.80 TO STA. 8+33.80

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	03-00050-00-BR	DUPAGE	45	5
		CONTRACT NO. 63468		
	ILLINOIS	FED. AID PROJECT	BRM-8003 (676)	