

THERMOPLASTIC PAVEMENT MARKING	
LOCATION (STA. TO STA.)	LINE 4 IN (FT)
6+24.80 TO 6+52.10	62
8+12.10 TO 8+33.80	44
TOTAL	106

POLYUERA PAVEMENT MARKING TYPE I	
LOCATION (STA. TO STA.)	LINE 4 IN (FT)
6+52.10 TO 8+12.10	320
TOTAL	320

EARTHWORK QUANTITIES				
LOCATION (STA. TO STA.)	EARTH EX. (CU YD)	ADJ. EARTH EX. (15%)	EMBANKMENT (CU YD)	BALANCE WASTE (+) OR SHORTAGE (-)
6+24.80 TO 6+82.10	62.0	52.7	40.9	11.9
7+82.10 TO 8+33.80	57.4	48.8	27.3	21.5
TOTAL	119.4	101.5	68.1	33.4

FILE NAME =	USER NAME = pcsecha	DESIGNED - LP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHORT STREET OVER EAST BRANCH DUPAGE RIVER SCHEDULES OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
W:\071-002 Short Phase I\VCADD_Sheets\071-002-sht-schedule.dgn	PLOT SCALE = 20.0000' / IN.	DRAWN - LP	REVISED -			03-00050-00-BR	DUPAGE	45	7	
		CHECKED - JP	REVISED -			CONTRACT NO. 63468				
		DATE - 08/02/2010	REVISED -			[ILLINOIS] FED. AID PROJECT BRM-8003 (676)				
				SCALE: NTS	SHEET NO. 7 OF 45 SHEETS	STA. 6+24.80 TO STA. 8+33.80				