

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
PAY ITEM NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% LOCAL 1000-2A	BRIDGE 80% FEDERAL 20% LOCAL X028-2A
20101000	TEMPORARY FENCE	FOOT	195	195	---
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	945	945	---
20400800	FURNISHED EXCAVATION	CU YD	250	250	---
20800150	TRENCH BACKFILL	CU YD	55	55	---
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,670	1,670	---
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	50	50.0	---
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4	---
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	31	31	---
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	31	31	---
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	31	31	---
25100630	EROSION CONTROL BLANKET	SQ YD	1,670	1,670	---
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	35	35	---
28000305	TEMPORARY DITCH CHECKS	FOOT	32	32	---
28000400	PERIMETER EROSION BARRIER	FOOT	655	655	---
28000510	INLET FILTERS	EACH	1	1	---
28100105	STONE RIPRAP, CLASS A3	SQ YD	16	16	---
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	45	---	45
28200200	FILTER FABRIC	SQ YD	20	20	---
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	725	725	---
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	725	725	---
40201000	AGGERGATE FOR TEMPORARY ACCESS	TON	25	25	---
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	45	45	---
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	85	85	---
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	85	85	---
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	510	510	---
44000100	PAVEMENT REMOVAL	SQ YD	610	610	---
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	85	85	---
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	28	28	---
44000600	SIDEWALK REMOVAL	SQ FT	470	470	---
48101200	AGGREGATE SHOULDERS, TYPE B	TON	40	40	---
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	---	1
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	---
50901750	PARAPET RAILING	FOOT	71	---	71
51500100	NAME PLATES	EACH	1	---	1
54001001	BOX CULVERT END SECTIONS, 1 CUVERT NO. 1	EACH	2	---	2
54002020	EXPANSION BOLTS 3/4 INCH	EACH	60	---	60
54021005	PRECAST CONCRETE BOX CULVERT 10'X5' (M273)	FOOT	160	---	160
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	78	78	---
55101200	STORM SEWER REMOVAL 24"	FOOT	60	60	---
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	---
60603800	COMBINATION CURB AND GUTTER, TYPE B-6.12	FOOT	328	328	---
67100100	MOBILIZATION	L SUM	1	1	---
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	---
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	420	420	---
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10	10	---
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	200	200	---
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	85	85	---
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	---

\* SPECIALTY ITEM

COMPANY NAME: SEC Group, Inc.  
 PROJECT CONTACT: [Redacted]  
 CLIENT: Village of Berwyn  
 DATE PLOTTED: 8/18/2010 3:24:19 PM  
 FILE NAME: 080594-Seq.dgn  
 PLOT DRIVER: pct.plt  
 PEN TABLE: STANDARD-TRANS.tbl



USER NAME = whoad	DESIGNED - JPC	REVISED -
FILE NAME = 080594-Seq.dgn	DRAWN - WJH	REVISED -
PLOT SCALE = N.T.S.	CHECKED - RGD	REVISED -
PLOT DATE = 8/18/2010	DATE - 8/18/10	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

AYER STREET OVER MOKELER CREEK SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. OF	SHEETS	STA. _____ TO STA. _____

F.A.U. RTE. 0005	SECTION 06-00057-00-BR	COUNTY McHENRY	TOTAL SHEETS 22	SHEET NO. 3
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 63508	