

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GIRDER 21

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. S. Abut.	569+53.42	60.54	736.34	736.34
☉ Brg. S. Abut.	569+57.74	60.54	736.27	736.27
A	569+67.05	60.54	736.10	736.12
B	569+76.36	60.54	735.92	735.95
C	569+85.66	60.54	735.73	735.76
D	569+94.97	60.54	735.52	735.54
E	570+04.28	60.54	735.30	735.31
☉ Pier 1	570+13.50	60.54	735.07	735.07
G	570+22.81	60.54	734.83	734.83
H	570+32.12	60.54	734.57	734.58
I	570+41.42	60.54	734.30	734.31
J	570+50.73	60.54	734.01	734.03
K	570+60.04	60.54	733.72	733.72
☉ Pier 2	570+71.35	60.54	733.34	733.34
M	570+80.66	60.54	733.01	733.01
N	570+89.97	60.54	732.68	732.68
O	570+99.27	60.54	732.35	732.35
P	571+08.58	60.54	732.01	732.01
Q	571+17.89	60.54	731.68	731.68
☉ Pier 3	571+26.22	60.54	731.38	731.38
R	571+35.53	60.54	731.05	731.07
S	571+44.84	60.54	730.72	730.75
T	571+54.14	60.54	730.39	730.43
U	571+63.45	60.54	730.05	730.10
V	571+72.76	60.54	729.72	729.76
☉ Brg. N. Abut.	571+84.62	60.54	729.30	729.30
Bk. N. Abut.	571+88.09	60.54	729.17	729.17

☉ ILLINOIS ROUTE 251 & PGL

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. S. Abut.	568+88.69	0.00	735.58	735.58
☉ Brg. S. Abut.	568+93.76	0.00	735.54	735.54
A	569+03.76	0.00	735.46	735.48
B	569+13.76	0.00	735.36	735.40
C	569+23.76	0.00	735.25	735.29
D	569+33.76	0.00	735.12	735.15
E	569+43.76	0.00	734.98	734.99
F	569+53.76	0.00	734.82	734.82
☉ Pier 1	569+58.31	0.00	734.74	734.74
G	569+68.31	0.00	734.56	734.57
H	569+78.31	0.00	734.37	734.38
I	569+88.31	0.00	734.16	734.17
J	569+98.31	0.00	733.93	733.95
K	570+08.31	0.00	733.69	733.70
L	570+18.31	0.00	733.43	733.44
☉ Pier 2	570+24.00	0.00	733.28	733.28
M	570+34.00	0.00	733.00	733.00
N	570+44.00	0.00	732.71	732.71
O	570+54.00	0.00	732.40	732.40
P	570+64.00	0.00	732.07	732.07
Q	570+74.00	0.00	731.73	731.73
☉ Pier 3	570+85.40	0.00	731.33	731.33
R	570+95.40	0.00	730.97	730.99
S	571+05.40	0.00	730.61	730.65
T	571+15.40	0.00	730.26	730.31
U	571+25.40	0.00	729.90	729.95
V	571+35.40	0.00	729.54	729.58
☉ Brg. N. Abut.	571+50.05	0.00	729.02	729.02
Bk. N. Abut.	571+53.87	0.00	728.88	728.88



g:\project\2082773_001\cadd\structural\sheet\1010190-64B79-01F-SlabEL_5.dgn 11/12/17 AM 10/19/2010

DESIGNED - JY
CHECKED - GSP
DRAWN - MJB
CHECKED - JY

TOP OF SLAB ELEVATIONS (5 OF 5)
STRUCTURE NO. 101-0190

SHEET NO. 12	F.A.* RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*	1-HBR & 1-2HB-D	WINNEBAGO	216	67
61 SHEETS	IL RTE 251 & FOREST HILLS RD		CONTRACT NO. 64B79		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT					



* F.A.P. 303 & F.A.U. 5146

Revised 10/25/10 BHS