

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	L23 STP	L23 STP	L1C BRRP	L23 STP
				80% FED - 20% STATE 0014	80% FED 20% STATE RDWAY 0005	Spring Creek 80% FED 20% STATE 0011	Forest Hills 80% FED 20% STATE 0014
20200100	EARTH EXCAVATION	CU YD	2481		2481		
2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	695			608	87
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5880		5880		
* 25000200	SEEDING, CLASS 2	ACRE	1.50		1.50		
* 25100630	EROSION CONTROL BLANKET	SQ YD	6065		6065		
* 25100900	TURF REINFORCEMENT MAT	SQ YD	246		246		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	750		750		
28000305	TEMPORARY DITCH CHECKS	FOOT	30		30		
28000400	PERIMETER EROSION BARRIER	FOOT	2678		2678		
28000500	INLET AND PIPE PROTECTION	EACH	35		35		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	5789		5789		
40600535	LEVELING BINDER (HAND METHOD), N70	TON	2		2		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	35		35		
40600735	POLYMERIZED LEVELING BINDER (HAND METHOD), N70	TON	49	49			
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	969	969			
40600990	TEMPORARY RAMP	SQ YD	639	639			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	244		244		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	53		53		
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	1453	1453			
42001200	PAVEMENT FABRIC	SQ YD	496		496		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1816	1782	34		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6930	6930			
42400800	DETECTABLE WARNINGS	SQ FT	80	80			
44000100	PAVEMENT REMOVAL	SQ YD	1535		1535		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	17382		17382		
44000300	CURB REMOVAL	FOOT	117		117		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3281		3281		
44000600	SIDEWALK REMOVAL	SQ FT	4666	4666			
40004552	APPROACH SLAB REMOVAL	SQ YD	1402		1402		
44001980	CONCRETE BARRIER REMOVAL	FOOT	2788		2788		

FILE NAME =	USER NAME = goffjl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwork\pwidot\goffjl\dms41657\c21445-shr-cover.dgn		DRAWN -	REVISED -			•	1-HBR & 1-2HB-D	WINNEBAGO	216	5	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64B79					
PLOT DATE = Wed Sep 01 11:46:30 2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.			