

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	L23 STP	L23 STP	L1C BRRP	L23 STP
				80% FED. 20% STATE OO14	80% FED 20% STATE RDWAY 0005	Spring Creek 80% FED 20% STATE 0011	Forest Hills 80% FED 20% STATE 0014
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	248		248		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	496		496		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	496		496		
44003100	MEDIAN REMOVAL	SQ FT	3773		3773		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1340		1340		
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1515		1515		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1
50102400	CONCRETE REMOVAL	CU YD	37.5				37.5
50104650	SLOPEWALL REMOVAL	SQ YD	168				168
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1				1
50157300	PROTECTIVE SHIELD	SQ YD	1992			1636	356
50200100	STRUCTURE EXCAVATION	CU YD	1026			918	108
50300100	FLOOR DRAINS	EACH	9				9
50300225	CONCRETE STRUCTURES	CU YD	1660.5			1565.5	95.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1835.9			1418.1	417.8
50300260	BRIDGE DECK GROOVING	SQ YD	5240			4085	1155
50300300	PROTECTIVE COAT	SQ YD	6319			4856	1463
50500105	FURNISH AND ERECTING STRUCTURAL STEEL	L SUM	1			1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	9083				9083
50500505	STUD SHEAR CONNECTORS	EACH	19426			18566	860
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	12				12
Z0001905	STRUCTURAL STEEL REPAIR	POUND	3223				3223
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1				1
Z0007112	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1				1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	697510			564910	132600
50800515	BAR SPLICERS	EACH	523			398	125
51100100	SLOPEWALL 4 INCH	SQ YD	1507			1339	168
51201600	FURNISHING STEEL PILES HP12X53	FOOT	9638			9638	
51202305	DRIVING PILES	FOOT	9638			9638	
51203600	TEST PILES STEEL HP12X53	EACH	5				5

FILE NAME =	USER NAME = goffjl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwidot\goffjl\dms41657\d21445-shr-cover.dgn		DRAWN -	REVISED -			•	1-HBR & 1-2HB-D	WINNEBAGO	216	6	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT					
PLOT DATE = Wed Sep 01 11:46:30 2010		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 64B79		