

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	L23 STP	L23 STP	L1C BRRP	L23 STP
				80% FED 20% STATE 0014	80% FED 20% STATE RDWAY 0005	Spring Creek 80% FED 20% STATE 0011	Forest Hills 80% FED 20% STATE 0014
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4648		4648		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	400		400		
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	923			569	354
* 81301200	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE 12" X 10" X 6"	EACH	6			4	2
* 81603034	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	469			368	101
* 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1C NO. 6	FOOT	904			538	366
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	451			356	95
Z0013798	CONSTRUCTION LAYOUT	L SUM	1			0.5	0.5
44201299	DOWEL BARS 1 1/2"	EACH	600		600		
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	2			2	
44213204	TIE BARS 3/4"	EACH	150		150		
Z0028415	GEO TECHNICAL REINFORCEMENT	SQ YD	929		929		
* Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1		1		
* Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2		2		
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1		1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	5		5		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	7		7		
Z0034806	MODULAR EXPANSION JOINT - SWIVEL 6"	FOOT	63				63
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	1		1		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		0.5	0.5	
Z0062456	TEMPORARY PAVEMENT	SQ YD	769		769		
X2020502	BRACED EXCAVATION	CU YD	1012			1012	
* Z0033026	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1			0.5	0.5
X0322011	LIGHT POLE REMOVE AND RE-ERECT	EACH	3			2	1
* X0322951	CABLE SPLICE SPECIAL	EACH	5			4	1
Z0012154	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	158				158
X0964700	SHOULDERS, SPECIAL	SQ YD	237		237		
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	769		769		
X5210015	ELASTOMERIC BEARING ASSEMBLY, TYPE I (SPECIAL)	EACH	42			42	
X5210025	ELASTOMERIC BEARING ASSEMBLY, TYPE II (SPECIAL)	EACH	42			42	
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1			0.5	0.5

* SPECIALTY ITEMS

FILE NAME =	USER NAME = goffjl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\pwsdot\goffjl\dms41657\d21440-shr-cover.dgn		DRAWN -	REVISED -			•	1-HBR & 1-2HB-D	WINNEBAGO	216	9	
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT					
PLOT DATE = Wed Sep 01 11:46:31 2010		DATE -	REVISED -			CONTRACT NO. 64B79					