

SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	LOCATION	OFFSET	REMARKS
44000600	SIDEWALK REMOVAL	SQ. FT.	SPRING CREEK ROAD		
		2674.2	15+87.4 TO 21+00.2	RT	
		1992.0	17+71.9 TO 21+72.8	LT	
		4666			
44001980	CONCRETE BARRIER REMOVAL	SQ. FT.	IL 251		
		974	559+04.6 TO 568+78.2		
		1814	571+33.9 TO 589+48.1		
		2788			
44003100	MEDIAN REMOVAL	SQ. FT.	SPRING CREEK ROAD		
		3211	16+84.0 TO 20+80.9	MEDIAN	
		298	18+73.0 TO 20+43.0		PIER 1
		264	19+68.5 TO 21+15.0		PIER 3
		3773			
44004250	PAVED SHOULDER REMOVAL	SQ. YD.	FOREST HILLS ROAD		
		113.3	596+20.3 TO 597+27.8	RT	
		307.8	601+00.0 TO 604+28.2	RT	
		91.0	601+67.8 TO 602+47.0	LT	
			IL 251		
		369.4	564+55.0 TO 567+81.5	NB	INCLUDES RAMP
		458.1	564+55.0 TO 567+59.3	SB	INCLUDES RAMP
		1339.6			
442001200	PAVEMENT FABRIC	SQ. YD.			
		496			TO BE USED IF NEEDED
44200970	CLASS B PATCHES, TY II, 10 INCH	SQ. YD.			
		248			TO BE USED IF NEEDED
44200974	CLASS B PATCHES, TY III, 10 INCH	SQ. YD.			
		496			TO BE USED IF NEEDED
44200976	CLASS B PATCHES, TY IV, 10 INCH	SQ. YD.			
		496			TO BE USED IF NEEDED
44201299	DOWEL BARS 1 1/2"	EACH			
		600			TO BE USED IF NEEDED
44213204	TIE BARS 3/4"	EACH			
		150			TO BE USED IF NEEDED

ITEM NO.	DESCRIPTION	UNIT	LOCATION	OFFSET	REMARKS
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ. YD.	FOREST HILLS ROAD		
		142.2	596+20.3 TO 597+30.4	RT	
		275.3	601+00.0 TO 604+28.2	RT	
		84.1	601+53.0 TO 602+47.0	LT	
			IL 251		
		404.3	564+55.0 TO 567+83.0	NB	
		445.7	564+55.0 TO 567+45.3	SB	
		68.6	565+42.1 TO 565+59.9	SB	RAMP-SB TO EB
		2.9	567+68.3 TO 567+68.5	NB	RAMP-EB TO NB
		45.2	597+46.8 TO 598+74.0	LT	
		46.7	598+59.7 TO 599+85.8	RT	
		1514.9			
60200705	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 6 FRAME AND GRATE	EACH	SPRING CREEK ROAD		
		1	20+50.0	43 LT	
		1	20+54.0	43 LT	
		2			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	SPRING CREEK ROAD		
		1	19+22.0	3.5 LT	
		1	20+06.0	3.0 LT	
		1	20+91.0	2.5 LT	
		3			
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW, TYPE 1 FRAME AND GRATE, OPEN LID	EACH	SPRING CREEK ROAD		
		1	21+30.5	41.7' RT	
		1	21+83.8	31.4' LT	
		1	22+63.2	40.6' RT	
		3			
60255500	MANHOLES TO BE ADJUSTED	EACH	SPRING CREEK ROAD		
		1	16+67.0	11.8 RT	
		1	18+00.9	49.6 RT	
		1	18+03.8	35.6 LT	
		1	18+42.9	47.9 RT	
		1	19+84.3	35.9 LT	
		1	20+52.7	36.0 LT	
		1	20+93.7	35.8 LT	
		1	22+65.8	24.5 LT	
		1	22+66.0	14.6 RT	
		1	22+97.5	10.9 LT	
		1	23+28.9	14.0 RT	
		1	24+14.1	47.6 LT	
		1	24+93.7	35.5 RT	
		13			
60251000	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 6, FRAME AND GRATE	EACH	SPRING CREEK ROAD		
		1	15+79.1	29.2 RT	
		1	16+41.2	37.2 LT	
		1	18+37.5	43.7 RT	
		1	20+76.6	75.0 RT	
		1	20+91.1	48.4 RT	
		1	20+94.4	50.0 RT	
		1	21+30.5	41.7 RT	
		1	21+83.8	30.4 LT	
		1	22+78.6	47.9 RT	
		1	24+13.9	42.1 RT	
		10			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH			
		1			TO BE USED IF NEEDED
60257900	MANHOLES TO BE RECONSTRUCTED	EACH			
		1			TO BE USED IF NEEDED

* F.A.P. 303 & F.A.U. 5146