

SCHEDULE OF QUANTITIES

60500040 REMOVING MANHOLES			
EACH	LOCATION	OFFSET	REMARKS
1	19+22.0	3.5 LT	
1	20+06.4	3.3 LT	
1	20+90.7	2.6 LT	
3			

60500080 REMOVING CATCH BASINS TO MAINTAIN FLOW			
EACH	LOCATION	OFFSET	REMARKS
1	20+50.0	43 LT	
1	20+54.0	43 LT	
2			

60609200 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12			
FOOT	LOCATION	OFFSET	REMARKS
IL 251			
32	567+40.1 TO 567+60.7	RT	NORTHBOUND
40	567+66.8 TO 568+06.3	LT	SOUTHBOUND
141	567+86.2 TO 569+27.6	RT	NORTHBOUND
80	571+48.3 TO 572+28.0	LT	SOUTHBOUND
81	572+16.0 TO 572+96.6	RT	NORTHBOUND
41	572+69.0 TO 572+90.8	LT	SOUTHBOUND
SPRING CREEK ROAD			
682	16+84.6 TO 23+66.3	RT	EB MEDIAN
682	16+84.2 TO 23+66.3	LT	WB MEDIAN
1779			

60610400 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24			
FOOT	LOCATION	OFFSET	REMARKS
SPRING CREEK ROAD			
733	15+90.1 TO 21+13.3	RT	
452	17+67.0 TO 21+74.9	LT	
187	21+30.6 TO 21+27.9	RT	
289	21+77.8 TO 24+08.6	LT	
1660			

60618300 CONCRETE MEDIAN SURFACE, 4 INCH			
SQ FT	LOCATION	OFFSET	REMARKS
SPRING CREEK ROAD			
SPRING CREEK ROAD			
3211	16+84.0 TO 20+80.9	MEDIAN	
298	18+73.0 TO 20+43.0		PIER 1
264	19+68.5 TO 21+15.0		PIER 3
3773			

60611600 COMBINATION CURB AND GUTTER, (SPECIAL)			
FOOT	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
66	597+18.2 TO 597+84.2	LT	

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT, POSTS			
FOOT	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
225	595+52.3 TO 597+77.3	LT	
75.0	596+42.2 TO 597+17.2	RT	
187.5	601+43.9 TO 603+31.4	RT	
IL 251			
37.5	572+40.7 TO 572+75.5	RT	
525.0			

63000015 STEEL PLATE BEAM GUARDRAIL, TYPE D			
FOOT	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
175	593+77.8 TO 595+52.3	LT	

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2			
EACH	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
1	596+29.7 TO 596+42.2	RT	
IL 251			
1	567+45.0	LT	
1	572+87.0	RT	
3			

63100070 TRAFFIC BARRIER TERMINAL, TYPE 5			
EACH	LOCATION	OFFSET	REMARKS
IL 251			
1	568+03.0	LT	
1	571+98.0	RT	
FOREST HILLS ROAD			
1	597+77.3 TO 597+92.0	LT	
1	597+17.2 TO 597+31.9	RT	
4			

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6			
EACH	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
1	601+00.1 TO 601+43.9	RT	
1	601+53.3 TO 601+97.1	LT	
IL 251			
1	569+41.5	RT	
1	571+26.5	LT	
1	598+31.0 TO 598+74.8	LT	
1	599+42.1 TO 599+85.8	RT	
6			

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL), TANGENT			
EACH	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
1	601+43.9 TO 602+47.1	LT	
1	603+31.4 TO 603+81.4	RT	
IL 251			
1	568+51.0	RT	
1	572+29.0	LT	
1	597+81.0 TO 598+31.0	LT	
1	598+92.1 TO 599+42.1	RT	
6			

63200310 GUARDRAIL REMOVAL			
FOOT	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
581	593+45.0 TO 597+98.0	LT	
100	595+38.1 TO 596+38.1	RT	
275	600+77.1 TO 603+72.1	RT	
100	601+47.2 TO 602+47.2	LT	
IL 251			
104	568+43.4 TO 569+47.2	RT	
120	570+95.1 TO 572+14.9	LT	
99	571+80.6 TO 572+80.0	RT	
1380			

63500105 DELINEATORS			
EACH	LOCATION	OFFSET	REMARKS
FOREST HILLS ROAD			
1	602+47.1	LT	
1	603+81.4	RT	
IL 251			
1	568+20.0	568+20.0	RT
1	572+54.0	572+54.0	LT
1	597+81.0		LT
1	598+92.1		RT
6			