

# SCHEDULE OF QUANTITIES

78200410 GUARDRAIL MARKERS, TYPE A				
EACH	LOCATION	OFFSET	REMARKS	
	FOREST HILLS ROAD			
6	593+52.3 TO 597+92.0	LT	80' O.C. CRYSTAL	
4	596+29.7 TO 597+31.9	RT	Min. 4 AMBER	
5	601+00.1 TO 603+81.4	RT	80' O.C. CRYSTAL	
4	601+97.1 TO 602+47.1	LT	Min. 4 AMBER	
	IL 251			
4	567+45.0 TO 568+03.0	LT	Min. 4 CRYSTAL	
4	568+51.0 TO 569+41.5	RT	Min. 4 CRYSTAL	
4	571+26.5 TO 572+29.0	LT	Min. 4 CRYSTAL	
4	571+98.0 TO 572+87.0	RT	Min. 4 CRYSTAL	
4	597+81.0 TO 598+74.7	LT	Min. 4 CRYSTAL	
4	598+92.2 TO 599+85.8	RT	Min. 4 CRYSTAL	
<b>23</b>				

78200520 BARRIER WALL MARKERS, TYPE B				
EACH	LOCATION	OFFSET	REMARKS	
	FOREST HILLS ROAD			
12	596+29.7 TO 601+00.1	RT	Quantities for Top and Side	
10	597+92.0 TO 601+97.1	LT	80' O.C. CRYSTAL - PARAPET	
	IL 251			
19	559+10.1 TO 564+34.8	MEDIAN	100' O.C. AMBER - BARRIER WALL	
54	564+34.8 TO 577+83.2	MEDIAN	80' O.C. AMBER - BARRIER WALL	
8	568+02.9 TO 571+26.5	LT	80' O.C. CRYSTAL - PARAPET	
6	569+41.5 TO 571+98.3	RT	85' O.C. CRYSTAL - PARAPET	
14	577+83.2 TO 582+48.9	MEDIAN	125' O.C. AMBER - BARRIER WALL	
15	582+48.9 TO 589+50.0	MEDIAN	175' O.C. AMBER - BARRIER WALL	
<b>138</b>				

78201000 TERMINAL MARKER - DIRECT APPLIED				
EACH	LOCATION	OFFSET	REMARKS	
	FOREST HILLS ROAD			
1	602+47.1	LT		
1	603+81.4	RT		
	IL 251			
1	568+51.0	LT		
1	572+29.0	RT		
1	602+47.0	LT		
1	603+81.0	RT		
<b>6</b>				

78300100 PAVEMENT MARKING REMOVAL				
SQ FT	LOCATION	OFFSET	REMARKS	
	STAGE 1			
	IL 251			
1977	551+90.0 TO 588+22.1			
	STAGE 1A			
	SPRING CREEK ROAD			
726	16+11.5 TO 25+61.7			
	STAGE 2			
	IL 251			
649	548+73.9 TO 581+72.5			
	STAGE 1B			
	SPRING CREEK ROAD			
481	15+94.7 TO 23+66.1			
	STAGE 3			
	IL 251			
301	584+66.7 TO 590+78.7			
<b>4648</b>				

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				
EACH	LOCATION	OFFSET	REMARKS	
	IL 251			
188	548+69.8 TO 584+66.7	RT		
140	558+37.9 TO 590+78.7	LT		
	SPRING CREEK ROAD			
40	16+12.4 TO 25+61.7	RT		
32	16+12.4 TO 25+61.7	LT		
<b>400</b>				

Z0004552 APPROACH SLAB REMOVAL				
SQ YD	LOCATION	OFFSET	REMARKS	
	FOREST HILLS ROAD			
55	597+40.4 TO 597+60.4			
55	600+95.3 TO 601+15.3			
	IL 251			
410	567+81.5 TO 568+81.6	SB		
386	568+59.5 TO 569+47.2	NB		
239	570+95.1 TO 571+52.5	SB		
257	571+35.9 TO 571+90.2	NB		
<b>1402</b>				

Z0028415 GEOTECHNICAL REINFORCEMENT				
SQ YD	LOCATION	OFFSET	REMARKS	
	IL 251			
	IL 251			
411.9	564+55.0 TO 567+83.0	NB		
445.5	564+55.0 TO 567+45.3	SB		
68.6	565+42.1 TO 565+59.9	SB	RAMP-SB TO EB	
2.5	567+68.3 TO 567+68.5	NB	RAMP-EB TO NB	
<b>928.5</b>				

Z0029999 IMPACT ATTENUATOR REMOVAL				
EACH	LOCATION	OFFSET	REMARKS	
	IL 251			
1	559+04.6	RT		
<b>1</b>				

Z0030070 IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3				
EACH	LOCATION	OFFSET	REMARKS	
	IL 251			
1	559+04.8	MEDIAN		
1	589+50.0	MEDIAN		
<b>2</b>				

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3				
EACH	LOCATION	OFFSET	REMARKS	
	STAGE 1			
	IL 251			
1	574+65.7	18' LT		
	STAGE 1A			
	SPRING CREEK ROAD			
1	18+22.4	10.8' RT		
1	23+36.8	44.6' LT		
1	23+51.7	11.2' LT		
	IL 251 UNDER FORESTHILLS ROAD			
1	580+00.0	0.0' LT		
<b>5</b>				