



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 20, 2010

SUBJECT: FAS Route 1279 (IL 178)
Project ACRS-ACTE-1279 (111)
Section 6R, B
LaSalle County
Contract No. 66547
Item No. 53, November 5, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Revised page 13 of the Special Provisions.
4. Added pages 189 - 192 to the Special Provisions.
5. Revised sheets 7, 103 & 104 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: George F. Ryan, Region 2, District 3; Mike Renner; Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XX005967	TOPSOIL PLANT MIXTURE	CU YD	396.000				
XX006652	STAMP CLRD PCC MED 4	SQ FT	354.000				
XX007335	PVC CASING PIPE 8	FOOT	173.000				
* X0301852	DEWATERING STRUCT N1	EACH	1.000				
X0325607	GR STAB GEOSYNTHETIC	SQ YD	16,119.000				
X0325670	CONC BR RL SDWLK MNTD	FOOT	190.000				
X0326498	GFCI20A DX RECEPTACLE	EACH	16.000				
X0326654	ORNAM LIGHT UNIT COMP	EACH	27.000				
X0327065	ENGNEERD SOIL SPL	TON	973.000				
X0327066	IG FIX UPLIGHTING	EACH	26.000				
X0327067	PVC CASING PIPE 10	FOOT	22.000				
X0327068	PAVT COLOR & TEXTURE SPL	SQ YD	383.000				
X2070304	POROUS GRAN EMB SPEC	CU YD	268.000				
X4240440	PC CONC SIDEWALK 6 SP	SQ FT	233.000				
X5020501	UNWAT STR EX PROT L1	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6063600	COMB CC&G TM4.24	FOOT	150.000				
X7800610	URETH PAVT MK LINE 4	FOOT	7,779.000				
X7800630	URETH PAVT MK LINE 6	FOOT	1,872.000				
X7800640	URETH PAVT MK LINE 8	FOOT	416.000				
X7800650	URETH PAVT MK LINE 12	FOOT	570.000				
Z0001050	AGG SUBGRADE 12	SQ YD	16,119.000				
Z0004002	BOLLARDS	EACH	38.000				
Z0007430	TEMP SIDEWALK	SQ FT	1,844.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0007603	BLDG REMOV NO 3	L SUM	1.000				
Z0007604	BLDG REMOV NO 4	L SUM	1.000				
Z0007605	BLDG REMOV NO 5	L SUM	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0023900	FILL EXIST WELLS	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0046304	P UNDR FOR STRUCT 4	FOOT	135.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0049901	R&D NON-FR ASB BLD 1	L SUM	1.000				
Z0049903	R&D NON-FR ASB BLD 3	L SUM	1.000				
Z0050900	REM CONC FDN	EACH	10.000				
Z0056650	SS 1 WAT MN 15	FOOT	15.000				
Z0065000	SET PILES IN ROCK	EACH	7.000				
Z0067100	STEEL CASINGS 8	FOOT	40.000				
20100110	TREE REMOV 6-15	UNIT	38.000				
20100210	TREE REMOV OVER 15	UNIT	16.000				
20100500	TREE REMOV ACRES	ACRE	0.360				
20200200	ROCK EXCAVATION	CU YD	201.000				
20201200	REM & DISP UNS MATL	CU YD	6,550.000				
20300100	CHANNEL EXCAVATION	CU YD	764.000				
20400800	FURNISHED EXCAVATION	CU YD	6,666.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20800150	TRENCH BACKFILL	CU YD	1,727.400				
25000100	SEEDING CL 1	ACRE	0.510				
25000400	NITROGEN FERT NUTR	POUND	155.000				
25000500	PHOSPHORUS FERT NUTR	POUND	155.000				
25000600	POTASSIUM FERT NUTR	POUND	155.000				
25100115	MULCH METHOD 2	ACRE	0.330				
25100630	EROSION CONTR BLANKET	SQ YD	939.000				
25200110	SODDING SALT TOLERANT	SQ YD	8,707.000				
25200200	SUPPLE WATERING	UNIT	392.000				
28000250	TEMP EROS CONTR SEED	POUND	5,090.000				
28000400	PERIMETER EROS BAR	FOOT	1,525.000				
28000500	INLET & PIPE PROTECT	EACH	14.000				
28100107	STONE RIPRAP CL A4	SQ YD	732.000				
28200200	FILTER FABRIC	SQ YD	732.000				
35100100	AGG BASE CSE A	TON	112.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
35501316	HMA BASE CSE 8	SQ YD	810.000				
35501322	HMA BASE CSE 9 1/2	SQ YD	240.000				
35501326	HMA BASE CSE 10 1/2	SQ YD	143.000				
40201000	AGGREGATE-TEMP ACCESS	TON	200.000				
40600100	BIT MATLS PR CT	GALLON	295.000				
40600300	AGG PR CT	TON	3.500				
40600400	MIX CR JTS FLANGEWYS	TON	0.500				
40600625	LEV BIND MM N50	TON	83.000				
40600990	TEMPORARY RAMP	SQ YD	153.000				
40603080	HMA BC IL-19.0 N50	TON	157.000				
40603310	HMA SC "C" N50	TON	85.000				
40800050	INCIDENTAL HMA SURF	TON	198.000				
42000201	PCC PVT 7 JOINTED	SQ YD	1,977.000				
42000411	PCC PVT 9 1/2 JOINTD	SQ YD	10,120.000				
42000501	PCC PVT 10 JOINTED	SQ YD	135.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42001200	PAVEMENT FABRIC	SQ YD	135.000				
42001300	PROTECTIVE COAT	SQ YD	14,534.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	254.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	418.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	1,440.000				
42400100	PC CONC SIDEWALK 4	SQ FT	21,284.000				
42400800	DETECTABLE WARNINGS	SQ FT	311.000				
44000100	PAVEMENT REM	SQ YD	7,383.000				
44000155	HMA SURF REM 1 1/2	SQ YD	1,432.000				
44000200	DRIVE PAVEMENT REM	SQ YD	1,310.000				
44000300	CURB REM	FOOT	410.000				
44000500	COMB CURB GUTTER REM	FOOT	3,742.000				
44000600	SIDEWALK REM	SQ FT	11,195.000				
44201753	CL D PATCH T2 9	SQ YD	20.000				
44201757	CL D PATCH T3 9	SQ YD	17.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201815	CL D PATCH T2 14	SQ YD	11.000				
44201819	CL D PATCH T3 14	SQ YD	47.000				
48101200	AGGREGATE SHLDS B	TON	21.000				
48300200	PCC SHOULDERS 7	SQ YD	172.000				
50200100	STRUCTURE EXCAVATION	CU YD	183.000				
50200400	ROCK EXC STRUCT	CU YD	122.000				
50300100	FLOOR DRAINS	EACH	6.000				
50300225	CONC STRUCT	CU YD	296.700				
50300255	CONC SUP-STR	CU YD	353.900				
50300260	BR DECK GROOVING	SQ YD	140.000				
50300280	CONCRETE ENCASEMENT	CU YD	7.500				
50300300	PROTECTIVE COAT	SQ YD	972.000				
50400405	P P CONC DK BM 21 DP	SQ FT	3,296.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	1,116.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800205	REINF BARS, EPOXY CTD	POUND	100,810.000				
50800515	BAR SPLICERS	EACH	90.000				
50900305	STEEL RAILING TY T1	FOOT	200.000				
51201400	FUR STL PILE HP10X42	FOOT	338.000				
51202305	DRIVING PILES	FOOT	198.000				
51203400	TEST PILE ST HP10X42	EACH	2.000				
51500100	NAME PLATES	EACH	2.000				
52100500	ANCHOR BOLTS 1/2	EACH	18.000				
52100520	ANCHOR BOLTS 1	EACH	24.000				
542A0220	P CUL CL A 1 15	FOOT	78.000				
542A0223	P CUL CL A 1 18	FOOT	84.000				
5421D018	P CUL CL D 1 18 TEMP	FOOT	13.000				
54213657	PRC FLAR END SEC 12	EACH	4.000				
54213660	PRC FLAR END SEC 15	EACH	2.000				
54213663	PRC FLAR END SEC 18	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54213678	PRC FLAR END SEC 33	EACH	1.000				
550A0050	STORM SEW CL A 1 12	FOOT	996.000				
550A0070	STORM SEW CL A 1 15	FOOT	6.000				
550A0340	STORM SEW CL A 2 12	FOOT	228.000				
550A0360	STORM SEW CL A 2 15	FOOT	125.000				
550A0410	STORM SEW CL A 2 24	FOOT	82.000				
550A0430	STORM SEW CL A 2 30	FOOT	28.000				
550A0440	STORM SEW CL A 2 33	FOOT	312.000				
550A2320	SS RG CL A 1 12	FOOT	453.000				
550A2330	SS RG CL A 1 15	FOOT	31.000				
550A2530	SS RG CL A 2 15	FOOT	134.000				
550A2570	SS RG CL A 2 27	FOOT	97.000				
550A2590	SS RG CL A 2 33	FOOT	120.000				
55100500	STORM SEWER REM 12	FOOT	142.000				
56100600	WATER MAIN 6	FOOT	1,958.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
56100700	WATER MAIN 8	FOOT	645.000				
56200200	WATER SERV LINE 3/4	FOOT	579.000				
56400500	FIRE HYDNNTS TO BE REM	EACH	6.000				
56400600	FIRE HYDRANTS	EACH	7.000				
56500700	DOM WAT SER BOX REM	EACH	5.000				
58100200	WATERPRF MEMBRANE SYS	SQ YD	344.000				
58300100	PC MORTAR FAIRING CSE	FOOT	1,000.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	291.000				
59300100	CONTR LOW-STRENG MATL	CU YD	271.000				
60218300	MAN TA 4 DIA T1F OL	EACH	2.000				
60218400	MAN TA 4 DIA T1F CL	EACH	7.000				
60218500	MAN TA 4 DIA T3F&G	EACH	2.000				
60221100	MAN TA 5 DIA T1F CL	EACH	5.000				
60221200	MAN TA 5 DIA T3F&G	EACH	3.000				
60224446	MAN TA 7 DIA T1F CL	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60235700	INLETS TA T3F&G	EACH	15.000				
60236200	INLETS TA T8G	EACH	6.000				
60240220	INLETS TB T3F&G	EACH	16.000				
60240225	INLETS TB T4F&G	EACH	1.000				
60255500	MAN ADJUST	EACH	2.000				
60257900	MAN RECONST	EACH	1.000				
60260400	INLETS ADJ NEW T1F CL	EACH	1.000				
60266910	VALVE BOX REMOVED	EACH	7.000				
60500040	REMOV MANHOLES	EACH	2.000				
60500050	REMOV CATCH BAS	EACH	5.000				
60500060	REMOV INLETS	EACH	9.000				
60600095	CLASS SI CONC OUTLET	CU YD	3.900				
60600605	CONC CURB TB	FOOT	340.000				
60605000	COMB CC&G TB6.24	FOOT	5,627.000				
60609600	COMB CC&G TM6.12 SPL	FOOT	88.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60611815	COMB CC&G TM SPL	FOOT	1,755.000				
60625800	ISLAND PAVEMENT SPL	SQ YD	127.000				
60900140	TY B INLET BOX 609006	EACH	1.000				
66700205	PERM SURV MKRS T1	EACH	4.000				
66900105	UNDERGR STOR TANK REM	EACH	2.000				
66900200	NON SPL WASTE DISPOSL	CU YD	1,438.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	2.000				
66901000	BACKFILL PLUGS	CU YD	35.000				
67000400	ENGR FIELD OFFICE A	CAL MO	21.000				
67100100	MOBILIZATION	L SUM	1.000				
70103700	TRAF CONT COMPL	L SUM	1.000				
70300100	SHORT-TERM PAVT MKING	FOOT	267.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	175.600				
70300220	TEMP PVT MK LINE 4	FOOT	9,888.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300240	TEMP PVT MK LINE 6	FOOT	1,743.000				
70300250	TEMP PVT MK LINE 8	FOOT	416.000				
70300260	TEMP PVT MK LINE 12	FOOT	466.000				
70300280	TEMP PVT MK LINE 24	FOOT	311.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	5,643.000				
72000100	SIGN PANEL T1	SQ FT	245.000				
72800100	TELES STL SIN SUPPORT	FOOT	595.000				
73000100	WOOD SIN SUPPORT	FOOT	16.000				
78004200	PREF PL PM TB INL L&S	SQ FT	298.000				
78004280	PREF PL PM TB INL L24	FOOT	447.000				
78100100	RAISED REFL PAVT MKR	EACH	89.000				
78200300	PRISMATIC CURB REFL	EACH	28.000				
81000400	CON T 1 1/4 GALVS	FOOT	22.000				
81000700	CON T 2 1/2 GALVS	FOOT	390.000				
81001000	CON T 4 GALVS	FOOT	56.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66547

State Job # - C-93-028-05
 PPS NBR - 3-44320-0000
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - 6R,B

Project Number
 ACRS-ACTE-1279/111/

Route
 FAS 1279

* REVISED : OCTOBER 20, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81012400	CON T 1 1/4 PVC	FOOT	422.000				
81200120	CON EMB STR 2 GALVS	FOOT	210.000				
81200215	CON EMB STR 1.25 PVC	FOOT	238.000				
81400730	HANDHOLE C CONC	EACH	23.000				
81603000	UD 2#8 #8G XLP USE 3/4	FOOT	800.000				
81603158	UD 5#8#8G XLP USE 1 1/4	FOOT	2,261.000				
81702120	EC C XLP USE 1C 8	FOOT	1,560.000				
81702420	EC C XLP USE 3-1C 8	FOOT	925.000				
81900200	TR & BK FIL F ELECT WK	FOOT	3,480.000				
82500410	LT CONT BASM 240V200D	EACH	1.000				
83600120	LIGHT POLE FDN SPL	FOOT	136.000				
83600200	LIGHT POLE FDN 24D	FOOT	12.500				
84200500	REM LT UNIT SALV	EACH	1.000				
84200804	REM POLE FDN	EACH	4.000				
84400105	RELOC EX LT UNIT	EACH	3.000				

FLAGGER AT SIDE ROADS AND ENTRANCES (BDE) 105

FRAMES AND GRATES (BDE) 105

HOT-MIX ASPHALT – ANTI-STRIPPING ADDITIVE (BDE) 106

HOT-MIX ASPHALT – DROP-OFFS (BDE) 106

HOT-MIX ASPHALT - FINE AGGREGATE (BDE) 106

HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE) 107

HOT-MIX ASPHALT – QC/QA ACCEPTANCE CRITERIA (BDE) 108

HOT-MIX ASPHALT – TRANSPORTATION (BDE) 108

LIQUIDATED DAMAGES (BDE) 109

METAL HARDWARE CAST INTO CONCRETE (BDE) 109

MULCH (BDE) 110

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 112

PAVEMENT MARKING REMOVAL (BDE) 113

PAVEMENT PATCHING (BDE) 113

PAYMENTS TO SUBCONTRACTORS (BDE) 114

PERSONAL PROTECTIVE EQUIPMENT (BDE) 115

PRECAST CONCRETE HANDLING HOLES (BDE) 115

PRISMATIC CURB REFLECTORS (BDE) 116

RAISED REFLECTIVE PAVEMENT MARKERS (BDE) 117

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 117

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 124

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE) 124

SEEDING (BDE) 125

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE) 127

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) 131

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 132

TEMPORARY EROSION CONTROL (BDE) 133

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 134

FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 137

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 141

STORM WATER POLLUTION PREVENTION PLAN 145

404 PERMIT 154

NATIONWIDE PERMITS AND CONDITIONS 158

IEPA REGIONAL CONDITIONS 171

IDNR PERMIT 189

For the high pressure water spray, the pressure at the nozzle shall be approximately 25,000 psi (172,000 kPa) with maximum flow rate of 15 gal/min (56 L/min). The nozzle shall be in close proximity to the pavement surface.

DEWATERING STRUCTURE NO. 1

Description. This work shall include all labor, materials, and equipment to **dewater the construction area for structure 050-0250** on each side of the construction to allow bridge construction or other construction activities within the canal, as shown on the plans, and as directed by the Engineer. All work shall be performed in accordance with Section 502 of the Standard Specifications, except as modified herein, shown on the plans, or as directed by the Engineer. After construction of the dewatering structure, the Contractor shall remove all surface water from within the limits of the structures by draining, pumping, or other acceptable means, and maintain dry working conditions during construction. After construction activities within the canal have been completed, the Contractor shall remove the structures to the acceptability of the Engineer.

Materials. Dewatering Structure No. 1 shall consist of any temporary earthen embankment, dike, or engineered structure, including, but not limited to, sandbags, driven sheet pile, etc., as approved by the Engineer. The structure shall prevent water from entering the construction area. All materials and equipment used in construction shall comply with the requirements of the Illinois Department of Natural Resources permit, as required by these provisions.

Construction Requirements. The Contractor shall submit plans, showing a sequence of work, design and construction methods, and description of materials and equipment used to complete the construction of the dewatering structure. The plans shall be accompanied by supporting calculations, and both shall be signed and sealed by a Structural Engineer licensed in the State of Illinois.

Before any construction activities take place within the limits of the canal, a construction permit shall be obtained from the Illinois Department of Natural Resources (IDNR), Office of Water Resources for any temporary work taking place. Any fill or other stabilizing materials placed within the limits of the structures shall comply with the provisions of the permit. Agitation of canal sediment shall be limited during installation and removal of the dewatering system.

It is the responsibility of the Contractor to maintain a dry working area suitable for all activities required to complete construction. Damage to work previously completed due to improper protection, shall be repaired to the satisfaction of the Engineer at no additional compensation. All water shall be discharged outside the limits of the structures within the canal banks. Pumping water from excavated areas may require the use of filtering via filter bags, portable filtering tanks, sediment basins, or other acceptable means. The dewatering system shall not be the cause of flooding of adjacent property.

The exact location of Dewatering Structure No. 1 shall be determined by the Contractor according to clearance needs during construction, and as directed by the Engineer. All work shall be completed within the right-of-way or construction easements.

The Contractor will be responsible for the stability and structural adequacy of the structure in resisting all hydrostatic forces imposed due to water surfaces at any elevation within the canal banks, as well as any other imposed forces. Excavation required to install or remove the dewatering system shall be included in the cost of Dewatering Structure No. 1.

Revised 10/20/2010

IDNR PERMIT



Illinois Department of
Natural Resources

One Natural Resources Way • Springfield, Illinois 62702-1271
<http://dnr.state.il.us>

Rod R. Blagojevich, Governor

Sam Flood, Acting Director

June 6, 2008

SUBJECT: Permit No. DS2008045
Bridge Construction
FAS 1279 (IL Route 178)
Illinois & Michigan Canal
LaSalle County

Gregory L. Mounts, P.E.
Region 2 Engineer
Illinois Department of Transportation
Division of Highways - District 3
700 East Norris Drive
Ottawa, Illinois 61350

Dear Mr. Mounts:

Enclosed is Illinois Department of Natural Resources, Office of Water Resources Permit No. DS2008045 authorizing the subject project. This permit does not supersede any other federal, state or local authorizations that may be required for the project.

If any changes of the permitted work are found necessary, revised plans should be submitted promptly to this office for review and approval. Also, this permit expires on the date indicated in Condition (13). If unable to complete the work by that date, the permittee may make a written request for a time extension.

Upon receipt and review of this permit and all of its conditions, please properly execute and return the attached acceptance blank within sixty (60) days from the date of the permit. Please feel free to contact Rob Giesing of my staff at 217/785-1661 if you have any questions concerning this authorization.

Sincerely,

Michael L. Diedrichsen, P.E.
Acting Manager, Downstate Regulatory Programs

MLD:RCG:crw

Enclosure

cc: IDOT, Bureau of Bridges and Streets (Ralph Anderson, Attn: Todd E. Ahrens)
IDNR, Illinois & Michigan Canal State Trail (Dan Bell)

PERMIT NO. DS2008045

THIS PERMIT IS SUBJECT TO THE FOLLOWING CONDITIONS:

- 1) This permit is granted in accordance with the Rivers, Lakes and Streams Act "615 ILCS 5."
- 2) This permit does not convey title to the permittee or recognize title of the permittee to any submerged or other lands, and furthermore, does not convey, lease or provide any right or rights of occupancy or use of the public or private property on which the activity or any part thereof will be located, or otherwise grant to the permittee any right or interest in or to the property, whether the property is owned or possessed by the State of Illinois or by any private or public party or parties.
- 3) This permit does not release the permittee from liability for damage to persons or property resulting from the work covered by this permit, and does not authorize any injury to private property or invasion of private rights.
- 4) This permit does not relieve the permittee of the responsibility to obtain other federal, state or local authorizations required for the construction of the permitted activity; and if the permittee is required by law to obtain approvals from any federal or other state agency to do the work, this permit is not effective until the federal and state approvals are obtained.
- 5) The permittee shall, at the permittee's own expense, remove all temporary piling, cofferdams, false work, and material incidental to the construction of the project. If the permittee fails to remove such structures or materials, the Department may have removal made at the expense of the permittee.
- 6) In public waters, if future need for public navigation or other public interest by the state or federal government necessitates changes in any part of the structure or structures, such changes shall be made by and at the expense of the permittee or the permittee's successors as required by the Department or other properly constituted agency, within sixty (60) days from receipt of written notice of the necessity from the Department or other agency, unless a longer period of time is specifically authorized.
- 7) The execution and details of the work authorized shall be subject to the review and approval of the Department. Department personnel shall have the right of access to accomplish this purpose.
- 8) Starting work on the activity authorized will be considered full acceptance by the permittee of the terms and conditions of the permit.
- 9) The Department in issuing this permit has relied upon the statements and representations made by the permittee; if any substantive statement or representation made by the permittee is found to be false, this permit will be revoked; and when revoked, all rights of the permittee under the permit are voided.
- 10) In public waters, the permittee and the permittee's successors shall make no claim whatsoever to any interest in any accretions caused by the activity.
- 11) In issuing this permit, the Department does not ensure the adequacy of the design or structural strength of the structure or improvement.
- 12) Noncompliance with the conditions of this permit will be considered grounds for revocation.
- 13) If the construction activity permitted is not completed on or before December 31, 2011, this permit shall cease and be null and void.



PERMIT NO. DS2008045
DATE: June 6, 2008

State of Illinois
Department of Natural Resources, Office of Water Resources

Permission is hereby granted to:

ILLINOIS DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS - DISTRICT 3
700 EAST NORRIS DRIVE
OTTAWA, ILLINOIS 61350

to construct a new bridge for Illinois Route 178 over the Illinois and Michigan Canal in the Southeast ¼ of Section 8, Township 33 North, Range 2 East of the 3rd Principal Meridian in LaSalle County,

in accordance with an application dated June 29, 2005 and submitted on April 14, 2008, and the plans and specifications entitled:

GENERAL PLAN
IL 178 RELOCATED OVER I & M CANAL, PUBLIC WATER
FAS 1279 SEC. 6R, STA. 179+33.66
LASALLE COUNTY, S.N. 050-0250

(Stamped APPROVED by IDOT on July 23, 2007 as a basis for preparation of detailed plans).

Examined and Recommended:

Handwritten signature of Michael L. Diedrichsen in black ink.

Michael L. Diedrichsen, Acting Manager
Downstate Regulatory Programs

Approval Recommended:

Handwritten signature of Gary R. Clark in black ink.

Gary R. Clark, Director
Office of Water Resources

Approved:

Handwritten signature of Sam Flood in black ink.

Sam Flood, Acting Director
Department of Natural Resources

This PERMIT is subject to the terms and special conditions contained herein.

**PERMIT NO. DS2008045
IDOT/DIST. 3
BRIDGE - IL ROUTE 178
OVER I & M CANAL**

PERMIT ACCEPTANCE

This Acceptance must be signed and returned to the address below to validate this permit. See Condition No. 8.

**ILLINOIS DEPARTMENT OF NATURAL RESOURCES
OFFICE OF WATER RESOURCES
One Natural Resources Way
Springfield, Illinois 62702-1271**

The undersigned permittee, personally, or if a corporation by its duly authorized officers, hereby accepts the permit bearing the above serial number subject to all conditions named therein, on this _____ day of _____, 20__.

By _____

By _____

If a corporation
affix seal here.