BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. of S. Abut	26950.74	-47.25	674.03	674.03
CL S. Abut	26952.04	-47.25	674.03	674.03
A	26962.04	-47.25	674.05	674.05
B	26972.04	-47.25	674.07	674.07
C	26982.04	-47.25	674.08	674.09
CL Pier 1	26993.75	-47.25	674.10	674.10
D	27003.75	-47.25	674.11	674.12
E	27013.75	-47.25	674.11	674.14
F	27023.75	-47.25	674.11	674.16
G	27033.75	-47.25	674.11	674.15
H	27043.75	-47.25	674.11	674.13
CL Pier 2	27058.25	-47.25	674.10	674.10
I	27068.25	-47.25	674.08	674.08
J	27078.25	-47.25	674.07	674.07
K	27088.25	-47.25	674.05	674.05
CL N. Abut.	27100.04	-47.25	674.02	674.02
Bk. of N. Abut.	27101.26	-47.25	674.02	674.02

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. of S. Abut	26951.63	-40.08	673.90	673.90
CL S. Abut	26952.94	-40.08	673.90	673.90
A	26962.94	-40.08	673.92	673.93
B	26972.94	-40.08	673.94	673.94
C	26982.94	-40.08	673.96	673.96
CL Pier 1	26994.64	-40.08	673.97	673.97
D	27004.64	-40.08	673.98	673.99
E	27014.64	-40.08	673.98	674.01
F	27024.64	-40.08	673.98	674.03
G	27034.64	-40.08	673.98	674.02
H	27044.64	-40.08	673.98	674.00
CL Pier 2	27059.14	-40.08	673.97	673.97
I	27069.14	-40.08	673.95	673.95
J	27079.14	-40.08	673.94	673.94
K	27089.14	-40.08	673.92	673.92
CL N. Abut.	27100.94	-40.08	673.89	673.89
Bk. of N. Abut.	27102.15	-40.08	673.89	673.89

TOP OF SLAB ELEVATIONS
STRUCTURE NO. 053-0186 (SB)

Coombe-Bloxdorf P.C.
-CIVIL ENGINEERS-
-STRUCTURAL ENGINEERS-
-LAND SURVEYORS-
Design Firm License No. 184-002703

PROJECT NO.	05004-10
SCALE	
DATE	8/10/10
DESIGN BY	GB/MCB
DRAWN BY	MML
CHECKED BY	MCB

SHEET NO. 8
42 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(53-1) HBR & HBR-1	LIVINGSTON	102	27
		CONTRACT NO. 66856		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

E-S

11-1-09

FILE NAME = ...\05304186_0187-66856-08-tog2-eb.dgn
PLOT SCALE = 0ULO25397 '2" / 1N.
USER NAME = CPC.