

HOT MIX ASPHALT SCHEDULE								
LOCATION	HMA SURF COURSE TON	HMA LEVEL BINDER MACHINE TON	HMA LEVEL BINDER HAND TON	HMA BINDER COURSE TON	HMA SHLDR 8" SQ YD	HMA SUR REM BUTT JT SO YD	BIT MAT (PR CT) GAL	AGG (PR CT) TON
STA. 160+10 TO STA. 160+70						173		
STA. 160+10 TO STA. 162+77	65						62	1.5
STA. 160+81 TO STA. 161+30		8	0.1				11	0.3
STA. 161+30 TO STA. 162+77			0.2	143			34	0.9
STA. 160+10 TO STA. 162+92					204			
STA. 159+89 TO STA. 162+92 LT					226			
STA. 164+29 TO STA. 165+50 RT	29						28	0.7
STA. 164+29 TO STA. 164+50			0.1	11			5	0.1
STA. 164+50 TO STA. 164+90		6	0.1				9	0.2
STA. 164+14 TO STA. 167+17					228			
STA. 164+14 TO STA. 166+13 LT					128			
STA. 164+90 TO STA. 165+50 RT						173		
TOTALS	94	14	0.5	154	786	346	149	3.7

GUARDRAIL SCHEDULE								
LOCATION	GUARDRAIL REMOVAL	SPBGR	TR BAR TRM T1 SPL TAN	TR BAR TRM T1 SPL FLAR	TR BAR TRM T6	GUARDRAIL MARK	TERM MARK DIR APPLIED	R&R RAIL ELEM EX GDRL
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	FOOT
STA. 162+10 TO STA. 163+28 LT	118							
STA. 161+24 TO STA. 161+74 LT				1			1	
STA. 161+74 TO STA. 162+49 LT		75				2		
STA. 162+49 TO STA. 162+92 LT					1		1	
STA. 162+09 TO STA. 163+10 RT	101							101
STA. 160+24 TO STA. 160+74 RT				1			1	
STA. 160+74 TO STA. 162+49 RT		175				4		
STA. 162+49 TO STA. 162+92 RT					1		1	
STA. 163+96 TO STA. 164+97 LT	101							101
STA. 164+14 TO STA. 164+57 LT					1		1	
STA. 164+57 TO STA. 166+32 LT		175				4		
STA. 166+32 TO STA. 166+82 LT				1			1	
STA. 163+95 TO STA. 164+97 RT	102							102
STA. 164+14 TO STA. 164+57 RT					1		1	
STA. 164+57 TO STA. 165+32 RT		75				2		
STA. 165+32 TO STA. 165+82 RT			1				1	
TOTALS	422	500	1	3	4	12	8	202

PAVEMENT MARKING					
LOCATION	PVMT MARK WHITE, 4"	PVMT MARK YELLOW, 6"	RAISED REF PVMT MARK REMOVAL	RAISED REFLECT PVMT MARK	PAVEMENT MARKING REMOVAL
	FOOT	FOOT	EACH	EACH	SQ FT
STA. 160+10 TO STA. 165+50 LT	540				180
STA. 160+10 TO STA. 165+50 RT	540				180
STA. 160+10 TO STA. 165+50		135	7	7	68
TOTALS	1080	135	7	7	428

EARTHWORK		
LOCATION	EARTH EXCAVATION	FURNISHED EXCAVATION
	CU YD	CU YD
STA. 160+10 TO STA. 163+07 LT	3	28
STA. 159+84 TO STA. 163+07 RT	4	25
STA. 163+99 TO STA. 167+17 RT	7	71
STA. 163+99 TO STA. 165+13 LT	5	22
TOTALS	19	146

SEEDING						
LOCATION	SEEDING CL 2	MULCH METHOD 2	EROSION CONTROL BLANKET SQ YD	NITRO FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND
STA. 160+10 TO STA. 163+07 LT	0.1	0.1	300	9	9	9
STA. 159+84 TO STA. 163+07 RT	0.1	0.1	100	11	11	11
STA. 163+99 TO STA. 167+24 LT	0.1	0.1	275	11	11	11
STA. 163+99 TO STA. 166+13 RT	0.1	0.1	200	9	9	9
TOTALS	0.4	0.4	875	40	40	40

TEMPORARY PAVEMENT MARKING				
LOCATION	TEMP PVMT MARK WHITE, 4"	TEMP PVMT MARK WHITE, 24"	SHORT TERM PVMT MARK	WORK ZONE PAVT MARK REMOVAL
	FOOT	FOOT	FOOT	SQ FT
STA. 159+82 RT		12		24
STA. 159+82 LT TO STA. 167+14 LT	732		73	244
STA. 159+82 RT TO STA. 165+27 RT	545		55	182
STA. 167+14 LT		12		24
STA. 160+12 LT TO STA. 165+45 LT	533		53	178
STA. 160+12 RT TO STA. 166+45 RT	633		63	211
TOTALS	2443	24	244	862

DRAINAGE SCHEDULE					
LOCATION	SHOULDER INLET	PIPE DRAINS CS 12	STEEL END SECT. 12"	THRUST BLOCKS	CONCRETE SHOULDER CURB
	EACH	FOOT	EACH	EACH	FOOT
STA. 164+34 15.0' LT	1				
STA. 164+34 15.0' LT TO STA. 164+34 28.0' LT		15			
STA. 164+34 28.0' LT			1	1	
STA. 164+29 16.0' LT TO STA. 164+39 16.0' LT					10
STA. 164+34 15.0' RT	1				
STA. 164+34 15.0' RT TO STA. 164+34 28.0' RT		15			
STA. 164+34 28.0' RT			1	1	
STA. 164+29 16.0' RT TO STA. 164+39 16.0' RT					10
TOTALS	2	30	2	2	20

STAGE CONSTRUCTION SCHEDULE				
LOCATION	TEMPORARY CONCRETE BARRIER FOOT	RELOCATE TEMP. CONC BARRIER FOOT	IMPACT ATTENUATORS EACH	RELOCATE IMPACT ATTENUATORS EACH
STA. 161+44 TO STA. 165+58	412.5		2	
STA. 161+68 TO STA. 165+43		375.0		2
TOTALS	412.5	375.0	2	2

TEMPORARY PAVEMENT SCHEDULE		
LOCATION	TEMPORARY PAVEMENT	TEMPORARY RAMP
	SY	SY
STA. 161+74 TO STA. 163+11 RT	91	8
STA. 163+95 TO STA. 165+19 RT	83	8
TOTAL	174	16

TEMPORARY EROSION CONTROL		
LOCATION	TEMP EROSION SEEDING	PERIM EROSION BARRIER
	POUND	FOOT
STA. 160+10 TO STA. 163+07 LT	9	297
STA. 159+84 TO STA. 163+07 RT	6	323
STA. 163+99 TO STA. 167+24 RT	9	325
STA. 163+99 TO STA. 166+13 LT	6	214
TOTALS	30	1159

FILE NAME = ... \D366861-SHT-Schedules.dgn	USER NAME = SAW	DESIGNED - RAC	REVISED -
		DRAWN - RAC	REVISED -
	PLOT SCALE = 1:800000 / IN.	CHECKED - DAZ	REVISED -
	PLOT DATE = 7/29/2012	DATE - 07/30/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



SCHEDULE OF QUANTITIES

F.A. RTE. 681	SECTION 118 BR	COUNTY IROQUOIS	TOTAL SHEETS 42	SHEET NO. 5
SHEET NO. 5 OF 42 SHEETS			STA. 159+89 TO STA. 167+17	
[ILLINOIS] FED. AID PROJECT				

CONTRACT NO. 66861