

## SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS ROUTE 331 ( CH 10 )  
 VERMILION COUNTY  
 SN 092-2039  
 Sta. 45+25.00 to Sta. 51+00.00  
 RURAL  
 80% FED  
 20% STATE  
 0011

CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30.0
20200100	EARTH EXCAVATION	CU YD	2275.0
20300100	CHANNEL EXCAVATION	CU YD	440.0
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,837.0
25000200	SEEDING, CLASS 2	ACRE	1.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	100.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	100.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	100.0
† 25000750	MOWING	ACRE	1.1
25100115	MULCH, METHOD 2	ACRE	2.2
25100630	EROSION CONTROL BLANKET	SQ YD	540.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	110.0
28000305	TEMPORARY DITCH CHECKS	FOOT	48.0
28000400	PERIMETER EROSION BARRIER	FOOT	865.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	245.0
28200200	FILTER FABRIC	SQ YD	365.0
28400100	GABIONS	CU YD	188.0
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	560.0
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	490.0
42001200	PAVEMENT FABRIC	SQ YD	490.0
42001300	PROTECTIVE COAT	SQ YD	490.0
44000100	PAVEMENT REMOVAL	SQ YD	190.0
Z0004552	APPROACH SLAB REMOVAL	SQ YD	200.0
44004000	PAVED DITCH REMOVAL	FOOT	110.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	50.0

† NON-PARTICIPATING 100% STATE

FILE NAME :	USER NAME : blackrt	DESIGNED - RTB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwwork\pwwork\blackrt\00128383\text		DRAWN - JRP	REVISED -			331	Z-BR	VERMILION	49	4	
		CHECKED -	REVISED -			CONTRACT NO. 70016					
		DATE - 06/2008	REVISED -			SHEET NO. OF SHEETS		ILLINOIS FED. AID PROJECT			