

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS ROUTE 331 (CH 10)
 VERMILION COUNTY
 SN 092-2039
 Sta. 45+25.00 to Sta. 51+00.00
 RURAL
 80% FED
 20% STATE
 CONSTRUCTION TYPE CODE: 0011

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50200100	STRUCTURE EXCAVATION	CU YD	50.0
50800105	REINFORCEMENT BARS	POUND	86,640.0
51500100	NAME PLATES	EACH	1.0
54003000	CONCRETE BOX CULVERTS	CU YD	322.9
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A , 6 FOOT POSTS	FOOT	437.5
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	100.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2.0
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2.0
63200310	GUARDRAIL REMOVAL	FOOT	600.0
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6.0
67100100	MOBILIZATION	L SUM	1.0
* 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20.0
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	1,575.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,575.0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4.0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1.0
XX006983	CLEARING	ACRE	0.1
Z0038700	PERMANENT BENCH MARKS	EACH	1.0
* SPECIALITY ITEMS			

FILE NAME :	USER NAME : black-t	DESIGNED - RTB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - JRP	REVISED -			331	Z-BR	VERMILION	49	5	
		CHECKED -	REVISED -			CONTRACT NO. 70016					
		DATE - 06/2008	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
PLOT SCALE = 4x2222 / IN.		PLOT DATE = 8/18/2012		SHEET NO. OF SHEETS							