

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N & TS-1	McLean	497	269
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 70514

SCHEDULE OF QUANTITIES LIGHTING ITEMS

CODE NO.	ITEM	UNIT	TOTAL QTY	VETERANS PKWY & MORRIS AVE	VETERANS PKWY & GREENWOOD AVE	MORRIS AVE & SIX POINTS RD
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	1	1	1
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, CONTROL 400 WATT	EACH	10	4	3	3
	CONDUIT PUSHED, 75MM DIA., PVC SCHEDULE 80	METER	345	140	80	125
M8170040	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE), 1/C NO. 6	METER	990	360	290	340
M8170030	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE), 1/C NO. 8	METER	495	180	145	170
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	93	25	57	11
MX810070	CONDUIT IN TRENCH, 75MM DIA., PVC, SCHEDULE 80	METER	93	25	57	11
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 60 AMP	EACH	3	1	1	1
X8410105	TEMPORARY LIGHTING SYSTEM	EACH	2	1	0	1
XX002059	REMOVAL OF EXISTING LIGHTING UNIT - COMPLETE	EACH	6	2	0	4

\$FILE\$
10/14/2010 \$TIME\$


▲ REVISED SHEET 10/25/10 TS-20

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: NONE
DATE: MARCH, 2009

DRAWN BY: RV
DESIGNED BY: AS/SM
CHECKED BY: MSA


AMES Engineering, Inc.
 Consulting Engineers
 1341 Warren Avenue
 Downers Grove, IL 60515